

# Property Evaluation Report

## MODULAR BUILDING ASSESSMENT

### & CRITICAL REPAIRS

Project Number 2016-286

Tumwater, Washington



Washington State Department of Enterprise Services

by

The logo for EHM Architecture Inc. consists of a solid red square with the letters "EHM" in white, bold, sans-serif font centered within it.

Ehm Architecture Inc.  
1200 Fifth Avenue, Suite 1208  
Seattle, WA 98101

July 5, 2016

# **MODULAR BUILDING ASSESSMENT AND CRITICAL REPAIRS**

**Project Number 2016-286  
Tumwater, Washington**

## **Table of Contents**

<b>TAB</b>	<b>ITEM</b>	<b>Page</b>
1	Executive Summary	3
2	Architectural	6
3	Mechanical	26
4	Structural	44
5	Electrical	60
6	Cost Estimate	68
7	Appendix	70
	Appendix 7A – Roof Inspection Report	71
	Appendix 7B – Dock Leveler Report	84
	Appendix 7C – Cooling Tower Calculations	87
	Appendix 7D – Mezzanine Storage Capacity Calculations	96
	Appendix 7F – Modular Building Racks Memorandum	114
	Appendix 7G – Investment Grade Energy Audit	116
	Appendix 7H – Sewer Piping Maps	169
	Appendix 7I – 1999 Isabella Bush Soils Report	176
	Appendix 7J – Tier 1 Seismic Study Checklist	180
	Appendix 7K – Tier 2 Seismic Study Structural Calculations	184



## EXECUTIVE SUMMARY

**Introduction:** Ehm Architecture was engaged by DES in March 2016 to perform a Building Assessment, to report on our findings and to make recommendations for emergency repairs. This assessment covers Architectural, Mechanical, Structural and Electrical Systems. Each recommended repair is listed as a separate line item, which includes estimated cost of repairs and priority level. The priority levels are offered for the benefit of DES, to assist with determination of which items will be included in its legislative funding request for its 10-year capitol plan.

**Architectural:** The original roof system was installed as part of the original building construction in 1980, was repaired in 1992 and was replaced in 2000. The roof repair has outlived its useful service life, and is recommended for full replacement. The exterior finish of the building has deteriorated over time, with minor damage to exterior insulating panels and failure of thermal and weatherproofing seals between panels. We recommend repair of damaged panels, replacement of panel seals and painting of the building exterior. Dock levelers have either outlived their useful service life, or require preventative maintenance and repair. Overhead rolling door assemblies have outlived their useful service life and need to be replaced.

Ship's ladders do not meet current building codes, and constitute a potential hazard to facility employees. They are therefore recommended for replacement. Concrete ramps, guardrails and Accessible Path of Travel at the building entry do not comply with ADA Accessibility and Building Code Regulations. They are recommended for replacement or reconstruction to achieve full compliance. Current site drainage and lack of storm drains in the parking lots result in ponding of water adjacent to the building and in the easterly parking lot. These conditions have significant potential to undermine the building foundation, and have accelerated degradation of the asphaltic parking lot. We recommend remedial grading with new paving at these areas.

**Mechanical –** Outside air is insufficient to control indoor fumes and odors from printing processes. Intake air volumes are recommended to be adjusted accordingly. Air handling units violate current State Energy Code, and are to be replaced. This replacement will require air terminal units and ductwork to be replaced as well. The cooling tower and hydronic system has outlived their useful service life, and should be replaced. Various components of the HVAC system are either in disrepair or are inadequate for their intended purpose. These items should be replaced. There are insufficient cleanouts for the main sewer line at the south side of the building and the four sewer laterals entering the building from the east, making inspection and maintenance difficult. We recommend installation of new cleanouts on the main sewer lines and laterals. Sanitary sewer main and lateral piping exhibit evidence of moisture and sedimentary intrusion at the joints. We recommend relining larger pipes and replacing smaller pipes. Some roof drain assemblies and rainwater leaders in the Low Bay area are not properly insulated, allowing heat loss through the piping. We recommend insulating those elements to improve overall energy efficiency.

**Structural –** The existing parapet is not adequate for fall protection and does not meet current building code for life safety. We recommend vertical extension of the parapet. Cooling tower fall restraint is inadequate, but this condition will be rectified through the planned replacement of the cooling tower with low-rise, roof-mounted cooling equipment. The mezzanine structural system is inadequate for posted loading capacity, so we recommend that the posted capacity be lowered to reflect the design capacity. Storage racks appear to be overloaded beyond their design capacities. We recommend limiting rack loading to maximum design capacity. The building's structural system is inadequate to resist code-prescribed lateral loading in a seismic event. Given the building use's importance in a significant, regional earthquake event and the State's need to keep it operational, we recommend structural retrofits to strengthen the building to code-prescribed levels.



**Electrical** – We recommend preventive maintenance of electrical equipment, to extend its useful service life and to prevent hot spots and overloads. Replacement of the power distribution system is not warranted at this time, and will continue to function with the system maintenance recommended. From among our recommended options to maintain, upgrade or replace the existing lighting system, DES has opted to maintain the existing lighting system.



## 2. ARCHITECTURAL

### I. INTRODUCTION

**A.** Ehm Architecture inspected architectural components of the Modular Building on April 26, 2016. The Scope of Work included assessment of building envelope (roof system, exterior finish and panel seals), overhead rolling doors, loading dock levelers, building code life safety issues, ADA compliance and deferred maintenance.

### **B. GENERAL DESCRIPTION OF THE EXISTING STRUCTURE**

The Modular Building consists of a low-bay element to the north (photograph 1/AA-1), and a high-bay element to the south (photograph 2/AA-1). The high-bay Isabella Bush Records Center exists south of the Modular Building, and was excluded from this assessment at the direction of Department of Enterprise Services (DES) project management staff.

**AGE:** Built in 1980, the modular structure is approximately thirty-six years old.

**CONDITION:** The building is in good condition, with the exception of several items as further outlined herein.

**ADEQUACY OF COMPONENTS:** Adequacy of components varies according to individual components and their relationship to the assemblage as a whole. Individual building components are addressed in detail in the descriptions that follow this section.

**REMAINING SERVICE LIFE:** Through a program of preventive maintenance, and through critical repair and upgrade of building components and systems as outlined herein, this building should have a remaining service life of approximately fifty years. The remaining service lives of individual building components are listed in the corresponding sections of this report.

### **BUILDING ENVELOPE**

#### **Roof System**

The original built-up roofing system, installed in 1980, was repaired in 1992. The building was completely re-roofed with the existing PVC membrane system in summer of 2000 (photographs 3/AA-2 and 4/AA-2). While no warranty information was obtained during our initial archives search, we are aware that a common warranty period for PVC membrane roofing systems typically ranges from 15 to 20 years. In that respect, it is reasonable to assume that the existing membrane roofing system has reached or is nearing the end of its useful and/or warranted service life.

Our inspection of the roof system yielded issues and raised concerns which are consistent with those identified and quantified in the Inspection Report by Wayne's Roofing Inc. of October 2015 (Appendix A). It is not known to Ehm Architecture to what extent their recommended temporary repairs may have been made, but anything other than a warranted application should be considered as strictly temporary.

The low bay roof supports two large air handlers (photograph 5/AA-3) and a cooling tower (photograph 6/AA-3). The high bay roof supports two large air handlers (photograph 7/AA-4), a roof hatch (photograph 8/AA-4), smoke ventilators (photograph 9/AA-5) and exhaust fans (photograph 10/AA-5). Both roof areas are bounded by parapets, which while ranging in height are inadequate to provide fall protection as required by code (photographs 11/AA-6 and 12/AA-6). The adjacent Isabella Bush Building, which is not within the scope of this assessment, features a guardrail which is code-compliant and which represents a good example of a potential design solution to the inadequate parapet height on the Modular Building roof (photograph 13/AA-7).

#### **Exterior Finish**

Typical exterior walls are finished with insulated metal panels (photograph 14/AA-7). Numerous areas of mold growth and discoloration are evident around the building (photograph 15/AA-8). Two areas of damage to insulated panels were noted, one on the east side of the building adjacent to the loading docks (photograph 16/AA-8).

### **Panel Seals**

Panel seals were reported by facility maintenance staff to be largely in disrepair and/or failing. This issue is consistent with the age of the building and normal degradation of the building materials used to achieve panel seals when built.

### **Dock Levelers**

Dock levelers were reported by Facilities Maintenance staff to be in various degrees of functionality and disrepair. Our inspection included an onsite evaluation by Industrial Hydraulics (IH) of Tumwater. Their report is included herein as Appendix B.

In summary, Leveler #1 was inoperable, so could not be evaluated. IH noted that the leveler appears to be original equipment, and not a replacement model as are some others. Leveler #2 (photograph 17/AA-9), which also appears to be original, is operational but in need of repair. Leveler #3 (photograph 18/AA-9) is newer in appearance and of a different configuration than Levelers # 1 and 2. In that sense, it appears to be a replacement model. It is in good working order. The appearance and configuration of Leveler #4 (photograph 19/AA-10) is similar to that of Leveler #3, suggesting that this may also be a replacement model. IH noted that the small cylinder which would operate the lip extender is not operational.

### **Overhead Rolling Doors**

Overhead rolling doors (photograph 20/AA-10) have outlived their useful service life. Facility maintenance staff reports that broken springs and failing motors are a common occurrence.

### **Building Code Life Safety Issues**

Ship's ladders to the Mezzanine (photograph 21/AA-11) have a riser height of 12 inches (photograph 22/AA-11), which significantly exceeds the current code maximum height of 9-1/2 inches. Further, current code only allows for ship's ladders to be used at areas not exceeding 250 square feet. The existing mezzanine areas far exceed 250 square feet.

## **SITE**

### **Concrete Ramps at Entry**

Disabled-access ramps adjacent to the westerly building entries (photograph 23/AA-12) are non-compliant with current ADA guidelines, which constitute a potential liability to the State of Washington. In particular, visual detection devices adjacent to the ramps and adjacent to parking areas are inadequate to inform vision-disabled individuals of existing hazards.

### **Guardrails at Entry**

Under current code, guardrails for landings above 30 inches in height may have a maximum sphere spacing of 4 inches to prevent small children from slipping through or getting their heads stuck in vertical or horizontal members of guardrails. The existing guardrails (photograph 24/AA-12) have vertical members approximately 12 inches apart, which – although it may be unlikely for small children to access the entry areas – constitutes a hazard to such individuals, which could potentially expose the State to liability. The stair guardrails do not meet the handgrip requirement of a stair handrail, and the horizontal return at the bottom stair tread does not meet current code.

### **Path of Travel at Parking Lot**

Visual detection devices are required under current code, at walking surfaces which are directly adjacent to parking areas. A ramp from the entry stair toe to the parking area is unprotected (photograph 25/AA-13), with no warnings to the visually-impaired that they are about to enter a vehicular way.

### **Site Drainage**

Visual observation of the parking area east of the building revealed that the site does not have adequate stormwater drainage. Where one would normally expect to find catch basins (at the low point of paving slopes), none exist. The existing asphalt paving shows evidence of ponding, which was confirmed by facility maintenance staff. An aerial image from Google Earth also serves as evidence

in this regard. Such ponding accelerates deterioration of asphalt and potentially undermines it. It also renders parking spaces either unusable, and creates a potential nuisance by causing staff or visitors to unwittingly step into standing water during and after rain events. Such a nuisance could result in lost time for workers, as they would have to dry their shoes, socks and feet to safely and comfortably perform their duties. Water ponds at the west side of the building (photograph 26/AA-13), directly adjacent to the building foundation, which creates potential for settlement and/or undermining of building foundations.

## C. CONSTRUCTION

### • BUILDING CODE

The building was built under the 1979 Edition of the Uniform Building Code by the International Conference of Building Officials, and the 1976 Uniform Fire Code.

**Occupancy Type:** B-2

**Construction Type:** V-N (NOTE: A fire alarm system was added in 2005).

### • EXISTING DRAWINGS

Record drawings were obtained from DES archives.

### • ORIGINAL PROJECT TEAM - 1979

Original Owner: Department of General Administration  
Division of Engineering & Architecture

Original Consulting Engineer/Planner: Victor O. Gray & Company

Original Interior Space Planner: Marvin Stein & Associates

Original Mechanical / Electrical Engineer: Valentine, Fisher & Tomlinson

Original Soils Engineer: Neil H. Twelker & Associates

Original Landscape Architect: Richard Haag & Associates

Original Contractor: Unknown

### • ROOF REPAIR PROJECT TEAM - 1992

Architect: The BJSS Group

### • ROOF REPLACEMENT PROJECT TEAM - 2000

Architect: Masini Sanford Gabrielse & Schoenfeldt

Contractor: Roof Toppers

## II. PROBLEMS TO BE CORRECTED AT THIS TIME

**NOTE: See end of this section for listing and description of Priority Levels which are indicated below.**

### 1. PUBLIC HAZARD

**PROBLEM: Ramps at Entry**

Visual detection devices are non-existent at the top of the main entrance ramps. While current code would only require ADA compliance if the building is modified, the lack of warning devices constitutes a hazard to the public – and a potential liability to the State - and should be corrected.

**SOLUTION:** Grind warning grooves into the concrete slab at the top of both ramps, or sawcut and replace slab as required to provide grooves.

**QUANTITY:** 8 linear feet x 12" wide

**COST:** \$ 2,518

**PRIORITY LEVEL:** 1

**PROBLEM: Guardrails at Entry**

Under current code, guardrails for landings above 30 inches in height may have a maximum sphere spacing of 4 inches, to prevent small children from slipping through or getting their heads stuck in vertical or horizontal members of guardrails. This constitutes a hazard to the public – and a potential liability to the State - and should be corrected.

**SOLUTION:** Remove existing guardrails and install compliant guardrails

**QUANTITY:** 60 linear feet x 42" high

**COST:** \$ 11,897

**PRIORITY LEVEL:** 1

**PROBLEM: Path of Travel at Entry**

Lack of visual warning devices at the entrance walkway leading to the parking lot constitutes a hazard to the public – and a potential liability to the State - and should therefore be corrected.

**SOLUTION:** Grind warning grooves into the concrete slab at the top of the ramp leading to the vehicular way, or sawcut and replace slab as required to provide grooves.

**QUANTITY:** 12 linear feet x 12" wide

**COST:** \$ 793

**PRIORITY LEVEL:** 1

### 2. BUILDING REPAIR AND MAINTENANCE

**PROBLEM: Damaged Insulated Panels**

Two Insulated panels are damaged, allowing moisture intrusion and thereby compromising the integrity of the panels.

**SOLUTION:** Remove and replace damaged panels.

**QUANTITY:** 2 panels @ 30" wide x 17'-4" high

**COST:** \$ 8,290

**PRIORITY LEVEL:** 2

**PROBLEM: Insulated Panel Finish**

Panels exhibit mold growth and discoloration. DES staff has requested inclusion of exterior painting in the critical repair scope of work.

**SOLUTION:** Clean, prime and paint existing insulated panels with elastomeric paint.

**QUANTITY:** x square feet

**COST:** \$ 150,647

**PRIORITY LEVEL:** 3

**PROBLEM: Failing Panel Seals**

Panel seals are in disrepair and/or failing.

**SOLUTION:** Remove, clean adjacent surfaces and install new panel seals.

**QUANTITY:** 10,086 linear feet

**COST:** \$ 46,665

**PRIORITY LEVEL:** 2

**PROBLEM: Dock Levelers**

Levelers #2, 3 and 4 require maintenance and/or repair, per the Inspection Report by Industrial Hydraulics (Appendix B).

**SOLUTION:** Perform maintenance and repair of dock levelers as recommended,

**QUANTITY:** Per Appendix B.

**COST:** \$ 6,760

**PRIORITY LEVEL:** 1

**PROBLEM: Overhead Rolling Door Failure**

Overhead rolling doors have outlived their useful service life. Facility maintenance staff reports that broken springs and failing motors are a common occurrence.

**SOLUTION:** Remove and replace overhead rolling doors.

**QUANTITY:** (6) 11' wide x 12' high overhead coiling rolling doors complete with motors, hardware and operating devices.

**COST:** \$ 65,435

**PRIORITY LEVEL:** 2

**3. CONSULTANT RECOMMENDATIONS****PROBLEM: Aging Roof System**

The 2000 reroofing system has outlived its useful service life, and should be replaced with a new PVC roofing system with 20-year warranty.

**SOLUTION:** Demo and replace existing roofing system. Repair damage to insulation and /or structural members below as necessary.

**QUANTITY:** 105,600 square feet

**COST:** \$ 1,961,441

**PRIORITY LEVEL:** 3

**PROBLEM: Inoperable Dock Levelers**

Leveler #1 is inoperable, due to an electrical problem. The leveler appears to be original construction. As two other original docks have been previously replaced, Ehm Architecture recommends replacing Leveler #1.

**SOLUTION:** Remove and replace existing dock leveler.

**QUANTITY:** 1 leveler complete with hydraulics and electric motor.

**COST:** \$ 11,194

**PRIORITY LEVEL:** 2

**PROBLEM: Noncompliant Ship's Ladders**

Ship's ladders are 33% steeper than required by current code, and service mezzanine areas which far exceed the current area allowed to be served by ship's ladders. For practicality and for the safety of facility staff, we recommend the replacement of two ship's ladders with compliant stairs.

**SOLUTION:** Remove and replace two ship's ladders with 42" wide code-compliant steel stairs with handrails and guardrails, one at each mezzanine.

**QUANTITY:** 2

**COST:** \$ 18,507

**PRIORITY LEVEL:** 1

**PROBLEM: Lack of Parking Lot Drainage**

Lack of storm drainage facilities at the east and west parking lots creates ponding water. Water ponds at the west side of the building, directly adjacent to the building foundation.

**SOLUTION:** Remove asphalt, perform remedial grading to facilitate sheet drainage to adjacent retention ponds, repave and restripe parking lot.

**QUANTITY:** 82,200 square feet

**COST:** \$ 580,849

**PRIORITY LEVEL:** 5

## PRIORITY LEVEL DESCRIPTIONS

**Level 1:** Critical life safety and hazardous issues which should be addressed immediately, as emergency repairs.


**Level 2:** Critical issues which, if not immediately repaired or replaced *would* continue to cause deterioration of or damage to the existing structure or building materials.

**Level 3:** Significant issues which, if not soon repaired or replaced (within one to two years) *may* continue to cause deterioration of or damage to the existing structure or building materials.

**Level 4:** Moderate issues which, if not soon repaired or replaced *may* continue to cause deterioration of or damage to the existing structure or building materials, but which could serve their intended purpose for a limited time (one to two years).

**Level 5:** Minor maintenance issues requiring preventative maintenance, cleaning and/or monitoring, or items which could be deferred beyond two years and/or as funding allows.

I HEREBY CERTIFY THAT THIS DOCUMENT WAS PREPARED BY ME PERSONALLY, AND THAT I AM A DULY REGISTERED ARCHITECT IN THE STATE OF WASHINGTON.







Low Bay Section of Modular Building  
PHOTOGRAPH 1



High Bay Section of Modular Building (Isabella Bush Building at right)  
PHOTOGRAPH 2

## MODULAR BUILDING ASSESSMENT

Architectural AA-01



Low Bay Roof  
PHOTOGRAPH 3



High Bay Roof  
PHOTOGRAPH 4

MODULAR BUILDING ASSESSMENT

Architectural AA-2





Low Bay HVAC Equipment  
PHOTOGRAPH 5




Low Bay Cooling Tower  
PHOTOGRAPH 6

MODULAR BUILDING ASSESSMENT



High Bay HVAC Equipment  
PHOTOGRAPH 7



High Bay Roof Hatch  
PHOTOGRAPH 8

MODULAR BUILDING ASSESSMENT






High Bay Ventilator  
PHOTOGRAPH 9



High Bay Exhaust Fan  
PHOTOGRAPH 10



Unsafe Parapet Height  
PHOTOGRAPH 11



Unsafe Parapet Height  
PHOTOGRAPH 12

MODULAR BUILDING ASSESSMENT



Fall-Protection Guardrail at Adjacent Isabella Bush Building  
PHOTOGRAPH 13



Insulated Panels at High Bay  
PHOTOGRAPH 14

## MODULAR BUILDING ASSESSMENT

Architectural AA-7





Insulated Panel Mold Growth and Discoloration  
PHOTOGRAPH 15



Damaged Panel at Loading Dock  
PHOTOGRAPH 16

MODULAR BUILDING ASSESSMENT





Dock Leveler #2  
PHOTOGRAPH 17



Dock Leveler #3  
PHOTOGRAPH 18

## MODULAR BUILDING ASSESSMENT

Architectural AA-9



Dock Leveler #4  
PHOTOGRAPH 19



Overhead Rolling Door  
PHOTOGRAPH 20

## MODULAR BUILDING ASSESSMENT

Architectural AA-10





Ship's Ladder to Mezzanine  
PHOTOGRAPH 21



Riser Dimension at Ship's Ladder  
PHOTOGRAPH 22

## MODULAR BUILDING ASSESSMENT

Architectural AA-11



Ramp at Entry  
PHOTOGRAPH 23



Guardrail at Entry  
PHOTOGRAPH 24

## MODULAR BUILDING ASSESSMENT

Architectural AA-12





Path of Travel at Vehicular Way  
PHOTOGRAPH 25



Ponding at Building Wall  
PHOTOGRAPH 26

MODULAR BUILDING ASSESSMENT

Architectural AA-13



### 3. MECHANICAL

#### I. INTRODUCTION

A. The Greenbusch Group performed an inspection of the Modular Building mechanical systems on 4/26/16. On 5/4/16 and 6/1/16, Flohawks Plumbing and Septic conducted video inspections of the sanitary waste pipes for the building. The results of these inspections are included below.

#### B. GENERAL DESCRIPTION OF THE EXISTING FACILITY

**AGE:** Approximately 37 years

**CONDITION:** Several of the building's mechanical systems are deteriorating due to age, as detailed below.

**ADEQUACY OF COMPONENTS:** Adequacy of components varies according to individual components and their relationship to the assemblage as a whole. Individual mechanical components are addressed in detail in the descriptions that follow this section.

**REMAINING SERVICE LIFE:** A number of the building's mechanical systems have been partially or completely replaced at various stages in the history of the building. As a result, there is significant variability in the condition and life expectancy of the building's various pieces of mechanical equipment. The remaining service lives of individual mechanical components are listed in the corresponding sections of this report.

Specific problems, along with proposed solutions, approximate costs for addressing the issues, and the priority level of each item, are presented in the subsequent section, "Problems to be Corrected at This Time".

#### MECHANICAL SYSTEMS

##### Air Handlers

The facility is served by four rooftop air handling units (AHU's)—two for the High Bay and two for the Low Bay (photograph 01/MM-1). The air handlers are original to the building and employ dual-deck hydronic heating and cooling. This type of conditioning is not permitted under current energy code. The insulation and interior of the AHU's are deteriorating due to water infiltration. All of the AHU's are past their useful service lives at this point. However, all four air handlers have had their fan motors and variable frequency drives (VFD's) replaced recently (within the last one to two years) and, if salvaged, these components may have up to 20 years of service life remaining. However, the motors and VFD's may suffer shortened lifespans due to the noted water infiltration.

The low bay roof also houses two smaller air handling units (photograph 02/MM-1), which are dedicated to a secure section of the building. These units are relatively new and associated with a portion of the structure that is outside of the scope of this assessment.

##### Chiller and Cooling Tower

A centrifugal chiller (photograph 03/MM-2) and a cooling tower (photograph 04/MM-3) provide cold water to the cooling coils of the air handling units. The cooling tower has a chemical treatment system in place (photograph 05/MM-4). The existing chiller and cooling tower and their associated pumps were installed in 2001. The chiller has up to approximately 10 years of service life remaining, with proper maintenance. The cooling tower is having corrosion and leakage issues and is likely within its last five years of useful service.

##### Boilers and Circulation Pumps

Two hot water boilers (photograph 06/MM-5) are currently in place, providing heating water both to the unit heaters in the building and the AHU's on the roof. At the time of the inspection, one of the boilers was out of service for repairs. Both boilers date to the early 1990's but have newer model Honeywell controllers. The boilers are currently past their useful service life. The hot water circulation pumps (photograph 07/MM-5) associated with each boiler have motors that were replaced within approximately the last two years and should have another 15 years of life remaining.

## **Pipes and Distribution**

A hydronic piping system (photograph 08/MM-6) distributes hot water from the boilers to the AHU's and unit heaters, and cold water from the chiller to the cooling tower and the AHU's. The hydronic piping suffers from poor sealing throughout the building and reportedly leaks in multiple locations if the water temperature is permitted to drop below 90 degrees Fahrenheit. Based on scaling and rust that is visible at fittings where leaks previously occurred, the interior condition of the piping is likely very corroded and deteriorated. The heating water piping is well past its useful service life and should be replaced.

As noted above, Flohawks Plumbing and Septic conducted video inspections of the sanitary waste pipes for the building. Appendix 7H includes record drawings of the exterior and interior below-grade waste pipes. The pipes that were inspected by video camera are indicated in red. Those not marked with red were either inaccessible for scoping or were found to be non-existent or decommissioned. Scoping of the sanitary waste piping shows that the main lines are a combination of cement pipes and PVC pipes, and the laterals are PVC pipe with glued joints. There are some signs of groundwater infiltration at the joints, as indicated by the volume of water that is in the pipes even when no fixtures are in use (photograph 09/MM-6, and photographs 10 and 11/MM-7). In addition, the inspection revealed that, over a 20 foot section of one of the lateral waste lines, the pipe slopes backward (into the building) at a grade of about .45 inches per foot (see Sanitary Waste Piping Map, Low Bay, Appendix-7H-2). This condition can hamper flow and contribute to blockages, creating a maintenance issue. However, barring any significant change in use for the building, The PVC waste piping is still expected to have a remaining useful service life of 20 years or more.

The local waste piping that connects the restroom fixtures to the lateral lines is composed of cast iron. These pipes show an expected amount of pitting and oxidation for their age, and some accumulation of refuse locations (photographs 12 and 13/MM-8). However, the inspection did not indicate the presence of immediate issues such as blistering, cracking, or significant buildup of rust. The cast iron piping should continue to serve for up to approximately 10 more years. It is recommended that the waste system be hydro-jetted approximately every two years to clear any accumulation and prevent blockages.

There is also a now-abandoned network of steam piping (photographs 14/MM-9 and 15/MM-10) throughout the facility. This piping is no longer in use but appears to be entirely iron, which has made its removal a difficult proposition.

## **Terminal Units and Ductwork**

The facility contains a total of approximately 78 dual-deck air terminal units (photograph 16/MM-11) which are original to the building. These units have newer electronic controls and actuators. These units are not fan-powered; they modulate the hot and cold air volumes via motor-actuated dampers. The majority of the ductwork is original to the building and therefore somewhat leaky. Most of it is insulated sheet metal or flex duct, however many of the sections of rectangular duct that connect with the terminal units in the Low Bay area are reportedly constructed entirely of duct board, which makes them fragile. Left undisturbed, the terminal units and their associated ductwork could continue to serve for up to another 10 years. However, if the AHU's are upgraded, it will be necessary to replace the terminal units and ductwork as well, because their design capacity and layout are specific to the existing dual-deck HVAC system.

## **Unit Heaters and Pneumatic Valves**

The facility contains seven horizontal unit heaters (photograph 17/MM-11) and seven vertically-discharging "heat curtain" style heaters (photograph 18/MM-12), all of which employ hot water heating coils and electric fans. The heaters should be capable of serving for another five years. However, the hot water valves for all of these units are controlled by pneumatic valve actuators supplied by a dedicated air compressor. The only other known pneumatic actuators in the facility are two valve actuators that are on hot water pipes in the boiler room. All of these pneumatic valves are past their useful service lives.



### **Humidification**

There are seven Nortec Airfog humidification units installed in the High Bay area (photograph 19/MM-12). The units were installed in 2001 and have proven prone to leaking and breaking down. It is unlikely that their existing configuration is adequate to prevent microbial growth and their lack of dependability means the humidity level in the print shop is likely sporadic. These units are reportedly the property of the Print Shop and their replacement is therefore outside of the scope of this project. However, they are supplied with water by the domestic plumbing system and it is unknown if they currently have adequate backflow prevention in place.

As noted above, there is also a decommissioned steam system still in place which appears to have been formerly used for humidification. This includes a steam boiler, condensate trap, condensate pump, filtration system, and steam piping throughout the facility, all of which is currently unused. This system was most likely decommissioned in 2001 when the Nortec humidification units were installed.

### **Controls**

The HVAC systems, with the exception of the unit heaters and humidifiers, are controlled by a Metasys Building Automation System (BAS), by Johnson Controls.

## **C. CONSTRUCTION**

- **MECHANICAL CODE**

The building was built under the 1979 Edition of the Uniform Mechanical Code.

- **EXISTING DRAWINGS**

Record drawings from the original 1979 construction were obtained from the Owner, as well as control drawings from the boiler replacement.

## II. PROBLEMS TO BE CORRECTED AT THIS TIME

### 1. CODE ISSUES

**PROBLEM:** The current volume of outside air being supplied to the High Bay area is not sufficient to control fumes and odors.

**SOLUTION:** Increase the minimum outside air settings for the Print Shop and confirm that the volume of exhaust air is sufficient for this facility.

**COST:** \$6,750

**PRIORITY LEVEL:** 1

**PROBLEM:** The current air handling units are dual-deck systems which provide both hot and cold air, which is then mixed at the zone level to produce the desired supply air temperature. This system violates current Washington State Energy Code section C403.4.4 which restricts the heating of previously cooled air and/or the cooling of previously heated air.

**SOLUTION:** When the AHU's are replaced, a code-compliant single-duct system will need to be installed. This will also require replacement of all of the existing dual-deck air terminal units and associated ductwork throughout the facility.

**COST:** \$1,000,927

**PRIORITY LEVEL:** 3

**PROBLEM:** The High Bay humidifiers are connected to the domestic water system and it is unknown if code compliant backflow prevention has been installed.

**SOLUTION:** Install backflow prevention in the humidification system per plumbing code, if it does not exist.

**COST:** \$4,500

**PRIORITY LEVEL:** 2

### 2. PUBLIC HAZARD

**PROBLEM:** As noted under Code Issues, the current volume of outside air being supplied to the High Bay area is not sufficient to control fumes and odors.

**SOLUTION:** See Code Issue, item #1, above.

**COST:** See Code Issue, item #1, above.

**PRIORITY LEVEL:** 1

**PROBLEM:** All of the original AHU's have outside air louvers that are not wind-driven rain resistant and, as a result, rainwater is infiltrating the units and leaving standing water inside the AHU. This condition is causing corrosion and deterioration of the insulation and filters, as well as presenting an electrical hazard and the potential for indoor air quality issues such as mold (photograph 20/MM-13).

**SOLUTION:** Provide wind-driven rain protection until the air handlers are replaced with new units.

**COST:** \$11,250

**PRIORITY LEVEL:** 1

### 3. BUILDING MAINTENANCE

**PROBLEM:** Hot water boiler H-2 is prone to false alarms in the controls system and randomly tripping faults which do not appear related.

**SOLUTION:** Check controls programming, wiring, and sensors for source of recurring issues.

**COST:** \$7,500

**PRIORITY LEVEL:** 2

**PROBLEM:** The chiller capacitors are reportedly failing, though no specific issues were noted at the time of the inspection.

**SOLUTION:** Assess chiller capacitors with manufacturer's local representative and replace if needed.

**COST:** \$7,500

**PRIORITY LEVEL:** 3

**PROBLEM:** AHU supply fans typically ramp up to a static pressure of 3" WC in response to a single call for cooling, regardless of other calls in the system.

**SOLUTION:** Adjust controls programming so that fans provide a more measured response to cooling calls.

**COST:** \$30,000

**PRIORITY LEVEL:** 3

**PROBLEM:** There is some accumulation of effluent and silt in the waste pipes which can inhibit flow and eventually develop into blockages.

**SOLUTION:** Have the waste piping hydro-jetted to clear it of buildup.

**COST:** \$69,300

**PRIORITY LEVEL:** 4

**PROBLEM:** Sanitary sewer piping main lines and laterals show some signs of groundwater and silt infiltration at the joints.

**SOLUTION:** Re-line the waste piping to eliminate infiltration.

**COST:** \$33,750

**PRIORITY LEVEL:** 4

#### 4. CONSULTANT RECOMMENDATIONS

**PROBLEM:** Heating water boilers H-1 and H-2 are past their useful service lives and prone to leaks.

**SOLUTION:** Replace boilers.

**COST:** \$212,626

**PRIORITY LEVEL:** 2

**PROBLEM:** Hydronic system pipes and fittings show signs of rust, corrosion, and leakage. (photograph 21/MM-14) The boiler system has to be run at all times at a minimum of 90 degrees Fahrenheit in order to cause enough thermal expansion in the pipes and fittings to prevent leaks. The cooling tower is showing corrosion and has been repaired repeatedly due to leaks (photograph 22/MM-14).

**SOLUTION:** Replace the cooling tower, as well as hydronic piping, fittings, and seals throughout the facility.

**COST:** \$841,896

**PRIORITY LEVEL:** 1

**PROBLEM:** Pneumatic valve actuators are still in use on unit heaters and two hot water pipes. Actuator components are becoming corroded (photograph 23/MM-15).

**SOLUTION:** Replace pneumatic actuators with electric motorized actuators, which will eliminate the need to keep and maintain the pneumatic system, as well as allowing the actuators to be monitored and controlled remotely via the building automation system, if desired.

**COST:** \$27,000

**PRIORITY LEVEL:** 2

**PROBLEM:** Low Bay ductwork is prone to leakage and appears to have some portions that are constructed of duct board rather than sheet metal.

**SOLUTION:** Replace ductwork and fittings throughout the Low Bay.

**COST:** \$411,262

**PRIORITY LEVEL:** 3

**PROBLEM:** There are not currently cleanouts on the sewer main at the south side of the building or the four lateral lines that enter the building from the east, making inspection and maintenance of the pipes difficult.

**SOLUTION:** Install cleanouts outside of the building on the main sewer lines and laterals.

**COST:** \$2,400

**PRIORITY LEVEL:** 4

**PROBLEM:** One section of waste piping within the low bay slopes backward (into the building) for approximately 20 feet, at a grade of roughly .45 inches per foot. This condition can hamper flow and contribute to blockages, creating a maintenance issue.

**SOLUTION:** Re-grade the waste pipe so that it slopes downward toward where it exists the building.

**COST:** \$ 26,400

**PRIORITY LEVEL:** 4

**PROBLEM:** Roof drain assemblies and rainwater leaders in some observed portions of the Low Bay are not insulated, which allows heat loss through the piping (photograph 24/MM-16).

**SOLUTION:** Insulate all roof drains and rainwater leaders to improve the energy efficiency of the space.

**COST:** \$5,625

**PRIORITY LEVEL:** 4





Typical Air Handling Unit  
PHOTOGRAPH 01



New Air Handling Unit  
PHOTOGRAPH 02



Centrifugal Chiller  
PHOTOGRAPH\_03



Cooling Tower  
PHOTOGRAPH 04





Cooling Tower Treatment System  
PHOTOGRAPH 05







Heating Water Boiler  
PHOTOGRAPH 06



Heating Water Circulation Pump  
PHOTOGRAPH 07



Hydronic Piping  
PHOTOGRAPH\_08



Sewer Main Line, PVC  
PHOTOGRAPH\_09






Sewer Main Line, Cement  
PHOTOGRAPH 10



Sewer Lateral Line, PVC  
PHOTOGRAPH 11

**09:27:45 AM / 06-01-2016**



Waste Line, Cast Iron  
PHOTOGRAPH 12

**10:11:35 AM / 06-01-2016**



Waste Line, Cast Iron  
PHOTOGRAPH 13



Abandoned Steam Piping  
PHOTOGRAPH 14





Abandoned Steam Condensate System  
PHOTOGRAPH 15




Air Terminal Unit  
PHOTOGRAPH 16



Horizontal Unit Heater  
PHOTOGRAPH 17



Vertically-Discharging Unit Heater  
PHOTOGRAPH 18



Humidification Unit  
PHOTOGRAPH 19





AHU Moisture Damage  
PHOTOGRAPH 20



Signs of Rust and Scale in Pipes  
PHOTOGRAPH 21



Cooling Tower Leak Damage and Patches (View of Bottom of Tank)  
PHOTOGRAPH 22





Pneumatic Valve Actuator  
PHOTOGRAPH 23



Roof Drain and Drain Piping, Uninsulated  
PHOTOGRAPH 24



## 4. STRUCTURAL

### I. INTRODUCTION

- A. Peterson Structural Engineers (PSE) evaluated five locations/components of the Modular Building. PSE evaluated the following items:
- Fall Restraint for the Low and High Roof
  - Cooling Tower Fall Restraint and Anchorage
  - Mezzanine Loading and Access
  - Storage Racks
  - Building Seismic Analysis

### B. GENERAL CONDITION OF THE EXISTING STRUCTURE

#### Fall Restraint for the Low and High Roof

The height of the building parapet (both high and low bay buildings) is not sufficient to prevent falls from the roof. The minimum height required to adequately prevent falls and be considered a railing is 42" vertical (IBC 2012 Section 1013). Current vertical parapet heights vary from 12" (at roof "ridge") to approximately 41" (at roof corners) and follow the slope of the roof (photograph 1/SS-1). PSE understands that maintenance workers or contractors doing work on the roof are required to wear fall protection harnesses regardless of where the work being performed is located on the roof with the current parapet configuration.

To correct this deficiency, the height of the parapet should be increased or a railing added to comply with fall protection requirements. PSE has identified four options to provide code-compliant fall protection. Of these options, extending the parapet vertically is the preferred option.

- i. **Extend Parapet** – This option involves extending the parapet vertically using cold form steel stud in a fashion similar to the existing detail. The existing parapet is supported vertically by a structural steel channel which runs around the perimeter of the building and is located below the roof framing (photograph 2/SS-1 and 3/SS-2). The parapet cold form studs run outboard of the perimeter roof framing and form the parapet. The full parapet section includes exterior insulated metal panels, the steel channel studs, wood sheathing backing and the roof membrane.

To extend the parapet, new cold form steel studs would be placed back to back with the existing studs (photograph 4/SS-2). The new studs would have a height/length such that the 42-inch minimum for railings is satisfied. The option would require peeling back the roof membrane so a positive connection could be made between the structural steel roof framing and the parapet members. See sketch SSK-1 in Appendix A for a proposed detail.

- ii. **New Pipe Railing** – Install a new conforming pipe railing inboard of the existing parapet. The base of this pipe railing would need to be welded or bolted to the top flange structural steel roof framing. This option is highly intrusive and requires penetrating the roof membrane. Constructability is also a concern as the connection to the top flange of the steel roof beam would be difficult to access. The roof beam would also likely need to be braced for torsion along its length with kickers to neighboring structure.
- iii. **New Roof Anchor** - Install a new roof anchor to the top of an existing interior column to provide an engineered tie-off point for workers/maintenance staff on the roof. This option would still require workers to be tied off to the structure. This option also requires penetrating the roof membrane. It is viable from a structural perspective but does not change the need for workers to tie off when working on the roof.
- iv. **Extend Perimeter Columns** – This option creates a new railing by extending the existing perimeter columns vertically so a beam can span between them. This option also requires the roof

membrane to be penetrated. Besides an unappealing aesthetic, there are considerable constructability issues.

### Cooling Tower Fall Restraint and Anchorage

The cooling tower (photograph 5/SS-3) requires scaffolding (photograph 6/SS-3) to access the upper portion of the equipment during maintenance. It is desired that permanent scaffolding and/or fall restraint could be added to the cooling tower so temporary scaffolding would not be required every time the equipment required maintenance. It was apparent during the site visits that it was not feasible or practical to add scaffolding or fall restraint to the existing equipment. Assuming the existing cooling tower is to remain, the temporary shoring still appears to be the best solution.

PSE was also tasked with determining the anchorage demands for lateral loading (wind and seismic) loading from the equipment that is transmitted to the structure below. The purpose of determining the anchorage demands was for evaluating the existing anchorage and support structure.

Four vertical pipe supports carry the weight of the cooling tower above. These pipes are welded to the joists located immediately below the cooling tower (photograph 7/SS-4). In addition to the four vertical pipes, the support frame utilizes four outriggers (photograph 8/SS-4) to widen the support at the base, increasing the lateral stability of the cooling tower support frame. The ends of the outriggers are not positively connected to the structure below and are not capable of transmitting any shear or tensile loads. They are only able to transmit vertical compressive loads to the structure (joist) during lateral events via direct bearing. Additionally, the cooling tower sits on four damping springs located at the corner of the base frame. It is assumed that these springs are included to damp out vibrations due to normal operation of the equipment. PSE conservatively considered these springs to be rigid when determining demands from wind and seismic loading.

The existing equipment and support structure was analyzed under current code level wind and seismic loading. Seismic loading was found to govern anchorage demands relative to wind loading. Seismic overturning demands were approximately 35% greater than wind demands. Detailed calculations can be found in Appendix B of this report.

Maximum shear load (EQ only) transferred by the pipe supports directly beneath the cooling tower is approximately 1,800 lbs. Maximum tensile load (EQ + DL) transferred by the pipe was approximately 1,300 lbs. and maximum compression (vertically downward) load (EQ + DL) was approximately 2,800 lbs. The welds at the base of the pipe were found to be sufficient to transfer the forces to the joist below. Maximum compression transmitted by the outriggers (vertically downward) was 2,700 lbs. As previously stated, the outriggers are not capable of transmitting shear or uplift forces.

Table S01 below summarizes the utilization ratios for the different directions of controlling seismic and wind loads. Note that four separate joists support reactions from the cooling tower. The utilization ratios presented below represent the single joist with the highest utilization ratio. "Uplift" loads represent cases all loads applied to the beam were uplift loads. Due to the support frame geometry this was only possible when the wind or seismic forces acted in the N/S direction. It was determined that maximum utilization ratios ranged from 0.16 to 0.61.

No corrective action is required or anticipated. The existing attachment of the equipment and supporting structure (joists) are adequate for the anticipated loads.

EAST-WEST DIRECTION			NORTH-SOUTH DIRECTION		
ITEM	DIRECTION	UTILIZATION	ITEM	DIRECTION	UTILIZATION
SEISMIC	UPLIFT	n/a	SEISMIC	UPLIFT	0.22
SEISMIC	DOWNWARD	0.61	SEISMIC	DOWNWARD	0.50
WIND	UPLIFT	n/a	WIND	UPLIFT	0.16
WIND	DOWNWARD	0.36	WIND	DOWNWARD	0.35

**Table S01 – Cooling Tower Summary**

### **Mezzanine Loading and Access**

The mezzanine platform located in the high bay building is currently posted for 125-psf allowable storage load. PSE was tasked to confirm this posting or provide recommendations for lesser loading if appropriate (photographs 9/SS-5 and 10/SS-5). It was determined that the safe allowable loading for the mezzanine should be reduced to 100-psf. The loading was controlled by the capacity of the open web steel joist. Detailed calculations are included as part of Appendix C. Note that the calculated 100-psf loading supports the 100-psf design live load listed in the existing drawings general notes (DES 79-244 sheet S1).

The mezzanine is accessed by a stair way and a steep "ship's ladder" (photograph 11/SS-6). Building staff tasked PSE with evaluating the existing railings for compliance with current railing code requirements. Railings for both the stairs and ship's ladder (photograph 12/SS-6 and 13/SS-7) were evaluated under requirements found in the 2012 IBC Chapter 10 (Means of Egress) and OSHA 3124-12R 2003 (Stairways and Ladders, A Guide to OSHA Rules). Railings for both elements met the railing requirements for stairs and ladders, respectively. Detailed analysis can be found in Appendix D.

### **Storage Racks**

Some minor cracking has been observed around the existing storage racks (photograph 14/SS-7) near the mezzanine in the high bay building. PSE evaluated the cracking around the storage racks and believes that the cracking observed is normal for a concrete slab of that age and construction. It should also be noted that the concrete slab was evaluated in 2014 by AHBL and the existing concrete slab was also found to be adequate to support the storage loads.

PSE conducted an independent evaluation of the rack anchorage to the concrete slab under seismic loading following procedures found in ASCE 7-10 (Minimum Design Loads for Buildings and Other Structures) and the Rack Manufacturer's Institute (RMI) "Specification for the Design, Testing and Utilization of Industrial Steel Storage Racks". Assuming that each storage rack is anchored with (2) ½" diameter Hilti Kwik Bolt TZ expansion type anchors with 3.25-inch embedment (as PSE understands is common for these types of racks), the maximum product loading allowed per shelf is 85-psf or 2,640-lbs. The weight of the actual material being stored on the racks should be evaluated to confirm it is within the 2,640-lb per shelf limit. If the actual weight of product exceeds this load limit, the loads should either be reduced or the anchorage upgraded to comply with the increased demands. It should be noted that if the as-installed anchorage exceeds what has been assumed, additional product load capacity may be realized.

### **Whole Building Seismic Evaluation**

PSE understands that no upgrades to the main lateral force resisting system (MLFRS) have been completed since the building was constructed in the early 1980's. The existing MLFRS utilizes a braced frame system with two braces typical on each side of the building. However, given the age and construction of the building, PSE anticipates that the detailing of these braces may not be adequate for current code prescribed loading (amongst other potential deficiencies).

As part of the building seismic evaluation, PSE performed both a Tier 1 and Tier 2 seismic screening per ASCE/SEI 41-13: *Seismic Evaluation and Retrofit of Existing Buildings* (ASCE 41). These two screenings involve following prescriptive procedures to evaluate potential issues with the MLFRS, diaphragms, and foundations.

The checklists in the ASCE 41 Tier 1 screening are differentiated by building type and are based on past observed performance of similar buildings. Each item in the checklist must be marked as "Compliant", "Noncompliant", "Not Applicable", or "Unknown". In accordance with ASCE 41, any checklist item that was identified as "Noncompliant" or "Unknown" was deemed deficient. A completed Tier 1 checklist is included as Appendix J of this report.

In order to consider the structural deficiencies determined during the Tier 1 screening in more detail, PSE also performed a Tier 2 evaluation. This evaluation was limited to the items identified as "non-



compliant" during the Tier 1 evaluation. Detailed calculations produced for this portion of the evaluation are included as Appendix K.

For the Tier 1 screening, PSE considered the modular building as shown in the as-built documents (dated 04/07/1980 and revised 06/26/1981) provided by the client. PSE also performed two site visits (April 26<sup>th</sup>, 2016 and June 13<sup>th</sup>, 2016) to observe the existing condition of the MLFRS. The main lateral force resisting systems in all directions are concentrically braced steel chevron frames (photograph 15/SS-8). The building was analyzed in two different portions: northern and southern (low and high bay, respectively). Each wall of the building has two 20-foot bays which contain frames. The remaining bays have steel gravity only frames to resist gravity loads. The high bay portion of the modular building has two stories of frames while the northern portion of the building only has one. The roof diaphragms for each portion consist of Type B 1½"-deep, 20 gage metal decking. Since there is no concrete topping, the diaphragms were assumed to be flexible. Table S02 shows the pertinent design criteria for the screening performed on the subject building.

CRITERION	VALUE	LOCATION IN ASCE 41
Common Building Type	Steel Braced Frame (S2a)	Table 3-1
Structural Performance Level	Life Safety (S-3)	Section 2.3
Level of Seismicity	High $S_{D1} > 0.20g$	Table 2-5

**Table S02 – Design criteria for seismic evaluation, per ASCE 41**

From the table above, since the subject building has a MLFRS consisting of concentrically braced frames; it is defined by ASCE 41 as a common building type S2. The roof diaphragm is an untopped metal deck, which is defined as flexible in Table 3-1 of ASCE 41. This distinction means the building type is S2a, where the "a" indicates that the building has a flexible diaphragm.

A building that complies with the Life Safety structural performance level (given the designation S-3 by ASCE 41) may incur significant damage during a seismic event, but should not undergo partial or total collapse.

The level of seismicity was determined using site-specific acceleration data that was provided by the USGS Seismic Design Maps. This data was obtained by assuming Soil Site Class D (stiff soil). Table 2-5 of ASCE 41 requires the use of both design short-period spectral response acceleration,  $S_{DS}$ , and design spectral response acceleration at a one-second period,  $S_{D1}$ . Since the level of seismicity defined by  $S_{D1}$  controlled over the level defined by  $S_{DS}$ , this was the only value shown.

Per ASCE 41, a benchmark building is a building with a specific performance level that, if designed to a specific code, automatically complies with the Tier 1 screening procedure. According to the as-built documents, the subject building was designed according to the 1979 edition of the Uniform Building Code (UBC). However, for a building with steel concentrically braced frames and a Life Safety structural performance level, conformance to the 1997 edition (or later) of the UBC is required to satisfy the benchmark building requirement. The benchmark building criteria are given by Table 4-6 of ASCE 41.

The items listed below include the non-compliant or unknown statements from the requisite Tier 1 checklists provided in ASCE 41 and are updated with information from the Tier 2 study.

- i. **SEPARATION BETWEEN ADJACENT BUILDINGS:** There are three distinct structures on site and are immediately adjacent to each other: the low and high bay modular buildings and the Isabella Bush Building located to the south of the modular buildings. The seismic joint between the low and high bay buildings (gridlines G & H) allows for 2" of movement between the two buildings (per sheet A9 of drawing set 79-244). The height to top of roof of the low bay building at grids G and H is 13'-7". ASCE 41 states that the distance between adjacent structures must be greater than 4% of the shorter building height to be considered compliant. Under this requirement, a

6.5-inch seismic joint is required. By inspection, the existing 2-inch seismic joint is undersized for a building of this height. While outside the scope of this evaluation, it is assumed that the joint between the high bay and Isabella Bush building is similarly undersized.

Providing a seismic joint which allows for the anticipated seismic movements appears to be the most desirable option to address the separation issue. This option would appear to be rather intrusive as approximately 240 linear feet of joint would need to be replaced to account for horizontal and vertical joints. Tying or linking the buildings together to behave as one structure is not realistic due to the discrepancy in building heights. Another option is to accept that damage to the buildings is likely to occur during a seismic event but that collapse is unlikely. For an S-3 performance level this would be acceptable as life safety is preserved.

- ii. **SOIL LIQUEFACTION:** Per the Liquefaction Susceptibility Map for Thurston County (provided by the Washington State Department of Natural Resources), the subject building is located in an area that has a moderate susceptibility to liquefaction. Although the original construction documents state that existing soil be removed to a depth of ten feet and recompacted, and that another five feet of construction fill be placed on top of the recompacted native soil (DES 79-244 sheet C3), the Tier 1 requirement is that no liquefaction-susceptible soils be present within a depth of 50 feet.

There is no Tier 2 verification for the liquefaction requirement; however, ASCE 41 allows for the use of the liquefaction check in the Tier 3 evaluation (which is normally reserved for investigating the entire building). Per the geotechnical report included in the construction documents (DES 79-244 sheet C4), the underlying soil layer is medium dense, coarse to very coarse gravelly sand. This layer was present down to the maximum depth investigated, which was 24 feet below existing grade. The best-case estimated liquefaction susceptibility for this site is low. However, this site does not meet any of the criteria set forth in Section 8.2.2.2 of ASCE 41. These criteria dictate whether or not a site may be regarded as non-liquefiable.

Therefore, it is recommended that a new site-specific geotechnical investigation should be performed to confirm the liquefaction potential during a seismic event for this specific site. Future detailed retrofit design will require the consideration of the effects of liquefaction on the structure if liquefaction is likely.

- iii. **DIAPHRAGM TRANSFER TO STEEL BEAMS:** During the follow-up site visit, PSE was able to determine that the existing detail between the steel beams and diaphragm is able to transfer seismic loads into the MLFRS. No retrofit is anticipated to this area.
- iv. **BRACE CONNECTION STRENGTH:** Per the Tier 1 requirements, none of the brace connections have sufficient strength to develop the yield strength of the diagonal braces. Under the Tier 2 evaluation, demands for these connections were less stringent as they were based on limit-state analyses of the braced frames. None of these limit states were able to transmit a load large enough to cause the braces to yield. However, the demands on these connections were still greater than each connection's respective capacity.

Therefore, PSE recommends that brace frame connections be strengthened in order to increase their capacity. The connections may be strengthened by adding stiffener plates, anchor bolts, or welds, depending on the connection's specific configuration. A sample connection upgrade is shown in sketch SSK-2 in Appendix L.

- v. **WALL OUT OF PLANE CROSS TIES:** During the follow-up site visit, PSE was able to determine that the connection of the roof diaphragm and the wall is adequate for transferring out of plane loads. No retrofit is anticipated to this area.
- vi. **VERTICAL IRREGULARITY:** The original construction documents show two sets of stacked braced frames along each wall of the high bay building (DES 79-244 sheet S7). However, one of the

lower braces on the east side of the building was moved north two bays to accommodate a new roll up door (photograph 16/SS-8). This resulted in braced frames that are not continuous to the foundation. This condition is non-compliant with the Tier 1 vertical irregularities provision.

ASCE 41 allows for vertical irregularities provided that the load can adequately be transferred from frame to frame and to the foundation. This means that not only must there be elements in place to transfer seismic force—struts to transfer shear and columns to transfer the overturning forces—but these elements must also have the capacity to resist the seismic force.

These support elements (beams and columns) were analyzed using Tier 2 limit-state analysis. This analysis involved determining the expected strength of the MLFRS and using the corresponding seismic load to analyze the whole system. From this analysis, the support columns were deemed to be adequate, but the W12x26 beam that spans the 20-foot bay between the upper and lower frames was determined to be an inadequate strut. Because seismic force cannot be adequately transferred between frames, PSE recommends that either the strut be upgraded to a section that can adequately transfer the seismic force or that the upper frame is moved so that it shares the same bay with the lower frame.

## C. CONSTRUCTION

### Building Code

The building was originally constructed in 1979 under the 1979 Edition of the Uniform Building Code (UBC) by the International Conference of Building Officials. Original Engineer of Record (EOR) was Victor O. Gray & Company.

A mezzanine was added in 1982 under the 1979 Edition of the UBC. The mezzanine is located between grids A & G and 1 & 3.

It appears that only minor structural upgrades and repairs have been completed since the original construction. It appears that a lateral brace was moved from its original location on the east wall of the high bay building to make room for new roll up doors.

### Original Design Loadings (per DES 79-244 sheet S-1)

Dead (typical)	as required
Dead (future mezzanine)	60 psf
Live (mezzanine mech.)	150 psf
Live (roof)	25 psf
Live (hung equipment)	5 psf
Live (RTU's)	as required
Live (future mezzanine)	100 psf
Wind (UBC)	25 mph zone
EQ (UBC)	zone III
Allowable Soil Bearing	4,000 psf

## II. PROBLEMS TO BE CORRECTED AT THIS TIME

### 1. PUBLIC HAZARD

#### PROBLEM: Fall Restraint at the Low and High Roof

The existing parapet is not compliant with current code to prevent falls from the roof. Maintenance staff or contractors performing work are currently required to wear a harness regardless of where they are working on the roof.

**SOLUTION:** Extend the parapet per sketch SSK-1,  
**QUANTITY:** Approximately 1,320 LF of extended parapet  
**COST:** \$322,529  
**PRIORITY LEVEL:** 2

**PROBLEM: Cooling Tower Fall Restraint**

Temporary scaffolding is required when performing maintenance on the cooling tower.

**SOLUTION:** Continue to provide access with temporary scaffolding or replace cooling tower with unit that incorporates improved maintenance access

**QUANTITY:** 1

**COST:** N/A (cooling tower to be replaced per DES – see Mechanical section of report)

**PRIORITY LEVEL:** 3

**PROBLEM: Mezzanine Loading**

The mezzanine between grids A & G and 1 & 3 is posted for 125 psf but is only adequate to support 100-psf.

**SOLUTION:** Evaluate the weight of the products being stored on the mezzanine and confirm that less the weight is less than 100-psf. If the product load exceeds this limit, the weight of the product stored on the mezzanine should be reduced. The mezzanine should also be posted for a 100-psf storage load limit.

**QUANTITY:** Two locations

**COST:** \$1,200

**PRIORITY LEVEL:** 3

**PROBLEM: Storage Rack Capacity**

The storage racks may be overloaded depending on the weight of the products currently being stored.

**SOLUTION:** Evaluate the weight of the products being stored on the racks and confirm that less than 2,640-lbs are stored on any individual shelf. If the product load exceeds this limit, the weight stored per shelf should be reduced or the anchorage upgraded. Assuming no anchorage upgrades are made the storage racks should be posted for a 2,640-lb or 85-psf per shelf weight limit.

**QUANTITY:** Two locations

**COST:** \$1,200

**PRIORITY LEVEL:** 3

**PROBLEM: Separation Between Adjacent Buildings**

The as-built seismic joint located between grids G and H allows for only 2-inches of movement and is undersized for the anticipated movement demands.

**SOLUTION:** Replace the seismic joint between the two buildings with a joint that can accommodate the anticipated seismic loads. The replacement joint should allow for 6½-inches of movement.

**QUANTITY:** 240 linear feet

**COST:** \$44,994

**PRIORITY LEVEL:** 2

**PROBLEM: Soil Liquefaction**

It is unknown if the soils present at the building site are susceptible to liquefaction. If liquefiable soils are present, future detailed retrofit design will require the consideration of the effects of liquefaction on the structure.

**SOLUTION:** Conduct a site specific geotechnical investigation based on the constructed soil profile.

**QUANTITY:** n/a

**COST:** \$20,000

**PRIORITY LEVEL:** 2

**PROBLEM: Brace Connection Strength**

The seismic braced frame connections are not adequate to transfer the anticipated seismic demand.

**SOLUTION:** Retrofit the brace frame connections to increase their capacity. The connections may be strengthened by adding stiffener plates, anchor bolts, or welds, depending on the connection's specific configuration. A sample connection upgrade is shown in sketch SSK-2.

**QUANTITY:** 72 connections

**COST:** \$283,589

**PRIORITY LEVEL:** 2

**PROBLEM: Vertical Irregularity**

A vertical irregularity exists where a brace was moved to allow for installation of a new roll-up door on the east wall of the high bay building.

**SOLUTION:** Upgrade the W12x26 strut to a section that can adequately transfer the seismic force or move the upper braces north so it shares the same bay as the lower frame.

**QUANTITY:** 1 location

**COST:** \$23,284

**PRIORITY LEVEL:** 2

**2. BUILDING MAINTENANCE**

Not applicable.

**3. CONSULTANT RECOMMENDATIONS**

Not applicable.

I HEREBY CERTIFY THAT THIS DOCUMENT WAS PREPARED BY ME OR UNDER MY DIRECT PERSONAL SUPERVISION AND THAT I AM A DULY LICENSED ENGINEER IN THE STATE OF WASHINGTON.





Parapet From Roof (at roof "ridge")  
PHOTOGRAPH 1



Parapet Base From Interior (from Mezzanine)  
PHOTOGRAPH 2

## MODULAR BUILDING ASSESSMENT

Structural SS-1





Parapet Base Detail (from roof access)  
PHOTOGRAPH 3



Parapet Cavity  
PHOTOGRAPH 4

MODULAR BUILDING ASSESSMENT

Structural SS-2



Cooling Tower  
PHOTOGRAPH 5



Cooling Tower Scaffolding  
PHOTOGRAPH 6

## MODULAR BUILDING ASSESSMENT

Structural SS-3





Cooling Tower Support Pipe Connection to Joist Below  
PHOTOGRAPH 7



Cooling Tower Outrigger Detail  
PHOTOGRAPH 8

MODULAR BUILDING ASSESSMENT

Structural SS-4



Underside of Mezzanine  
PHOTOGRAPH 9



Mezzanine Framing  
PHOTOGRAPH 10

## MODULAR BUILDING ASSESSMENT

Structural SS-5





Mezzanine Ships Ladder  
PHOTOGRAPH 11



Mezzanine Ships Ladder Railing Detail  
PHOTOGRAPH 12

## MODULAR BUILDING ASSESSMENT

Structural SS-6





Mezzanine Stair Railing  
PHOTOGRAPH 13



Storage Racks  
PHOTOGRAPH 14

## MODULAR BUILDING ASSESSMENT

Structural SS-7



Typical Brace/Beam Connection  
PHOTOGRAPH 15




Offset Braces Resulting in Vertical Irregularity  
PHOTOGRAPH 16

## MODULAR BUILDING ASSESSMENT

Structural SS-8

**SCHEMATIC DESIGN – NOT FOR CONSTRUCTION**

NEW PARAPET COLD FORM STEEL AT 15" O.C. PLACED BACK TO BACK WITH EXISTING FROM NEW TOP OF PARAPET TO STEEL SUPPORT CHANNEL BELOW



**MODULAR BUILDING PARAPET**

**PROJECT SITE:**  
 WA State Print Shop  
 7580 New Market Street  
 Tumwater, WA 98501

**CLIENT INFO:**  
 Ehm Architecture  
 1200 Fifth Avenue, Suite 1208  
 Seattle, WA 98101

16-150-01  
**PROPOSED PARAPET MODIFICATIONS FOR FALL PROTECTION**


PSE JOB No.  
 16-150

DRAWN: WJS      CHECKED: TGM

DATE: 5/11/16

REVISIONS


SHEET  
 SSK-1



SCHEMATIC DESIGN – NOT FOR CONSTRUCTION

0 NOTICE 1

IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO SCALE



**PSE**  
 Peterson Structural Engineers, Inc.  
 5319 S.W. Westgate Dr., Suite 215  
 Portland, Oregon 97221  
 (503) 292-1635

**MODULAR BUILDING PARAPET**

**PROJECT SITE:**  
 WA State Print Shop  
 7580 New Market Street  
 Tumwater, WA 98501

**CLIENT INFO:**  
 Ehm Architecture  
 1200 Fifth Avenue, Suite 1208  
 Seattle, WA 98101

SHEET CONTENT  
 16-150-01

**PROPOSED TYPICAL  
 BRACE CONNECTION  
 RETROFIT**

PSE JOB No.  
 16-150

DRAWN WJS CHECKED TGM

DATE 6/30/16

REVISIONS

SHEET  
**SSK-2**





## 5. ELECTRICAL

### I. INTRODUCTION

A. Elcon Associates, Inc. personnel inspected electrical components of the Modular Building on April 8 and April 26, 2016. The Scope of Work included assessment of building power distribution system, interior lighting, and loading dock levelers. The Scope of Work also included a review of a 2012 ESCO Audit and update of associated costs.

### B. GENERAL DESCRIPTION OF THE EXISTING ELECTRICAL SYSTEMS

The power distribution and interior lighting systems are mostly original, with a few minor upgrades and modifications apparent.

**AGE:** Built in 1980, the modular structure's electrical systems are approximately thirty-six years old.

**CONDITION:** The building electrical components are in good to fair condition, as further outlined herein.

**ADEQUACY OF COMPONENTS:** The building power distribution and lighting systems are adequate to their current use. There are no significant anticipated changes to the building that would exceed the system capacity.

**REMAINING SERVICE LIFE:** Through a program of preventive maintenance, the power distribution and lighting system should have a remaining service life of approximately twenty years.

### BUILDING ELECTRICAL COMPONENTS

#### Electrical Distribution

The existing electrical distribution system consists of an incoming 480/277volt, 1500kVA Utility transformer that supplies a 480/277volt, 2500amp (approximately 2000kVA rated) fused switchboard (photograph 01/EE-1) loaded to 500kVA (600amps) or one-third of the Utility transformer. The Main Switchboard feeds four (4) 800amp 480/277volt switchboards (photograph 02/EE-1). A recently installed 250kW generator located outside next to the Utility transformer provides backup power for lighting, and payroll and check printers.

The electrical serviceable life is dependent on how hot the panels and circuit breakers have been due to electrical loading, also on the number of operations (on/off cycles) the circuit breaker/switch have been subjected to. Another item in determining serviceable life is the environment; is the equipment installed outside, inside, in dirty or clean location, and if there is condensing moisture, based on the ambient temperature.

The exposure to excessive heat shortens the life span of electrical equipment, unless the equipment has been too hot to touch, aging due to high temperatures is not an issue.

Another aspect of equipment aging is the number of operations (on/off cycles) the circuit breaker, fused switch, contactor, etc. has been subject to. A typical UL listed circuit breaker is tested for approximately 10,000 operations (27 years if cycled once per day, 365 days per year, 7 days a week); 6,000 operations at fully rated current and voltage, and additional 4,000 operations without current. A contactor or relay is typically rated for 100,000 electrical operations. Contactors are used in motor controllers and some lighting control panels.

The last set of items is environment and maintenance in determining aging factors for equipment. The building is clean and heating and ventilation keeps moisture out of equipment limiting corrosion. The cleanliness of the building also keeps contaminants out of equipment preventing arcing and tracking in the electrical equipment causing equipment failures.

#### Lighting

The lighting system is functioning normally, and there are no apparent immediate wholesale repair needs. Lighting levels are below recommended levels at printing stations. Light fixtures are mature, and appear to be at the point where components are reaching end of life and needing frequent replacement. See Audit discussion below.

### **Dock Levelers**

The load dock levelers (photograph 03/EE-2) are powered at 480volts 3-phase power. The dock leveler controllers (photograph 04/EE-2) are located inside the building next to each respective rollup door. Electrically the dock levelers are functional except for the North load dock, where power is disconnected, and it was not possible to verify if the dock leveler was functional. See related report by Industrial Hydraulics in Appendix B.

## **C. AUDIT**

### **Review**

The University Mechanical 11/27/2012 Investment Grade Audit for the State Modular Building Energy Upgrades' sole electrical consideration was the building interior lighting system. It discussed only possible energy reduction measures. It did not include any review of lighting levels, glare, color rendering, or other light quality or maintainability considerations. The audit proposed lighting retrofits or replacements for 1,199 fixtures out of 1,254 fixtures. The audit proposed adding 7 new occupancy controls. The audit identified \$4,383 design cost, \$87,650 construction cost, \$13,500 utility energy rebate, and a \$6,543 annual savings in energy use and operational savings. No defect was found in our review of the Audit costs identified, for the time they were issued.

**QUANTITY:** 1,199 replaced or retrofitted fixtures,

7 occupancy sensors

**COSTS:** \$4,383 design cost

\$87,650 construction cost

(\$13,500) utility energy rebate

(\$6,543) annual savings

### **Update**

The audit recommendations were not examined exhaustively in the field. It appears some the recommendations have already been implemented such as replacement of mercury-vapor lighting in lobby areas with compact fluorescent. The U.S. Inflation Rate has increased by 4.2% between 2012 and 2016. The 2012 Washington State Energy Code went into effect in July 2013, and its requirements were not reflected in the Audit costs. The 2015 Washington State Energy Code is scheduled to be in effect as of July 1, 2016, and is assumed applicable to any lighting work proposed. The Energy Code updates compel implementation of more lighting controls and attendant design than were included in the Audit. The 2016 update decreases the allowed energy use for lighting by approximately 20%, making LED fixtures the only viable solution for some applications. The Energy Code requirements dilute the potential utility rebate, since the utility will only pay for energy efficiency measures above and beyond what the Energy Code compels. .

**QUANTITY:** 1,199 replaced or retrofitted fixtures,

Whole building lighting control system per Code

**COSTS:** \$32,000 design cost

\$212,000 construction cost

(\$7,000) utility energy rebate

(\$7,500) annual savings

The approach taken in the Audit was directed purely at lighting changes to achieve energy savings that resulted in a 9.8 year simple payback. An alternative lighting design approach is one driven by operational needs - insuring appropriate lighting levels and quality are provided for the tasks performed. This design approach includes lighting measurements and calculations. Minimizing the energy use and construction cost is a secondary consideration. Cost estimating for this traditional design approach typically includes capital costs, and life-cycle costs when identified in the project scope. The lighting industry is shifting more and more to LED fixtures. Life-cycle cost evaluation typically finds that LED fixtures are a more appropriate solution in occupied facilities (~ 40 hrs/week). Fluorescent fixtures still are utilized, but are pretty much relegated to seldom used spaces such as storage closets where there isn't enough usage of the lighting to achieve payback of the additional cost for an LED solution.

## **D. CONSTRUCTION**

### **Existing Drawings**

Drawings were obtained from the Owner for most of the building elements. However, some minor building components do not appear on the available drawings.

### **Changes Required by Current Electrical Codes**

Our inspection supports an assessment that the lighting and power distribution systems are be compliant with the Code in effect at the time of installation. As such, these systems are 'grand-fathered' and are not required to be updated to meet current Code requirements. The factors which would trigger Code related updates are changes in use or occupancy of the building, and modification of the lighting or power distribution systems. The extent of Code required upgrades would depend on the good judgment of the engineer, the electrician, and the electrical inspector.

Any major remodel or re-lamping and re-ballasting will trigger current Washington State Energy Code and the modified lighting system would need to be brought into compliance with current energy limits and control requirements for lighting.

## **E. RECOMMENDATIONS**

### **Preventive Maintenance**

Perform regular maintenance of electrical equipment in accordance with NEMA, NFPA 70B, or other industry standard, to include annual infrared scanning (imaging) be done to locate any hot spots caused by loose connections, overloads, or dirty contacts in circuit breakers or fused switches. Regular maintenance of equipment ensures reliable facility operation, protects personnel and equipment from catastrophic failure of deteriorated equipment, and eliminates owner liability for preventable accidents.

**Cost:** \$ 2,400/Year

**Priority Level:** 3

### **Power Distribution**

Wholesale replacement of the building power distribution system is not warranted at this time. The system is expected to provide relatively trouble-free operation for at least the next five years with regular maintenance. As the system exceeds its design life, component repair and replacement needs will become more common. At some point the cost/benefit of continuing with spot repairs and declining reliability versus system replacement will motivate a building-wide refurbishment of the electrical distribution system.

**Cost:** \$ 572,880

**Priority Level:** 5

### **Lighting**

The recommended approach, depends on the objective. Three different recommendations are provided below to suit different objectives.



1 - Continue to maintain the existing lighting system on an as-needed basis. This is the least capital cost solution, and is appropriate for a maintenance-only budget, with a financial outlook of 10 years or less. Costs will be similar to those currently experienced in the facility.

**OPTION 1 COST:** \$54,000 annual maintenance (parts and labor)

2 – Perform an ESCO type lighting upgrade focused on retrofit or replacement of existing fixtures with lower wattage alternatives with a reasonable cost/benefit payback period. This would be an updated version of the 2012 Audit approach. Due to Code compelled increases in the controls and design costs, simple payback for this alternative is estimated at 12 years. Costs are noted in the Audit – Update section above.

**OPTION 2 COST:** \$229,500 net, see Audit Update for details

3 – Perform a complete building lighting system replacement with full design. This is a best management approach for a facility whose operation is expected to continue for the next 20 years or more. It ensures appropriate lighting for all the building operations, and replaces the existing lighting system, which is at the end of its design life. This is a capital equipment/building renovation project that it is not feasible under a maintenance budget that has limited dollars and many building systems to maintain.

**OPTION 3 COST:** \$344,000

I HEREBY CERTIFY THAT THIS DOCUMENT WAS PREPARED BY ME PERSONALLY, AND THAT I AM A DULY REGISTERED ENGINEER IN THE STATE OF WASHINGTON.





Elect Rm 704 - Main Switchboard 2500Amps  
PHOTOGRAPH 01



Elect Rm 704 - Switchboard 'HA' 800Amps  
PHOTOGRAPH 02

MODULAR BUILDING ASSESSMENT

Electrical EE-1



Load Dock Leveler  
PHOTOGRAPH\_03



Load Dock Leveler Controller  
PHOTOGRAPH\_04

## MODULAR BUILDING ASSESSMENT

Electrical EE-2





		PRIORITY LEVEL				
		1 - Critical Life Safety Issue	2 - Critical Issue	3 - Significant Issue	4 - Moderate Issue	5 - Minor Maintenance
<b>2</b>	<b>Architectural</b>					
	Repair Damaged Insulated Panels		\$8,290			
	Paint Insulated Panels			\$150,647		
	Replace Failing Panel Seals		\$46,665			
	Repair Dock Levelers	\$6,760				
	Replace Overhead Rolling Doors		\$65,435			
	Replace Inoperable Dock Levelers		\$11,194			
	Remediate Parking Lot Drainage					\$580,849
	Replace Aging Roof System			\$1,961,441		
	Modify Ramps at Entry	\$2,518				
	Replace Guardrail at Entry	\$11,897				
	Modify Path of Travel at Entry	\$793				
	Replace Noncompliant Ship's Ladders	\$18,507				
<b>3</b>	<b>Mechanical</b>					
	Increase Minimum Outside Air Settings	\$6,750				
	Replace AHU / Ductwork			\$1,000,927		
	Backflow Prevention at Humidification System		\$4,500			
	Wind/Rain Protection at AHU	\$11,250				
	Check Controls Programming for False Alarms		\$7,500			
	Replace Cooling Tower/Piping/Fittings/Seals	\$841,896				
	Replace Pneumatic Actuators with Electric		\$27,000			
	Assess Chiller Capacitors			\$7,500		
	Replace Ductwork in Low Bay			\$411,262		
	Adjust Controls Programming			\$30,000		
	Install Cleanouts on Main Sewer Lines/Laterals				\$2,400	
	Insulate All Roof Drains				\$5,625	
	Reline Waste Piping to Eliminate Infiltrations				\$33,750	
	Re-grade Twenty Foot Section of piping within the Low Bay section of the building				\$26,400	
	Hydro jet the waste piping				\$69,300	
	Replace hydronic heating boilers (2 boilers)		\$212,626			
<b>4</b>	<b>Structural</b>					
	Parapet Extension		\$322,529			
	Cooling Tower Fall Restraint			\$0		
	Mezzanine Load Posting			\$1,200		
	Storage Rack Load Posting			\$1,200		
	Replace Seismic Joint		\$44,994			
	Obtain Geotechnical Report		\$20,000			
	Retrofit Braced Frames		\$283,589			
	Address Vertical Irregularity of Brace		\$23,284			
<b>5</b>	<b>Electrical</b>					
	Continue to Maintain Existing Lighting				\$54,000	
	Esco Lighting Upgrade			\$229,500		
	Complete Lighting Upgrade			\$344,000		
	Preventive Maintenance			\$2400 per year		
	Replace Power Distribution Systems					\$572,880
	<b>TOTAL</b>	<b>\$900,371</b>	<b>\$1,077,606</b>	<b>\$4,137,677</b>	<b>\$191,475</b>	<b>\$1,153,729</b>

**Qualifications on Pricing**

Pricing includes Construction Costs only, and excludes all Soft Costs (Design, Sales Tax, Furnishings, Impact Fees).

Pricing Include applicable General Conditions, Supervision, Fee, Escalation in all all items

Contractor Markup/FEE/General Conditions change per item based on whether project is handled by prime subcontractor or managed by General Contractor





# Inspection Report



**Facility:** Modular Building High Bay

**Address:** 7580 New Market Street,  
Tumwater, WA 98501

**Customer:** Department of Enterprise Services

**Address:** PO Box 41475,  
Olympia, WA 98504

**Prepared By:**

Wayne's Roofing Inc.  
13105 Houston Rd. E.,  
Sumner, Washington 98390-9208

**Tel:** (253) 863-4455 **Fax:** (253) 863-8311

[www.waynesroofing.com](http://www.waynesroofing.com)

**Inspection Date:** Friday, September 18, 2015



# Inspection Report

Department of Enterprise Services, Tumwater, WA

Work Order #: 35198

Inspection Date: 10/2/2015 10:30:00 AM

## Roof Condition Summary

Building	Roof	SF	Roof System	Condition Rating
Imported Roofs	A -	170	White - PVC	Fair
Imported Roofs	B	304	White - PVC	Fair
Imported Roofs	C	885	White - PVC	Fair
Imported Roofs	D	1,202	White - PVC	Fair
Imported Roofs	E	3,147	Standing Seam - Metal	Fair
Imported Roofs	Bay	57,840	White - PVC	Fair
Imported Roofs	Bay	38,104	White -PVC	Fair



# Inspection Report

Department of Enterprise Services, Tumwater, WA


Work Order #: 35198

Inspection Date: -----

10:30:00 AM

Roof: A -

Building: Imported Roofs



Roof System: White - PVC  
Install Date: 1998 - Estimated  
Roof Deck: Metal  
Roof SF: 170  
Elevation: 15'  
Interior Sensitivity: 0 - None  
Warranty:

**Condition Assessment:** 50 - Fair

Roofs in fair condition. Minor debris were noted at this time. No visual problems noted during our inspection.

# Inspection Report

Department of Enterprise Services, Tumwater, WA



Work Order #: 35198

Inspection Date: -----

10:30:00 AM

Roof: B

Building: Imported Roofs



Roof System: White - PVC  
Install Date: 1998 - Estimated  
Roof Deck: Metal  
Roof SF: 304  
Elevation: 15'  
Interior Sensitivity: 0 - None  
Warranty:

**Condition Assessment:** 50 - Fair

Roofs in fair condition. No visual problems noted during our inspection.

# Inspection Report

Department of Enterprise Services, Tumwater, WA


Work Order #: 35198

Inspection Date: -----

10:30:00 AM

Roof: C

Building: Imported Roofs



Roof System: White - PVC  
Install Date: 1998 - Estimated  
Roof Deck: Metal  
Roof SF: 885  
Elevation: 18'  
Interior Sensitivity: 0 - None  
Warranty:

**Condition Assessment:** 50 - Fair

Roofs in fair condition. No visual problems noted during our inspection.

# Inspection Report

Department of Enterprise Services, Tumwater, WA


Work Order #: 35198

Inspection Date: -----

10:30:00 AM

Roof: D

Building: Imported Roofs



Roof System: White - PVC  
Install Date: 1998 - Estimated  
Roof Deck: Metal  
Roof SF: 1,202  
Elevation: 18'  
Interior Sensitivity: 0 - None  
Warranty:

**Condition Assessment:** 50 - Fair

Roofs in fair condition. No visual problems noted during our inspection.

# Inspection Report

Department of Enterprise Services, Tumwater, WA


Work Order #: 35198

Inspection Date: -----

10:30:00 AM

Roof: E

Building: Imported Roofs



Roof System: Standing Seam - Metal  
Install Date: - Unknown  
Roof Deck: Plywood  
Roof SF: 3,147  
Elevation: 30'  
Interior Sensitivity: 2 - Medium  
Warranty:

**Condition Assessment:** 50 - Fair

Roofs in fair condition. No visual problems noted during our inspection.



# Inspection Report

Department of Enterprise Services, Tumwater, WA


Work Order #: 35198

Inspection Date: -----

10:30:00 AM

Roof: Modular - High Bay

Building: Imported Roofs



Roof System: White - PVC  
Install Date: 1998 - Estimated  
Roof Deck: Unknown  
Roof SF: 57,840  
Elevation: 32'  
Interior Sensitivity: 2 - Medium  
Warranty:

## Condition Assessment: 50 - Fair

Roofs in fair condition at this time.



Condition: 004- Debris on roof  
Severity: 2 - Secondary Repair  
Qty: SF: 1 LF: 4 EA: 1

Minor debris noted around the drainage areas. Drainage areas should always be kept clear for proper drainage of the roof.



Condition: EG - 204 - Condensation Lines  
Severity: 2 - Secondary Repair  
Qty: SF: 1 LF: 4 EA: 1

The condensation lines are lying directly on the roof surface. This detail could cause the PVC line to rub through the field membrane with back and forth movement. Recommend lifting and supporting the PVC lines up off of the roof surface. (2 locations - approximately 150 LF each)

# Inspection Report

Department of Enterprise Services, Tumwater, WA

Work Order #: 35198

Inspection Date: 10/2/2015 10:30:00 AM



Condition: EG-224 - Improper Installation  
Severity: 2 - Secondary Repair  
Qty: SF: 1 LF: 4 EA: 1

Current access stairs installed on this roof section should have a protection walkpad installed to protect the field membrane from wear. (3'x5' walkpad)



Condition: F-112 Field Membrane- temporary repair  
Severity: 2 - Secondary Repair  
Qty: SF: 1 LF: 4 EA: 1

The patch currently installed is designed to be temporary. A permanent repair is recommended as soon as possible.



Condition: PP-152 Penetration - Sealant failure  
Severity: 2 - Secondary Repair  
Qty: SF: 1 LF: 4 EA: 1

During our inspection we noted the caulking at this penetration is failing and needs to be ressealed.



Condition: PP-152 Pitch Pan- Sealant failure  
Severity: 2 - Secondary Repair  
Qty: SF: 1 LF: 4 EA: 1

Sealant should be removed and replaced to prevent water entry.

# Inspection Report

Department of Enterprise Services, Tumwater, WA

Work Order #: 35198

Inspection Date: 10/2/2015  
10:30:00 AM



006

Condition: 006- Ponding

Severity: 1 - Monitor

Qty: SF: 2 LF: 8 EA: 2

Ponding can add weight to the roof, and can cause many undesirable problems. If the roof membrane is damaged in a ponded area, the water may drain into the roof system and potentially into the building. We will continue to monitor these areas for any potential problems.

# Inspection Report

Department of Enterprise Services, Tumwater, WA


Work Order #: 35198

Inspection Date: .....

10:30:00 AM

Roof: Modular - Low Bay

Building: Imported Roofs



Roof System: White -PVC  
Install Date: 1998 - Estimated  
Roof Deck: Unknown  
Roof SF: 38,104  
Elevation: 25'  
Interior Sensitivity: 2 - Medium  
Warranty:

**Condition Assessment:** 50 - Fair

Roofs in fair condition.



**G-100** Condition: F-100 Field Membrane- deteriorated  
Severity: 3 - Immediate Action  
Qty: SF: 25 LF: 24 EA: 2

The roof membrane is deteriorated and should be replaced to avoid further degradation and the potential for leaks. Approximately a 4'x8' section.



**D-206** Condition: D-206 Drain- vegetation build up  
Severity: 2 - Secondary Repair  
Qty: SF: 1 LF: 4 EA: 1

Minor debris noted around the drainage areas. Drainage areas should always be kept clear for proper drainage of the roof.

# Inspection Report

Department of Enterprise Services, Tumwater, WA

Work Order #: 35198

Inspection Date: 10/2/2015 10:30:00 AM



Condition: 026 - Staining  
Severity: 1 - Monitor  
Qty: SF: 2 LF: 8 EA: 2

Membrane is stained from natural weathering.



Condition: EG - 212 - New Equipment  
Severity: 1 - Monitor  
Qty: SF: 3 LF: 12 EA: 3

New Equipment, perimeter tie-in at new membrane flashings appear to have been stripped in using PS tape & sealant instead of heat welding the details?





# **INDUSTRIAL** **Hydraulics Inc.**

**Aberdeen**      **Chehalis**      **Tumwater**  
**(360) 533-7070**      **(360) 748-7878**      **(360) 956-7070**

---

**Ehm Architecture / Washington State Department of Enterprise Services**  
Assessment and recommendations for dock leveler hydraulic systems at  
Department of Printing and Imaging

**To:** Randal Ehm

**From:** Brady Sweeney

**Phone:** Office 206-763-1481 Ext 306  
Cell 206-719-0771

**Email:** [randal@ehmarch.com](mailto:randal@ehmarch.com)

**Date:** 5-10-16

---

**Leveler #1:** This system had an electrical problem when we were on site so we were unable to run it to get a look at the system under the platform. From the looks of the platform and the concrete, this system is an original and has not been updated. We are unable to provide an assessment at this time.

**Leveler #2:** This system also seems to be original. When we ran the system the pump was cavitating at the end of the stroke. We observed oil on the exterior of the tube for the main lift cylinder which indicates a leak that has diminished the oil level in the reservoir, causing the cavitation. In order to remedy this leak the main cylinder would need to be removed and brought into the shop to be rebuilt. The rebuild of the cylinder can vary greatly from a basic hone, polish and repack to a more extensive rebuild including machining new parts as needed. This system also lacks a brace to hold the platform up during maintenance.

**Estimate For Repair    \$3200.00**

**Includes**

Remove, basic rebuild, and reinstall cylinder

Fabricating support brace

Basic cleaning and inspection, and top-off hydraulic fluid

\*Any repairs or machining of parts for the main cylinder beyond a basic reseal would have to be quoted upon tear down. Any worn parts found upon further inspection would be quoted at that time (including bad hoses and fittings)

**Leveler #3:** This system looks newer than the first two and looks to be in good working order upon the initial inspection.

**Estimate For Repair \$400.00**

**Includes**

Basic cleaning and inspection

\*Any worn parts found upon further inspection would be quoted at that time (including bad hoses and fittings).

**Leveler #4:** This system also looks newer than the first two. Upon initial inspection there did not seem to be any apparent leaks. The main cylinder lifts the platform fine but the small cylinder to lift the lip does not extend. The lip cylinder is controlled by a sequence valve that is supposed to open when the main cylinder reaches the end of its stroke and the set pressure is reached. The lack of this function working could be caused by something as simple as the pressure setting being wrong on the sequence valve or by a bad sequence cartridge. We would need to trouble shoot the system further to find the cause of the problem.

**Estimate For Repair \$800.00**

**Includes**

Basic cleaning and inspection

Trouble shoot issue with lip cylinder and adjust sequence valve

\*If a bad sequence valve is found upon trouble shooting new parts would be quoted at that time. Any worn parts found upon further inspection would be quoted at that time (including bad hoses and fittings).

**Comments:** For the purpose of numbering, leveler #1 is the northernmost and #4 is the southernmost. Leveler #2 is the only one being used at this time so it should be the highest priority for repair.

As stated above these are estimates and only include the scope of work laid out. Any further repairs would be quoted upon further inspection.

---

***"Service is our most important product"***



## Reactions on the building by the cooling tower

### I/ Loads on the cooling tower:

#### 1. Dead load:

Total weight of the structure:  $D \approx 8,000$  lbs

#### 2. Seismic load: Chapter 13 ASCE 7-10

Importance factor:  $I_p = 1.0$

Amplification factor:  $O_p = 2.5$

Response mod. factor:  $R_p = 3.0$

$$\frac{z}{h} = 1$$

$$S_{ps} = 0.869$$

$$W_p = 8,000 \text{ lbs}$$

$$\begin{aligned} \Rightarrow F_p &= \frac{0.4 a_p S_{ps} W_p}{\left(\frac{R_p}{I_p}\right)} \left(1 + 2 \frac{z}{h}\right) \\ &= \frac{0.4 \cdot 2.5 \cdot 0.869 \cdot 8,000}{3.0} (1 + 2) = \underline{\underline{6952 \text{ lbs}}} \end{aligned}$$

$$F_{pmax} = 1.6 S_{ps} I_p W_p = 1.6 \cdot 0.869 \cdot 1.0 \cdot 8,000 = 11,123.2 \text{ lbs}$$

$$F_{pmin} = 0.3 S_{ps} I_p W_p = 0.3 \cdot 0.869 \cdot 1.0 \cdot 8,000 = 2,085.6 \text{ lbs}$$

$$\begin{aligned} \text{Vertical component: } F_v &= \pm 0.2 S_{ps} W_p = \pm 0.2 \cdot 0.869 \cdot 8,000 \\ &= \underline{\underline{\pm 1,390.4 \text{ lbs}}} \end{aligned}$$



# USGS Design Maps Summary Report

## User-Specified Input

**Report Title** Modular Building Assessment Project

Thu April 28, 2016 17:42:02 UTC

**Building Code Reference Document** 2012 International Building Code  
(which utilizes USGS hazard data available in 2008)

**Site Coordinates** 46.97832°N, 122.9131°W

**Site Soil Classification** Site Class D - "Stiff Soil"

**Risk Category** I/II/III



## USGS-Provided Output

$S_s = 1.303 \text{ g}$

$S_{MS} = 1.303 \text{ g}$

$S_{DS} = 0.869 \text{ g}$


$S_1 = 0.540 \text{ g}$

$S_{M1} = 0.809 \text{ g}$


$S_{D1} = 0.540 \text{ g}$

For information on how the  $S_s$  and  $S_1$  values above have been calculated from probabilistic (risk-targeted) and deterministic ground motions in the direction of maximum horizontal response, please return to the application and select the "2009 NEHRP" building code reference document.

**MCE<sub>R</sub> Response Spectrum**



**Design Response Spectrum**



Although this information is a product of the U.S. Geological Survey, we provide no warranty, expressed or implied, as to the accuracy of the data contained therein. This tool is not a substitute for technical subject-matter knowledge.

3. Wind load: Chapter 25 Section 29.5 ASCE 7-10

Risk Category: II (of the building)

$$\Rightarrow V_{ult} = 110 \text{ mph}$$

$$K_d = 0.85$$

Exposure Category C

$$K_{zt} = 1.0$$

$$G = 0.85$$

$$K_e = 0.96 \text{ (h=27.5 ft)}$$

$$\left. \begin{array}{l} K_e K_{zt} K_d V^2 \\ = 0.96 \cdot 1.0 \cdot 0.85 \cdot 110^2 \\ = 25.3 \text{ psf} \end{array} \right\} q_e$$

$$G C_r = 1.9$$

$\Rightarrow$  Wind pressure on the cooling tower:

$$\text{horizontal: } p_h = q_e (G C_r) = \underline{48 \text{ psf}}$$

$$\text{uplift: } p_{ul} = q_e (G C_r) = \underline{48 \text{ psf}}$$

$$A_{f N-S} = \frac{(140'' \times 86'')}{12^2} = 83.6 \text{ ft}^2$$

$$A_{f E-W} = \frac{(140'' \times 108'')}{12^2} = 105 \text{ ft}^2$$

$$A_r = \frac{(86'' \times 108'')}{12^2} = 64.5 \text{ ft}^2$$

$$\Rightarrow F_{h N-S} = 48 \cdot 83.6 = \underline{4013 \text{ (lbs)}}$$

$$F_{h E-W} = 48 \cdot 105 = \underline{5040 \text{ (lbs)}}$$

$$F_{vL} = 48 \cdot 64.5 = \underline{3096 \text{ (lbs)}}$$



[ASCE 7 Windspeed](#)
[ASCE 7 Ground Snow Load](#)
[Related Resources](#)
[Sponsors](#)
[About ATC](#)
[Contact](#)


## Search Results

**Query Date:** Thu Apr 28 2016  
**Latitude:** 46.9791  
**Longitude:** -122.9125

**ASCE 7-10 Windspeeds  
 (3-sec peak gust in mph\*):**

**Risk Category I:** 100  
**Risk Category II:** 110  
**Risk Category III-IV:** 115  
**MRI\*\* 10-Year:** 72  
**MRI\*\* 25-Year:** 79  
**MRI\*\* 50-Year:** 85  
**MRI\*\* 100-Year:** 91

**ASCE 7-05 Windspeed:**  
 85 (3-sec peak gust in mph)  
**ASCE 7-93 Windspeed:**  
 75 (fastest mile in mph)



\*Miles per hour  
 \*\*Mean Recurrence Interval

Users should consult with local building officials  
 to determine if there are community-specific wind speed  
 requirements that govern.



[Print your results](#)

### WINDSPEED WEBSITE DISCLAIMER

While the information presented on this website is believed to be correct, ATC and its sponsors and contributors assume no responsibility or liability for its accuracy. The material presented in the windspeed report should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. ATC does not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the windspeed report provided by this website. Users of the information from this website assume all liability arising from such use. Use of the output of this website does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site described by latitude/longitude location in the windspeed load report.



## II/ Structural Analysis:

### Load Combinations:

1.  $1.4 D$
2.  $(1.2 + 0.2 S_{ps}) D + E$
3.  $(0.9 - 0.2 S_{ps}) D + E$
4.  $0.9 D + W$


### Vertical load analysis:

Based on the configuration of the supporting structure for the cooling tower, all the vertical load will be resisted by the round pipes @ the 4 corners.

Assume a vertical force  $P$  acting on the structure, @ the base of each round pipe, the reaction is  $R = \frac{P}{4}$

### Lateral load analysis:

Based on the configuration of the supporting structure for the cooling tower, when a seismic force is applied to the tower, the whole structure will rotate about one of the steel pipe.



Assume a lateral force  $V$  acting @ the centroid of the cooling tower. The shear force on each steel pipe is

$$R = \frac{V}{4}$$

Tensile force @ base of the pipe =  
compressive force @ base of the truss sp =

$$R = \frac{V \cdot d}{2 \cdot e}$$





Combination no 2:  $(1.2 + 0.2 Sps) D + \pm 2.0 Q_E$

Shear force @ the base of the pipe:

$$S = \frac{V}{4} = \frac{6,952}{4} = \underline{1,738 \text{ (lbs)}}$$

★ Combination no. 3:  $(0.9 - 0.2 Sps) D + \pm 2.0 Q_E$

$$\Rightarrow P = (0.9 - 0.2 \cdot 0.869) \cdot 8,000 = 5766.4 \text{ lbs}$$

$$V = F_p = 6,952 \text{ lbs}$$

$\Rightarrow$  Compression force @ the base of the truss supports:

$$C = 0.382 \cdot V = \underline{2,556 \text{ (lbs)}}$$

Tension force @ the base of the pipe.

$$T = -\frac{P}{4} + 0.382 V = -\frac{5766.4}{4} + 0.382 \cdot 6,952 = \underline{1214 \text{ (lbs)}}$$

Shear force @ the base of the pipe:

$$S = \frac{V}{4} = \underline{1,738 \text{ (lbs)}}$$

★ Combination no. 4:  $0.9 D + 1.0 W$

$$P = 0.9 \cdot 8,000 - 3096 = 4104 \text{ (lbs)}$$

$$V = 5040 \text{ (lbs)}$$

$\Rightarrow$  Compression force @ the base of the truss supports:

$$C = 0.382 \cdot V = 0.382 \cdot 5040 = \underline{1925.3 \text{ (lbs)}}$$

Tension force @ the base of the pipe:

$$T = -\frac{P}{4} + 0.382 V = -\frac{4104}{4} + 0.382 \cdot 5,040 = \underline{899.3 \text{ (lbs)}}$$

Shear force @ the base of the pipe:

$$S = \frac{V}{4} = \frac{5040}{4} = \underline{1260 \text{ (lbs)}}$$

## Summary:

- Steel pipes:

Max shear :  $V_{max} = 1,738$  lbs (EQ controls)

Max tension :  $T_{max} = 1,214$  lbs (EQ controls)

Max compression :  $C_{max} = 2,800$  lbs (DL)

- Supports of the truss:

Max compression :  $C_{max} = 2,656$  lbs (EQ controls)



## Mezzanine Capacity evaluation

To evaluate the capacity of the mezzanine, we will evaluate each structural member one by one, and which one has the lowest capacity for Live load will be the controlling capacity of the whole structure:

1. Concrete on Metal deck.
2. Open web steel joist.
3. Steel beam (interior) W 24 x 84
4. Column.
5. Steel beam (Edge) W 21 x 50

1. Concrete on metal deck:

2  $\frac{1}{2}$ " normal weight concrete topping w / W2.9XW.2.9-6X6

W.W.F Reinf. over type "13-30"  $1\frac{1}{2}$ " deep 18 gauge metal deck.

spanning 4'-0"

$$\left. \begin{array}{l} \text{Deck weight} = 2.76 \text{ psf} \\ \text{Concrete weight} = 36.25 \text{ psf} \end{array} \right\} \text{total deck weight} = 39 \text{ psf}$$

From ASCSD page 113:

Maximum Superimpose load for this deck is:

$$1.6 L_{\text{allowed}} = 1358 \text{ psf}$$

$$\Rightarrow L_{\text{allowed}} = 849 \text{ psf}$$

So, the capacity of the deck is 849 psf ✓



TABLE OF CONTENTS



**BH-36 Composite Deck 4.4**

**4" Total Slab Depth**

**Normal Weight Concrete (145 pcf)**

Concrete Volume 0.931 yd<sup>3</sup>/100ft<sup>2</sup>



Maximum Unshored Span (in)

Gage	Single	Double	Triple	Gage	Single	Double	Triple
22	6' - 3"	6' - 8"	7' - 5"	18	8' - 6"	10' - 1"	10' - 8"
20	7' - 6"	8' - 2"	8' - 10"	16	9' - 2"	11' - 4"	11' - 4"

GA	Vertical Load Span (in)	ASD & LRFD - Superimposed Load, W (psf)															
		5'-0"	5'-6"	6'-0"	6'-6"	7'-0"	7'-6"	8'-0"	8'-6"	9'-0"	9'-6"	10'-0"	10'-6"	11'-0"	11'-6"	12'-0"	
22	ASD, W/Ω	663	543	451	380	324	279	241	211	185	163	144	128	114	102	91	
	LRFD, φW	1060	868	722	609	518	446	386	337	295	261	231	205	183	163	146	
	L/360	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	<b>LRFD - Diaphragm Shear, φS<sub>n</sub> (plf / ft) 36/4 Attachment Pattern</b>																
	Arc Spot Weld 1/2" Effective Dia	3124	3061	3008	2979	2939	2905	2875	2848	2825	2815	2795	2777	2761	2747	2733	
	PAF Base Steel ≥ .25"	2809	2774	2745	2736	2714	2695	2678	2663	2649	2649	2637	2627	2618	2609	2602	
	PAF Base Steel ≥ 0.125"	2784	2752	2724	2717	2696	2678	2662	2648	2636	2636	2625	2615	2607	2599	2591	
	#12 Screw Base Steel ≥ .0385"	2762	2731	2705	2700	2680	2663	2648	2635	2623	2624	2614	2605	2596	2589	2582	
	Concrete + Deck = 38.2 psf (I <sub>c</sub> +I <sub>d</sub> )/2 = 39.42 in <sup>4</sup> /ft					I <sub>c</sub> = 25.4 in <sup>4</sup> /ft I <sub>d</sub> = 53.4 in <sup>4</sup> /ft					M <sub>no</sub> /Ω = 27.1 kip-in/ft φM <sub>no</sub> = 41.5 kip-in/ft			V <sub>n</sub> /Ω = 2.26 kip/ft φV <sub>n</sub> = 3.40 kip/ft			

GA	Vertical Load Span (in)	ASD & LRFD - Superimposed Load, W (psf)															
		5'-0"	5'-6"	6'-0"	6'-6"	7'-0"	7'-6"	8'-0"	8'-6"	9'-0"	9'-6"	10'-0"	10'-6"	11'-0"	11'-6"	12'-0"	
20	ASD, W/Ω	780	640	533	450	384	331	287	251	221	195	173	155	138	124	112	
	LRFD, φW	1248	1024	853	720	614	529	459	402	353	312	277	247	221	198	179	
	L/360	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	<b>LRFD - Diaphragm Shear, φS<sub>n</sub> (plf / ft) 36/4 Attachment Pattern</b>																
	Arc Spot Weld 1/2" Effective Dia	3273	3195	3130	3099	3050	3008	2971	2939	2910	2900	2876	2854	2834	2816	2799	
	PAF Base Steel ≥ .25"	2888	2845	2810	2803	2776	2752	2731	2712	2696	2698	2684	2671	2659	2649	2639	
	PAF Base Steel ≥ 0.125"	2859	2819	2785	2781	2755	2732	2713	2695	2680	2682	2669	2657	2646	2636	2627	
	#12 Screw Base Steel ≥ .0385"	2834	2796	2765	2762	2737	2716	2697	2681	2666	2669	2657	2645	2635	2625	2617	
	Concrete + Deck = 38.5 psf (I <sub>c</sub> +I <sub>d</sub> )/2 = 42 in <sup>4</sup> /ft					I <sub>c</sub> = 28.8 in <sup>4</sup> /ft I <sub>d</sub> = 55.2 in <sup>4</sup> /ft					M <sub>no</sub> /Ω = 31.7 kip-in/ft φM <sub>no</sub> = 48.5 kip-in/ft			V <sub>n</sub> /Ω = 2.26 kip/ft φV <sub>n</sub> = 3.40 kip/ft			

GA	Vertical Load Span (in)	ASD & LRFD - Superimposed Load, W (psf)															
		5'-0"	5'-6"	6'-0"	6'-6"	7'-0"	7'-6"	8'-0"	8'-6"	9'-0"	9'-6"	10'-0"	10'-6"	11'-0"	11'-6"	12'-0"	
18	ASD, W/Ω	906	814	680	575	491	424	369	324	286	253	217	187	163	143	126	
	LRFD, φW	1358	1235	1087	919	786	679	591	518	457	405	361	323	290	262	237	
	L/360	-	-	-	-	-	-	-	-	-	253	217	187	163	143	126	
	<b>LRFD - Diaphragm Shear, φS<sub>n</sub> (plf / ft) 36/4 Attachment Pattern</b>																
	Arc Spot Weld 1/2" Effective Dia	3581	3474	3385	3352	3284	3226	3174	3129	3089	3082	3048	3017	2990	2964	2941	
	PAF Base Steel ≥ .25"	3053	2995	2945	2946	2907	2874	2845	2819	2796	2804	2784	2766	2750	2735	2721	
	PAF Base Steel ≥ 0.125"	3015	2960	2913	2916	2880	2848	2821	2796	2774	2784	2765	2748	2732	2718	2705	
	#12 Screw Base Steel ≥ .0385"	2988	2935	2891	2896	2861	2831	2804	2780	2760	2770	2752	2735	2720	2706	2694	
	Concrete + Deck = 39.8 psf (I <sub>c</sub> +I <sub>d</sub> )/2 = 46.4 in <sup>4</sup> /ft					I <sub>c</sub> = 34.6 in <sup>4</sup> /ft I <sub>d</sub> = 58.2 in <sup>4</sup> /ft					M <sub>no</sub> /Ω = 40.0 kip-in/ft φM <sub>no</sub> = 61.3 kip-in/ft			V <sub>n</sub> /Ω = 2.26 kip/ft φV <sub>n</sub> = 3.40 kip/ft			


GA	Vertical Load Span (in)	ASD & LRFD - Superimposed Load, W (psf)															
		5'-0"	5'-6"	6'-0"	6'-6"	7'-0"	7'-6"	8'-0"	8'-6"	9'-0"	9'-6"	10'-0"	10'-6"	11'-0"	11'-6"	12'-0"	
16	ASD, W/Ω	906	823	755	695	595	514	448	384	323	275	236	204	177	155	136	
	LRFD, φW	1358	1235	1132	1045	952	823	717	630	557	495	442	396	357	323	292	
	L/360	-	-	-	-	-	-	-	384	323	275	236	204	177	155	136	
	<b>LRFD - Diaphragm Shear, φS<sub>n</sub> (plf / ft) 36/4 Attachment Pattern</b>																
	Arc Spot Weld 1/2" Effective Dia	3910	3772	3657	3626	3538	3461	3395	3336	3283	3282	3237	3197	3161	3127	3097	
	PAF Base Steel ≥ .25"	3230	3154	3091	3103	3053	3009	2970	2936	2906	2924	2898	2874	2852	2832	2814	
	PAF Base Steel ≥ 0.125"	3157	3087	3029	3046	3000	2959	2924	2893	2865	2885	2861	2839	2818	2800	2783	
	#12 Screw Base Steel ≥ .0385"	3169	3100	3042	3059	3012	2972	2936	2905	2877	2898	2873	2851	2830	2812	2795	
	Concrete + Deck = 39.2 psf (I <sub>c</sub> +I <sub>d</sub> )/2 = 50.4 in <sup>4</sup> /ft					I <sub>c</sub> = 39.8 in <sup>4</sup> /ft I <sub>d</sub> = 61.1 in <sup>4</sup> /ft					M <sub>no</sub> /Ω = 48.0 kip-in/ft φM <sub>no</sub> = 73.5 kip-in/ft			V <sub>n</sub> /Ω = 2.26 kip/ft φV <sub>n</sub> = 3.40 kip/ft			

All Gages	LRFD - Diaphragm Shear, φS <sub>n</sub> (plf / ft) for all vertical load spans, WWF Designation or Area of Steel per foot width					
	3/4" Welded Shear Studs	6x6 W1.4xW1.4	6x6 W2.9xW2.9	6x6 W4.0xW4.0	4x4 W4xW4	4x4 W6xW6
	A <sub>s</sub> = 0.028 in <sup>2</sup> /ft	A <sub>s</sub> = 0.058 in <sup>2</sup> /ft	A <sub>s</sub> = 0.080 in <sup>2</sup> /ft	A <sub>s</sub> = 0.120 in <sup>2</sup> /ft	A <sub>s</sub> = 0.180 in <sup>2</sup> /ft	
6 in o.c.	3700	5050	6040	7840	10540	
12 in o.c.	3700	5050	6040	7840	10540	
18 in o.c.	3700	5050	6040	7840	8790	

B PANELS

## 2. Open-web Steel joist:

28 LH 12 steel joist @ 4'-0" O.C  
spanning 40'



Approximate weight 27 plf

$$\Rightarrow D = 27 \text{ plf} + 39 \text{ psf} \cdot 4' = 143 \text{ plf}$$

$$1.2D = 171.6 \text{ plf}$$

Strength capacity:  $1.6L = 1105 - 171.6 = 933.4 \text{ (plf)}$   
(SJI page 113)

$$\Rightarrow L_{\text{allowed}} = \frac{933.4}{1.6} = 583 \text{ (plf)}$$

$$\Rightarrow W_{LL \text{ allowed}} = \frac{583}{4} = 145 \text{ psf for 50ksi steel}$$
  
$$= 104 \text{ psf for 36ksi steel}$$

Deflection capacity:  $L_{\text{allowd}} = 408 \cdot \frac{360}{240} - 143 = 469 \text{ (plf)}$

$(\Delta \leq L/240)$   
(for D+L)

$$\Rightarrow W_{LL \text{ allowed}} = \frac{469}{4} = 117 \text{ psf}$$

$(\Delta \leq L/360)$   
'for L only)

$$L_{\text{demand}} = 408 \text{ plf}$$

$$\Rightarrow W_{LL \text{ allowed}} = \frac{408}{4} = 102 \text{ psf controls}$$

So the capacity of the steel joist is 102 psf

# STANDARD LRFD LOAD TABLE

## LONGSPAN STEEL JOISTS, LH-SERIES

Based on a 50 ksi Maximum Yield Strength  
Adopted by the Steel Joist Institute May 1, 2000  
Revised to May 18, 2010 – Effective December 31, 2010

The **BLACK** figures in the Load Table give the TOTAL safe factored uniformly distributed load-carrying capacities, in pounds per linear foot, of **LRFD** LH-Series Steel Joists.

The approximate joist weights, in pounds per linear foot, given in the Load Table may be added to the other building weights to determine the unfactored DEAD load. In all cases the factored DEAD load, including the joist self-weight, must be deducted from the TOTAL load to determine the factored LIVE load. The approximate joist weights do not include accessories.

The **RED** figures in the Load Table represent the unfactored, uniform load, in pounds per linear foot, which will produce an approximate joist deflection of 1/360 of the span. This load can be linearly prorated to obtain the unfactored, uniform load for supplementary deflection criteria (i.e. an unfactored uniform load which will produce a joist deflection of 1/240 of the span may be obtained by multiplying the **RED** figures by 360/240). In no case shall the prorated, unfactored load exceed the unfactored TOTAL load-carrying capacity of the joist as given in the Standard **ASD** Load Table for Longspan Steel Joists, LH-Series.

The Load Table applies to joists with either parallel chords or pitched top chords. Joists can have a top chord pitch up to 1/2 inch per foot. If the pitch exceeds this limit, the Load Table does not apply. When top chords are pitched, the load-carrying capacities are determined by the nominal depth of the joists at the center of the span. Sloped parallel-chord joists shall use span as defined by the length along the slope.

Where the joist span is in the **RED SHADED** area of the Load Table, the row of bridging nearest the mid span shall be diagonal bridging with bolted connections at chords and intersections. Hoisting cables shall not be released until this row of bolted diagonal bridging is completely installed. The **RED SHADED** area extends up through 60'-0".

Where the joist span is in the **BLUE SHADED** area of the Load Table, all rows of bridging shall be diagonal bridging with bolted connections at chords and intersections. Hoisting cables shall not be released until the two rows of bridging nearest the third points are completely installed. The **BLUE SHADED** area starts after 60'-0" and extends up through 100'-0".

The approximate gross moment of inertia (not adjusted for shear deformation), in inches<sup>4</sup>, of a standard joist listed in the Load Table may be determined as follows:

$$I_g = 26.767(W)(L^3)(10^{-6}), \text{ where } W = \text{RED figure in the Load Table, and} \\ L = (\text{span} - 0.33) \text{ in feet.}$$

Loads for span increments not explicitly given in the Load Table may be determined using linear interpolation between the load values given in adjacent span columns.

\*The safe factored uniform load for the spans shown in the SAFE LOAD Column is equal to (SAFE LOAD) / (span). The TOTAL safe factored uniformly distributed load-carrying capacity, for spans less than those shown in the SAFE LOAD Column are given in the MAX LOAD Column.

To solve for an unfactored RED figure for spans shown in the SAFE LOAD Column (or lesser spans), multiply the unfactored RED figure of the shortest span shown in the Load Table by (the shortest span shown in the Load Table – 0.33 feet)<sup>2</sup> and divide by (the actual span – 0.33 feet)<sup>2</sup>. In no case shall the calculated unfactored load exceed the unfactored TOTAL load-carrying capacity of the joist as determined from the Standard **ASD** Load Table for Longspan Steel Joists, LH-Series.







STANDARD LOAD TABLE FOR LONGSPAN STEEL JOISTS, LH SERIES

Based on a 50 ksi Maximum Yield Strength - Loads Shown in Pounds Per Linear Foot (plf)

Joist Designation	Approx. Wt in Lbs. Per Linear Ft. (Joists only)	Depth in inches	Max Load (plf) < 29	SAFELOAD* in Lbs. Between	SPAN IN FEET																	
					29-33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48		
					34-41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56		
24LH03	11	24	601	17430	513	508	504	484	460	439	418	400	382	366	351	336	322	310	298			
24LH04	12	24	737	21360	628	597	568	540	514	490	468	447	427	409	393	376	361	346	333			
24LH05	13	24	789	22890	673	669	660	628	598	570	544	520	496	475	456	436	420	403	387			
24LH06	16	24	1061	30780	906	868	832	795	756	720	685	655	625	598	571	545	522	501	480			
24LH07	17	24	1166	33810	997	957	919	882	847	811	774	736	702	669	639	610	583	558	535			
24LH08	18	24	1243	36060	1060	1015	973	933	895	858	817	780	745	712	682	650	625	600	576			
24LH09	21	24	1464	42450	1248	1212	1171	1146	1098	1044	994	948	903	861	822	786	751	720	690			
24LH10	23	24	1547	44850	1323	1284	1248	1213	1182	1152	1105	1053	1002	955	912	873	834	799	766			
24LH11	25	24	1630	47280	1390	1350	1312	1276	1243	1210	1180	1152	1101	1051	1006	963	924	885	850			
28LH05	13	28	623	21180	505	484	465	445	429	414	397	382	367	355	342	330	319	309	298			
28LH06	16	28	828	28140	672	643	618	592	568	546	525	505	486	469	451	436	421	406	393			
28LH07	17	28	934	31770	757	726	696	667	640	615	591	568	547	528	508	490	474	457	442			
28LH08	18	28	1001	34020	810	775	744	712	684	657	630	604	580	556	535	516	496	478	462			
28LH09	21	28	1232	41880	1000	958	918	879	844	810	778	748	721	694	669	645	622	601	580			
28LH10	23	28	1347	45810	1093	1056	1018	976	937	900	864	831	799	769	742	715	690	666	643			
28LH11	25	28	1445	49140	1170	1143	1104	1066	1023	982	943	907	873	841	810	781	753	727	702			
28LH12	27	28	1587	53970	1285	1255	1227	1200	1173	1149	1108	1063	1023	984	948	913	880	849	819			
28LH13	30	28	1654	56250	1342	1311	1281	1252	1224	1198	1173	1149	1126	1083	1041	1002	964	930	897			
32LH06	14	32	647	25230	507	469	472	455	441	426	412	399	385	373	363	351	340	330	321			
32LH07	16	32	728	28380	568	549	529	511	493	477	462	447	432	418	406	393	381	370	360			
32LH08	17	32	790	30810	616	595	574	553	535	517	499	483	468	453	439	426	412	400	388			
32LH09	21	32	992	38670	774	747	720	694	670	648	627	606	586	568	550	534	517	502	487			
32LH10	21	32	1096	42750	856	825	796	766	742	717	693	667	645	624	603	583	564	546	529			
32LH11	24	32	1201	46830	937	903	870	840	811	783	757	732	709	687	664	643	624	604	585			
32LH12	27	32	1409	54960	1101	1068	1032	996	961	928	897	867	838	811	786	762	738	715	694			
32LH13	30	32	1572	61320	1225	1201	1177	1156	1113	1072	1035	999	964	931	900	871	843	816	790			
32LH14	33	32	1618	63120	1264	1239	1215	1192	1170	1149	1107	1069	1032	997	964	933	903	874	846			
32LH15	35	32	1673	65250	1305	1279	1255	1231	1207	1186	1164	1144	1125	1087	1051	1017	984	952	924			
36LH07	16	36	590	25350	438	424	411	399	387	376	365	355	345	336	327	318	310	301	294			
36LH08	18	36	649	27900	481	466	453	439	426	414	402	390	379	369	358	349	340	331	322			
36LH09	21	36	832	35760	616	597	579	561	544	528	513	499	484	471	459	445	433	423	412			
36LH10	21	36	916	39390	681	660	639	619	601	583	567	550	535	520	507	492	480	466	454			
36LH11	23	36	1000	42990	742	720	697	676	657	637	618	601	583	567	552	537	522	508	495			
36LH12	25	36	1197	51450	889	862	835	810	784	762	739	717	696	675	655	636	618	600	583			
36LH13	30	36	1407	60510	1045	1012	981	951	922	894	868	843	819	796	774	753	732	712	694			
36LH14	35	36	1551	66890	1152	1132	1093	1059	1024	991	961	931	903	876	850	826	802	780	757			
36LH15	36	36	1635	70320	1213	1192	1171	1153	1115	1081	1047	1015	984	955	927	900	874	850	825			



# STANDARD ASD LOAD TABLE

## LONGSPAN STEEL JOISTS, LH-SERIES

Based on a 50 ksi Maximum Yield Strength  
Adopted by the Steel Joist Institute May 25, 1983  
Revised to May 18, 2010 – Effective December 31, 2010

The **BLACK** figures in the Load Table give the TOTAL safe uniformly distributed load-carrying capacities, in pounds per linear foot, of **ASD LH-Series Steel Joists**.

The approximate joist weights, in pounds per linear foot, given in the Load Table may be added to the other building weights to determine the DEAD load. In all cases the DEAD load, including the joist self-weight, must be deducted from the TOTAL load to determine the LIVE load. The approximate joist weights do not include accessories.

The **RED** figures in the Load Table represent the uniform load, in pounds per linear foot, which will produce an approximate joist deflection of 1/360 of the span. This load can be linearly prorated to obtain the uniform load for supplementary deflection criteria (i.e. a uniform load that will produce a joist deflection of 1/240 of the span may be obtained by multiplying the **RED** figures by 360/240). In no case shall the prorated load exceed the TOTAL load-carrying capacity of the joist.

The Load Table applies to joists with either parallel chords or pitched top chords. Joists can have a top chord pitch up to 1/2 inch per foot. If the pitch exceeds this limit, the Load Table does not apply. When top chords are pitched, the load-carrying capacities are determined by the nominal depth of the joists at the center of the span. Sloped parallel-chord joists shall use span as defined by the length along the slope.

Where the joist span is in the **RED SHADED** area of the Load Table, the row of bridging nearest the mid span shall be diagonal bridging with bolted connections at chords and intersections. Hoisting cables shall not be released until this row of bolted diagonal bridging is completely installed. The **RED SHADED** area extends up through 60'-0".

Where the joist span is in the **BLUE SHADED** area of the Load Table, all rows of bridging shall be diagonal bridging with bolted connections at chords and intersections. Hoisting cables shall not be released until the two rows of bridging nearest the third points are completely installed. The **BLUE SHADED** area starts after 60'-0" and extends up through 100'-0".

The approximate gross moment of inertia (not adjusted for shear deformation), in inches<sup>4</sup>, of a standard joist listed in the Load Table may be determined as follows:

$$I_j = 26.767(W)(L^3)(10^{-6}), \text{ where } W = \text{RED figure in the Load Table, and}$$
$$L = (\text{span} - 0.33) \text{ in feet.}$$

Loads for span increments not explicitly given in the Load Table may be determined using linear interpolation between the load values given in adjacent span columns.

\*The safe uniform load for the spans shown in the SAFE LOAD Column is equal to (SAFE LOAD) / (span). The TOTAL safe uniformly distributed load-carrying capacity, for spans less than those shown in the SAFE LOAD Column are given in the MAX LOAD Column.

To solve for a **RED** figure for spans shown in the SAFE LOAD Column (or lesser spans), multiply the RED figure of the shortest span shown in the Load Table by (the shortest span shown in the Load Table - 0.33 feet)<sup>2</sup> and divide by (the actual span - 0.33 feet)<sup>2</sup>. In no case shall the calculated load exceed the TOTAL load-carrying capacity of the joist.






**STANDARD LOAD TABLE FOR LONGSPAN STEEL JOISTS, LH-SERIES**  
 Based on a 50 ksi Maximum Yield Strength - Loads Shown in Pounds Per Linear Foot (plf)

Joist Designation	Approx. Wt in Lbs. Per Linear Ft (Joists only)	Depth in inches	Max Load (plf) < 29	SAFELOAD* in Lbs. Between	SPAN IN FEET																
					29-33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	
					34-41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	
24LH03	11	24	401	11620	342	339	336	323	307	293	279	267	255	244	234	224	215	207	199		
24LH04	12	24	491	14240	419	398	379	360	343	327	312	298	285	273	262	251	241	231	222		
24LH05	13	24	526	15260	449	446	440	419	399	380	363	347	331	317	304	291	280	269	256		
24LH06	16	24	708	20520	604	579	555	530	504	480	457	437	417	399	381	364	348	334	320		
24LH07	17	24	777	22540	665	638	613	588	565	541	516	491	468	446	426	407	389	373	357		
24LH08	18	24	829	24040	707	677	649	622	597	572	545	520	497	475	455	435	417	400	384		
24LH09	21	24	976	28300	832	808	785	764	731	696	663	632	602	574	548	524	501	480	460		
24LH10	23	24	1031	29900	882	856	832	809	788	768	737	702	668	637	608	582	556	533	511		
24LH11	25	24	1087	31520	927	900	875	851	829	807	787	768	734	701	671	642	616	590	567		
			< 34	34-41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56		
28LH05	13	28	415	14120	337	323	310	297	286	275	265	255	245	237	228	220	213	206	199		
28LH06	16	28	552	18760	448	429	412	395	379	364	350	337	324	313	301	291	281	271	262		
28LH07	17	28	623	21180	505	484	464	445	427	410	394	379	365	352	339	327	316	305	295		
28LH08	18	28	667	22680	540	517	496	475	456	438	420	403	387	371	357	344	331	319	306		
28LH09	21	28	821	27920	667	639	612	586	563	540	519	499	481	463	446	430	415	401	387		
28LH10	23	28	898	30540	729	704	679	651	625	600	576	554	533	513	495	477	460	444	429		
28LH11	25	28	964	32760	780	762	736	711	682	655	629	605	582	561	540	521	502	485	468		
28LH12	27	28	1058	35980	857	837	818	800	782	766	737	709	682	656	632	609	587	566	546		
28LH13	30	28	1103	37500	895	874	854	835	816	799	782	766	751	722	694	668	643	620	598		
			< 39	39-46	47-49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	
32LH06	14	32	431	16820	358	326	315	304	294	284	275	266	257	249	242	234	227	220	214		
32LH07	16	32	485	18920	379	366	353	341	329	318	308	298	288	279	271	262	254	247	240		
32LH08	17	32	527	20540	411	397	383	369	357	345	333	322	312	302	293	284	275	267	259		
32LH09	21	32	661	25780	516	498	480	463	447	432	418	404	391	379	367	356	345	335	325		
32LH10	21	32	731	28500	571	550	531	512	495	478	462	445	430	416	402	389	372	364	353		
32LH11	24	32	801	31220	625	602	580	560	541	522	505	488	473	458	443	429	416	403	390		
32LH12	27	32	939	36640	734	712	688	664	641	619	598	578	559	541	524	508	492	477	463		
32LH13	30	32	1048	40880	817	801	785	771	742	715	690	666	643	621	600	581	562	544	527		
32LH14	33	32	1079	42080	843	826	810	795	780	766	738	713	688	665	643	622	602	583	564		
32LH15	35	32	1115	43500	870	853	837	821	805	791	776	763	750	725	701	678	656	635	616		
			< 43	43-46	47-56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72
36LH07	16	36	393	16900	292	283	274	266	258	251	244	237	230	224	218	212	207	201	196		
36LH08	18	36	433	18600	321	311	302	293	284	276	268	260	253	246	239	233	227	221	215		
36LH09	21	36	554	23840	411	398	386	374	363	352	342	333	323	314	306	297	289	282	275		
36LH10	21	36	611	26260	454	440	426	414	401	389	378	367	357	347	338	328	320	311	303		
36LH11	23	36	667	28660	495	480	465	451	438	425	412	401	389	378	368	358	348	339	330		
36LH12	25	36	798	34300	593	575	557	540	523	508	493	478	464	450	437	424	412	400	389		
36LH13	30	36	938	40340	697	678	654	634	615	596	579	562	546	531	516	502	488	475	463		
36LH14	36	36	1034	44460	768	755	729	706	683	661	641	621	602	584	567	551	535	520	505		
36LH15	36	36	1090	46880	809	795	781	769	744	721	698	677	656	637	618	600	583	567	551		



### 3. Steel beam (interior):

W 24 X 84 @ 40' center spanning 20 ft  
braced @ 4 ft by the steel joists.



Weight of the beam: 84 plf

$$\Rightarrow D = 84 \text{ plf} + 39 \text{ psf} \cdot 40' + 27 \text{ plf} \cdot \frac{40'}{4} = 1914 \text{ (plf)}$$
$$\rightarrow 1.2 D = 2296.8 \text{ plf}$$

### Strength Capacity:

For W 24 X 84 :  $L_p = 6.89 \text{ ft}$  (AISC Table 3-2)

$$\phi_b M_{px} = 840 \text{ kip-ft}$$

$$L_b = 4 \text{ ft} < L_p = 6.89 \text{ ft}$$

$$\Rightarrow \phi_b M_{nx} = 840 \text{ kip-ft}$$

$$\Rightarrow w' = \frac{840 \text{ kip-ft} \cdot 8}{(20 \text{ ft})^2} = 16.8 \text{ kip/ft} = 16,800 \text{ plf}$$

$$\Rightarrow w_{\text{allowed}} = \frac{16,800 - 2,296.8}{1.6} = 9064.5 \text{ (plf)}$$

$$\Rightarrow w_{\text{LL allowed}} = \frac{9064.5}{40} = 226.6 \text{ psf}$$



## Deflection Capacity:

For W24x84:  $I_{xx} = 2370 \text{ in}^4$

$$\Delta = \frac{5wL^4}{384EI_x}$$

$$\Delta \leq \frac{L}{240} \text{ for } O+L$$

$$\Delta \leq \frac{L}{360} \text{ for } L \text{ alone}$$

$$\frac{L}{240} = \frac{20.12}{240} = 1 \text{ in}$$

$$\frac{L}{360} = \frac{20.12}{360} = \frac{2}{3} \text{ in}$$

$$W_{O+L} = 1914 \text{ psf} + L_{\text{allowed}} = 159.5 \text{ lbs/in} + L_{\text{allowed}}$$

$$\frac{5(159.5 + L_{\text{allowed}})(20.12)^4}{384 \cdot 29,000,000 \cdot 2370} = 1$$

$$\Rightarrow L_{\text{allowed}} = 1431.5 \text{ lbs/in} \Rightarrow W_{\text{allowed}} = \underline{429 \text{ psf}}$$

$$\frac{5(L_{\text{allowed}})(20.12)^4}{384 \cdot 29 \cdot 10^6 \cdot 2370} = \frac{2}{3}$$

$$\Rightarrow L_{\text{allowed}} = 1060 \text{ lbs/in} \Rightarrow W_{\text{allowed}} = \underline{318 \text{ psf}}$$

$$\Rightarrow \text{So, the capacity of the interior beam is } \underline{\underline{226.6 \text{ psf}}}$$

#### 4/Steel column:

$$\begin{aligned} W &= 10 \times 39 \\ A_g &= 11.5 \text{ in}^2 \\ r &= 1.98 \text{ in} \\ F_y &= 50 \text{ ksi} \\ E &= 29,000 \text{ ksi} \end{aligned}$$

$$\text{height } h = 15' - 10 \frac{1}{2}'' = 15.875 \text{ ft}$$

brace @ each end

to be conservative, assume the column is pin-pin

$$\Rightarrow K = 1$$

$$F_c = \frac{\pi^2 E}{\left(\frac{KL}{r}\right)^2} = \frac{\pi^2 \cdot 29000}{\left(\frac{15.875 \cdot 12}{1.98}\right)^2} = 30.92 \text{ (ksi)}$$

$$\Rightarrow \frac{F_y}{F_c} = \frac{50}{30.92} = 1.62 \leq 2.25$$

$$\Rightarrow F_{cr} = \left[0.658^{F_y/F_c}\right] F_y = 0.658^{1.62} \cdot 50 = 25.41 \text{ (ksi)}$$

$$\Rightarrow \phi P_n = 0.9 F_{cr} A_g = 0.9 \cdot 25.41 \cdot 11.5 = \underline{263 \text{ (kips)}}$$

$$\text{Weight of the column} = 39 \cdot 15.875 = 619.13 \text{ (lbs)}$$

$$\text{Tributary area of the column, } A_T = 20' \times 40' = 800 \text{ (ft}^2\text{)}$$

$$\text{Deck weight on the column} = 39 \text{ psf} \cdot 800 = 31,200 \text{ (lbs)}$$

$$\text{Joist weight on the column} = 5 \cdot (27 \text{ plf} \cdot 40') = 5,400 \text{ (lbs)}$$

$$\text{Beam weight on the column} = 20' \cdot 24 = 480 \text{ (lbs)}$$

$$\Rightarrow \text{Total dead load, } D = 37,080 \text{ (lbs)}$$

$$\Rightarrow 1.2D = 44,496 \text{ (lbs)}$$

$$\Rightarrow 1.6 L_{\text{allowed}} = 263,000 - 44,496 = 218,504 \text{ (lbs)}$$

$$\Rightarrow w_{\text{allowed}} = \frac{218,504}{1.6 \cdot 800} = 171 \text{ psf}$$

So, the capacity of the column is 171 psf

## 5. Steel beam (edge):

W 21 x 50 support + 20 ft deck and span 20 ft.  
unbraced.

weight of the beam: 50 plf

$$D = 50 \text{ plf} + 39 \text{ psf} \cdot 20' + 27 \text{ plf} \cdot \frac{20'}{4'} = 965 \text{ (plf)}$$

$$\Rightarrow 1.2 D = 1158 \text{ plf}$$

### Strength Capacity:

For W21 x 50 :  $L_{px} = 4.59 \text{ ft}$  (AISC Table 3-2)  
 $\phi_b M_{px} = 413 \text{ kip-ft}$

$$L_b = 4 \text{ ft} < L_{px}$$

$$\Rightarrow \phi_b M_{nx} = \phi_b M_{px} = 413 \text{ kip-ft}$$

$$\Rightarrow w = \frac{413 \cdot 8}{20^2} = 8.26 \text{ (kip/ft)} = 8,260 \text{ plf}$$

$$\Rightarrow L_{\text{allowed}} = \frac{8,260 - 1,158}{1.6} = 4,438.75 \text{ (plf)}$$

$$\Rightarrow W_{\text{allowed}} = \frac{4,438.75}{20} = \underline{\underline{222 \text{ (psf)}}}$$



## Deflection Capacity:

For W21 X 50 :  $I_{xx} = 984 \text{ in}^4$

$$\Rightarrow \frac{5wl^4}{384EI_{xx}}$$

$$\Delta \leq \frac{L}{240} = 1 \text{ in for D+L}$$

$$\Delta \leq \frac{L}{360} = \frac{2}{3} \text{ in for L alone}$$

$$W_{D+L} = 965 \text{ plf} + L_{\text{allowed}} = 80.417 \text{ lbs/in} + L_{\text{allowed}}$$

$$\frac{5(80.417 + L_{\text{allowed}}) \cdot (20.12)^4}{384 \cdot 29 \cdot 10^6 \cdot 984} = 1$$

$$\Rightarrow L_{\text{allowed}} = 580 \text{ lbs/in} \Rightarrow W_{\text{allowed}} = \underline{348 \text{ psf}}$$

$$\frac{5(L_{\text{allowed}})(20.12)^4}{384 \cdot 29 \cdot 10^6 \cdot 984} = \frac{2}{3}$$

$$\Rightarrow L_{\text{allowed}} = 440 \text{ lbs/in} \Rightarrow W_{\text{allowed}} = \underline{269 \text{ psf}}$$

$\Rightarrow$  So, the capacity of the edge beam is 222 psf

## Conclusion:

The capacity of the steel joists controls the capacity of the mezzanine platform.

Assume the weight of lightings & mechanical ducts as 2 psf.

⇒ The capacity of the mezzanine is 100 psf.

## Retrofit concept for mezzanine stair / ladder

I / Stair @ ④ on A6 of 82-111:

The slope of the stair is max  $\left\{ \begin{array}{l} \tan^{-1} \left( \frac{7' - 3\frac{15}{16}''}{9' - 7\frac{1}{2}''} \right) = 37.3^\circ \\ \tan^{-1} \left( \frac{8' - 6\frac{9}{16}''}{11' - 4\frac{1}{2}''} \right) = 36.9^\circ \end{array} \right.$

$\Rightarrow$  the slope is  $37.3^\circ < 50^\circ$

According to OSHA 3124-12R 2003 page 14 & 15:

- The handrail must be in between 30 inches and 37 inches from the upper surface of the handrail to the surface of the tread.

The actual handrail height is  $2' - 8\frac{3}{8}'' = 32.375''$

$\Rightarrow$  It meets the requirement from OSHA.

II / Ladder on A7 of 82-111:


The slope of the ladder  $\Rightarrow 60^\circ > 50^\circ$

According to OSHA 3124-12R 2003 page 9:


- the side rail for the ladder must be at least 42" vertically.

According to the drawing and the site visit photograph:  
height of the side rail = 42"

$\Rightarrow$  It meets the requirement from OSHA.







**4** SECTION AT MEZZANINE STAIR  
 (ALTERNATE #1)

1/4" = 1'-0"







## PROJECT MEMO

**To:** Janet Knoblach, AIA/ Engineering and Architectural Services Architect  
**From:** Joseph Simon, P.E./ AHBL Structural Engineers  
**AHBL Office:** Tacoma, WA (253) 383-2422  
**Date:** 9/30/2014  
**Project:** Modular Building New Storage Rack Installation  
**AHBL No.:** 2130191.29  
**Subject:** Floor Load Capacity Study

Janet, AHBL was retained to evaluate the capacity of the existing concrete slab on grade to support and anchor new storage racks to be installed in the portion of the Record Center Building currently housing a printing operation. To aid my efforts, I received foundation drawings and rack loading and dimension information from your office. I also contacted Mr. Tom Tate with Northwest Handling Systems to get information pertaining to their standard practices regarding rack installation.

Based on our investigation, it appears that the existing floor slab is adequate to support the proposed racks for load combinations including gravity and seismic forces. Furthermore, the existing slab is sufficiently thick to develop anchorage against seismically induced lateral and uplift forces.

Based on information I received, I understand that the new storage racks will match the width and shelf length of the existing rack system in an adjacent space (5'-4" wide, 10'-0" long shelf length) except that the proposed racks will be about 23'-4" tall to the highest shelf. The proposed racks are to have eleven shelves and each shelf is to support as much as 2160 pounds.

In talking with Mr. Tate, I understand that it is typical for each leg of the rack system to be anchored with two 1/2 inch diameter Hilti Kwik Bolt TZ expansion-type anchors with 3.25 inches of embedment. Based on our calculations, this means of anchorage appears to be acceptable. However, the rack manufacturer/supplier/installer should perform engineering calculations in accordance with the IBC detailing and justifying the actual means of anchorage.

I hope this information is helpful. Feel free to call with any questions.

Sincerely,

Joseph Simon, P.E.





## ENERGY SERVICES PROPOSAL

### INVESTMENT GRADE AUDIT FOR THE STATE MODULAR BUILDING ENERGY UPGRADES

PREPARED BY  
**UNIVERSITY MECHANICAL CONTRACTORS, INC.**  
November 27, 2012

---

## **TABLE OF CONTENTS**

---

- 1.0 EXECUTIVE SUMMARY**
- 2.0 EXISTING CONDITIONS**
- 3.0 FACILITY AUDIT & ANALYSIS**
- 4.0 PROPOSED SCOPE OF WORK**
- 5.0 PROJECT FINANCIALS**
- 6.0 MEASUREMENT AND VERIFICATION**
- 7.0 IMPLEMENTATION PLAN**
- 8.0 APPENDIX**



---

## 1.0 EXECUTIVE SUMMARY

---


University Mechanical Contractors, (UMC), is pleased to have the opportunity to present this Investment Grade Audit for the State Modular Building Energy Upgrades. The scope of this project is focused on reducing energy usage and improving the heating and cooling systems serving the facility. After performing a complete audit and analysis of the boiler plant and the chiller plant, we have worked directly with the state of WA Department of Enterprise Services to develop an energy conservation and facility upgrade program. When implemented, this program will provide the following benefits.

### Energy and Water Conservation Benefits:

1. Estimated annual savings include 12,227 therms natural gas and 100,647 kWh (1,566 million Btus)\*. This equates to \$21,881 / year at current utility rates.
2. Estimated PSE conservation incentives of \$13,500
3. Estimated Annual Operational Savings of \$1,667

Notes: \* (The savings shown here are estimated savings. See Section 6.1 for guaranteed energy savings)

### Atmospheric Benefits:



### Facility Infrastructure Benefits:

1. Upgrades lighting system with new lamps and fixture replacements in select locations.
2. Replaces all remaining pneumatic control devices in the facility with DDC. This includes the large pneumatic HW valves located in the boiler room.
3. Improves ventilation air quality supplied to printing area.

UMC is pleased to provide this project that meets the initial goals and provides substantial benefits for the State Modular Building. The estimated project investment; estimated utility incentive; and guaranteed utility consumption savings resulting from the project's implementation are shown in the following table.

### Savings and Investment Summary

Utility Conservation & Facility Upgrade Measures	Resulting Annual Savings <sup>(1)</sup>	Estimated Operational Savings	Potential Utility Rebate <sup>(2)</sup>	Guaranteed Project Cost	Simple Payback
	\$	\$	\$	\$	Yrs
	\$ -	\$ -	\$ -	\$ -	
UCM1: Lighting & Lighting Controls Upgrades	\$ 6,043	\$ 1,500	\$ 13,500	\$ 87,650	9.8
	\$ -	\$ -	\$ -	\$ -	
	\$ -	\$ -	\$ -	\$ -	
UCM2: HVAC Controls Upgrade	\$ 1,156	\$ -	\$ -	\$ 101,332	87.7
	\$ -	\$ -	\$ -	\$ -	
	\$ -	\$ -	\$ -	\$ -	
UCM3: Energy Based Re-Commissioning	\$ 9,717	\$ -	\$ -	\$ 87,448	9.0
	\$ -	\$ -	\$ -	\$ -	
<b>Subtotal</b>	<b>\$ 16,916</b>	<b>\$ 1,500</b>	<b>\$ 13,500</b>	<b>\$ 276,430</b>	<b>14.3</b>
				\$ -	
				\$ 4,146	
				\$ -	
<b>Subtotal - Construction</b>	<b>\$ 16,916</b>	<b>\$ 1,500</b>	<b>\$ 13,500</b>	<b>\$ 280,576</b>	<b>14.5</b>
<b>Additional Project Development and Implementation Costs</b>					
Investment Grade Audit				\$ 10,875	
Mechanical Design				\$ 13,215	
Lighting Design				\$ 4,383	
Project Management				\$ 16,586	
M&V (Years 2 & 3)				TBD	
Overhead				\$ 27,643	
Profit				\$ 22,114	
<b>Total Construction Cost - (All Measures / Excluding Tax)</b>	<b>\$ 16,916</b>	<b>\$ 1,500</b>	<b>\$ 13,500</b>	<b>\$ 375,392</b>	<b>19.7</b>
Construction Contingency				\$ 20,732	
				\$ -	
<b>Subtotal</b>				<b>\$ 396,124</b>	
Construction Allowance for B&G					
WA State GA Project Management Fee					
WA State GA M&V Fee (Years 2 & 3 total)					
Estimated Tax (@ 8.7%)				\$ 32,659	
<b>Total Installed Cost (Including Contingency)</b>				<b>\$ 428,783</b>	<b>22.5</b>
Notes:					
(1) Annual utility savings (\$) are based on current utility rate schedule					
(2) Rebates & Incentives are estimated, but not guaranteed					
(3) Estimated Tax applies to Total Construction Cost, excluding contingency					

We are excited to be the Energy Service Company (ESCO) partnering with Washington State, and will continue to work collaboratively in planning, developing and implementing a seamless project that achieves the financial, facility, engineering, and operational objectives.

## 2.0 EXISTING CONDITIONS

### 2.1 Facility Description & Overview



#### Overview:

The State Modular Building is a 97,600 square foot, production, warehouse & office facility. The facility was constructed in two phases. The first phase, constructed in 1979, consists of a 40,000 sqft low bay area currently used for printing, storage and fulfillment and a 57,600 sqft high bay area that houses the printing equipment and production department. The second phase, implemented in 1983, consisted of tenant

improvement in the high bay section. This facility is located directly adjacent to the Isabella Bush Records Center in Tumwater. This facility is currently occupied by the state printing department. There is currently some question as to the long term utilization of this facility and whether it will be modified to serve a different function in the near term.




#### HVAC System:

The HVAC system consists of four (4) rooftop mounted dual duct VAV units. There are two units (S-1 & S-2) that are located on the low bay section of the facility and two (S-3 & S-4) that are located on the high bay section. Each of these RTUs utilize HW and CHW from the central systems to heat & cool the respective hot/cold deck of each system. These units provide air to DD terminal boxes located throughout the facility.

#### Hot Water System:

Heating for the facility is provided by two (2) standard efficiency Burnham boilers located in a second floor mechanical room. The heating HW is distributed to the facility via a primary/secondary pumping system. There are two secondary loops, one of which serves the RTUs while the second serves ceiling hung unit heaters that are located at roll-up doors throughout the facility.



**Chilled Water System:**

A 300 ton Carrier water cooled centrifugal chiller (installed in 1999) is utilized to generate CHW for the facility. This system utilizes a BAC cooling tower (located on the roof) to reject heat. The CHW circulation system distributes CHW to the four RTUs.

**Domestic Hot Water:**

Domestic hot water (DHW) requirements are provided through small electric DHW heaters.

**Energy Management Systems:**

The majority of the facility is controlled via a Johnson Control Metasys DDC system.

**Lighting:**

The lighting for this facility is comprised primarily of a combination of 4' fluorescent fixtures with T8 32 watt lamps in a majority of the facility and 8' fluorescent fixtures with T12 HO lamps throughout the high bay production area.

**Water Fixtures:**

Water fixtures serving the facility are primarily high flow fixtures, consisting of 3.5 gpf water closets, 1.0 gpf urinals and 2.2 gpm faucets.

---

## 3.0 FACILITY AUDIT & ANALYSIS

---

### 3.1 Utility Data Analysis

#### Utility Suppliers

The individual utility suppliers are listed below.


#### Electricity & Natural Gas

Puget Sound Energy provides electricity and Natural Gas for the facility. The observed electrical blended rate over the last 12 months is \$0.096/kwh. The average natural gas rate during this same time frame was \$1.065/therm. The detailed baseline utility rate is shown in Section 6.

#### Electric Utility Data


Throughout the period starting June 2011 and ending May 2012, the facility consumed 1,736,800 kWh of electricity. The annual electric demand for the same period was 5,289 kW, with a monthly peak of 496 kW in April of 2012 and a monthly low of 369 kW in December.

The following charts shows historical electric consumption and demand during this period.



One method, to illustrate the upward or down ward trend of utility usage over a long period of time is through the use of a 12-month rolling average chart (shown below). Each bar on the following charts represents the total kW or kWh for the previous 12 months (including the month noted on the x-axis).






As illustrated in the chart above, the electrical usage and demand have both remained fairly consistent over the recent past. .


**Natural Gas Utility Data**

Throughout the period starting June 2011 and ending May 2012, the facility consumed 71,120 therms of gas, with a monthly peak of 9,704 therms in December of 2011 and a monthly low of 893 therms in August of 2011.

The following chart shows historical gas consumption during this period.



As illustrated in the following chart, there has been a slight downward trend in annual gas usage since March of 2011. This could be due primarily to weather fluctuations, but most likely there has been some effect from the recent controls commissioning that has been implemented by L&I.



### **Energy Use Index**

The Energy Use Index (EUI) is a method used to compare the energy usage between similar facilities in geographic regions throughout the United States. This EUI is a measure of the total energy usage (in British Thermal Units – Btu) divided by the total square footage of the facility. The EUI for the State Modular Building is 133,603 Btu/sqft/yr. This facility is very hard to benchmark against other facilities due to its unique and varied usage characteristics.

### 3.2 Building Baselines

For the purposes of this project, the proposed utility usage Baseline consumption for the State Modular Building is provided below.

**State Modular Building – Proposed Utility Usage Baseline**

MONTH	ELECTRICAL KWH	DEMAND KW	ELECTRICAL (\$)	GAS THERMS	GAS (\$)	UTILITY TOTAL (\$)
Jul-11	154,400	460	\$14,073	1,287	\$1,488	\$15,561
Aug-11	162,400	475	\$14,737	893	\$1,053	\$15,790
Sep-11	157,600	478	\$14,601	3,031	\$3,411	\$18,012
Oct-11	139,600	401	\$13,883	6,651	\$7,330	\$21,213
Nov-11	146,800	435	\$14,721	9,454	\$9,957	\$24,679
Dec-11	138,400	369	\$13,475	9,704	\$10,220	\$23,695
Jan-12	120,000	380	\$12,083	8,911	\$9,388	\$21,471
Feb-12	148,000	437	\$14,805	9,672	\$10,187	\$24,992
Mar-12	136,000	440	\$13,582	7,871	\$8,289	\$21,870
Apr-12	139,600	496	\$13,011	5,876	\$6,159	\$19,169
May-12	149,600	464	\$13,749	4,632	\$4,899	\$18,648
Jun-12	144,400	454	\$13,414	3,138	\$3,342	\$16,756
<b>Subtotals</b>	<b>1,736,800</b>	<b>5,289</b>	<b>\$166,133</b>	<b>71,120</b>	<b>\$75,723</b>	<b>\$241,856</b>

#### **Baseline Adjustment**


The implementation of UCM-3 Energy Base Re-Commissioning will result in an increased amount of ventilation air being supplied to the facility throughout the year. This air will have to be conditioned, and as a result there will be an increase in the baseline energy usage to account for this newly conditioned air. This additional energy usage has been estimated using a BIN weather analysis (provided in the appendix). This baseline adjustment will result in the following increased utility usage.

**Adjusted Annual Electrical Energy Usage:**  
 $1,736,800 \text{ kWh} + 25,344 \text{ kWh (adjustment)} = 1,762,144 \text{ kWh}$

**Adjusted Annual Gas Energy Usage:**  
 $71,120 \text{ therms} + 2,603 \text{ therms (adjustment)} = 73,723 \text{ therms}$

### **Baseline Operating Practices**

The operating practices during the Baseline period determine the utility consumption shown in the Tables shown above. The information in the following tables outlines the operating characteristics that were in effect during the Baseline period, as determined during the Investment Grade Audit.



EQUIPMENT	DESCRIPTION	QTY	HP	KW	OPERATING HRS/YR	ANNUAL KWH	ANNUAL COST
<b>Fans</b>							
<b>Supply Fans</b>							
S-1	Low Bay North	1	15.00	6.8	8,760	59,771	\$5,720
S-2	Low Bay South	1	20.00	9.1	8,760	79,695	\$7,627
S-3	High Bay West	1	25.00	11.4	8,760	99,618	\$9,533
S-4	High Bay East	1	30.00	13.6	8,760	119,542	\$11,440
<b>Return Fans</b>							
R-1	Low Bay North	1	5.00	2.3	8,760	19,924	\$1,907
R-2	Low Bay South	1	7.50	3.4	8,760	29,885	\$2,860
R-3	High Bay West	1	15.00	6.8	8,760	59,771	\$5,720
R-4	High Bay East	1	20.00	9.1	8,760	79,695	\$7,627
<b>EXHAUST FANS</b>							
EF-1	Dark rm	1	0.08	0.1	4,680	284	\$27
EF-2	Plate rm	1	0.10	0.3	4,680	1,193	\$114
EF-3	Dark rm	1	0.10	0.3	4,680	1,193	\$114
EF-4	Dark rm	1	0.10	0.4	4,680	2,059	\$197
EF-5	chemstor	1	0.10	0.1	8,760	638	\$61
EF-6	locker rm	1	0.10	0.1	4,680	341	\$33
EF-7	waste paper	1	30.00	21.8	4,680	102,184	\$9,779
EF-8	Ludlow Machine	1	0.10	0.1	4,680	341	\$33
E-8	Media Processing	1	0.75	0.5	4,680	2,555	\$244
<b>Relief Fans</b>							
Ref-1	Office Area	1	0.25	0.2	4,160	757	\$72
Ref-2	Office Area	1	0.25	0.2	4,160	757	\$72
H-8	109	1	0.05	0.0			
H-9	Lunchroom	1	0.05	0.0			
H-10	101	1	0.05	0.0			
H-11	107	1	0.05	0.0			
H-12	Corridor	1	0.03	0.0			
H-13	Receiving #125	1	0.17	0.1			
H-14	Receiving #125	1	0.17	0.1			
H-15	Receiving #125	1	0.17	0.1			
H-16	Receiving #125	1	0.17	0.1			
H-17	Maint. Grnds Entry	1	0.13	0.1			
H-18	Bir Rm	1	0.05	0.0			
H-19	Chir Rm	1	0.04	0.0			
H-20	Mezz. Storage	1	0.04	0.0			
H-21	Mezz. Storage	1	0.04	0.0			
Boiler 1		1		1.9			
Boiler 2		1		1.9			
Subtotal					91.2	660,201	\$63,181
<b>Pumps</b>							
<b>Circulation Pumps</b>							
R-3	CHW(Armstroing)	1	25.00	18.2	500	9,098	\$871
R-4	CNDW Pump	1	20.00	14.6	250	3,639	\$348
R-5	CNDW Pump	1	20.00	14.6	250	3,639	\$348
H-3	RTU Pump	1	5.00	3.6	4,160	15,138	\$1,449
H-4	Cab hrs & Unit hrs	1	2.00	1.5	4,160	6,055	\$579
H-5	Bir H-1 Recirc Pump	1	2.00	1.5	4,160	6,055	\$579
H-6	Bir H-2 Recirc Pump	1	2.00	1.5	4,160	6,055	\$579
	HHW Primary Loop Pump	1		3.0	1,820	5,481	\$525
Subtotal					58.3	55,161	\$5,279
<b>Cooling</b>							
R-6	CRCU	1	0.50	0.4	4,160	1,514	\$145
R-7	Air Cooled Condenser	1	0.33	0.2	4,160	999	\$96
CH-1	Chiller (York 300 Centrifugal w/ vfd)	1		210.0	500	105,000	\$10,049
Subtotal					210.6	107,513	\$10,289
<b>Cooling Towers</b>							
CT-1	Fan	1	20.00	14.6	500	7,278	\$697
	Fan	1	20.00	14.6	500	7,278	\$697
	Pan Heater	1		7.0	50	350	\$33
Subtotal					36.1	14,906	\$1,427
<b>Lighting</b>							
Percentage of Annual Electrical Usage							
Watts per Square Foot						4,472	
Percent Lights On at any one time						75%	
Building Occupancy %						100%	
Subtotal					-	283,235	\$27,106
<b>DHW</b>							
A-2	40 Gal 2 Element	1		6.0	900	5,400	\$517
A-3	30 Gal 2 Element	1		5.0	900	4,500	\$431
A-4	80 Gal 2 Element	1		10.0	900	9,000	\$861
A-5	20 Gal 1 Element	1		3.0	900	2,700	\$258
Subtotal					24.0	21,600	\$2,067
<b>Misc</b>							
Plug Load w/sqft						2	
Avg Load % On						20%	
Building Occupancy %						100%	
Printing/Copying Equipment							
Subtotal					3,640	142,106	\$13,600
R-8	Controls Air Compressor	1	3.00	2.2	200	437	\$42
	Printer Air Compressor	1	30.00	26.9	1,501	40,335	\$3,860
	Mezzanine Printer Air Compressor	1		14.6	1,501	21,849	\$2,091
	Air Dryer (Dominick-Hunter)	1		1.3	1,502	1,993	\$191
Subtotal					45.0	590,719	\$58,063
<b>Total</b>					<b>465.2</b>	<b>1,733,336</b>	<b>\$167,411</b>



### Existing Operating Characteristics

Existing Equipment Annual Operating Hours				
Annual Operating Hours =				
Day of Week	Run Hours (HVAC Equipment)			
Monday	24 hrs/day			
Tuesday	24 hrs/day			
Wednesday	24 hrs/day			
Thursday	24 hrs/day			
Friday	24 hrs/day			
Saturday	24 hrs/day			
Sunday	24 hrs/day			
Holiday	24 hrs/day			

Existing Heating/Cooling Operating Set Point Temperatures				
Day of Week	Office Space Occupied Degree F (Heating/Cooling)	Office Space Unoccupied Degree F (Heating/Cooling)		
Monday	68 / 72	68 / 72		
Tuesday	68 / 72	68 / 72		
Wednesday	68 / 72	68 / 72		
Thursday	68 / 72	68 / 72		
Friday	68 / 72	68 / 72		
Saturday	68 / 72	68 / 72		
Sunday	68 / 72	68 / 72		
Holiday	68 / 72	68 / 72		

---

## 4.0 PROPOSED SCOPE OF WORK

---

### 4.1 Scope of Work

The following is a detailed description of each Utility Conservation Measure (UCM) that is being recommended as part of this proposal.

UCM-1 Lighting and Control Upgrades
<b>Overview of Current Situation</b>
<p>The current lighting systems utilize a combination of fixture types including:</p> <ul style="list-style-type: none"><li>• 4' T8 32 watt fluorescent</li><li>• 4' &amp; 8' T12 HO fluorescent fixtures (printing area)</li><li>• Mercury Vapor lamps</li><li>• 2 Lamp F32 T8 U-Tube Lamps, NBF Ballast</li></ul>
<b>Recommendations</b>
<ul style="list-style-type: none"><li>• Retrofit the existing 4' &amp; 8' T12 HO fixtures with T8, 28 watt lamps, reflectors and HBF ballasts.</li><li>• Retrofit existing 4' T8, 32 watt fixtures with T8, 28 watt lamps</li><li>• Retrofit existing 2 Lamp F32 T8 U-Tube Lamps with Troffer Kit with Reflector 2' w 2 F17 17 watt Lamp NBF</li><li>• Replace exiting interior mercury vapor lamps with CFL</li><li>• Install occupancy sensors in select areas and restrooms to turn fixtures off when the space is unoccupied.</li></ul>
<b>Benefits (Including Occupant Health &amp; Safety)</b>
<ul style="list-style-type: none"><li>• Reduces electrical energy usage</li><li>• Improves lamp life and reduces annual lamp replacement costs</li></ul>

## UCM-2: HVAC Controls Upgrade

### Overview of Current Situation

The existing controls system for the Modular Building consists of a JCI DDC front end with E/P transducers used to control pneumatic end controllers. There are also several fully pneumatic control valves still in operation on the HW distribution system. There is a requested desire by DES to completely remove any remaining pneumatic controls from the facility and replace with DDC.

### Recommendations

- Replace remaining pneumatic control valves with new DDC controlled valves (located in boiler mechanical room & at unit heaters near roll-up doors).
  - (2) HW control valves located in boiler room
  - (7) HW control valves serving unit heaters at each roll-up door
  - (7) HW control valves serving unit heaters located throughout the facility
- Replace remaining pneumatic devices with new full DDC control that includes the following
  - Up to twenty (20) pneumatic thermostats located in low bay VAV boxes.

### Advantages/Benefits

- Improve operating efficiency of HVAC control system
- Solve operational issues
- Improve energy efficiency
- Improve occupant comfort

### Supporting Documentation

### UCM-3: Energy Based Re-Commissioning

#### Overview of Current Situation

The existing HVAC system serves the space heating, cooling & ventilating requirements of the facility adequately, but could be improved from an overall efficiency standpoint. During the course of the audit the following items were noted.

- There is a lack of control over the RA/OA dampers that limits the controllability of the ventilation air supplied by the 4 rooftop DD VAV units. This is especially prevalent with the 2 RTUs serving the high bay print area. The RA fan currently supplies excess air pressure such that it over-pressurizes the MA plenum and prevents sufficient ventilation air from entering the area served by these units. This operation also has the effect of inadvertently lowering the EUI baseline due to the reduced requirement of heating/cooling the OA that would otherwise be entering the RTU for ventilation purposes.
- Trends indicate that the issues with the lack of ventilation air occurs primarily during the occupied (daytime) periods for the facility. During the unoccupied (nighttime) periods, the ventilation air increases. This is actually the opposite of preferred operation for these units. As a result of the current mode of operation, the increase in OA at night results in a decrease in the MA temperature and also a significant increase in the Hot Deck temperature (as this is required to heat the MA and maintain the facility setpoint). During the daytime (when the RA over-pressurizes the MA plenum) the MA becomes the same temperature as the RA (~72F).
- In certain areas (low bay copy center, etc) there are some thermostats that control 2 DD boxes.
- The high bay print shop often leaves the rollup loading dock door open throughout the day. This may be a result of odors indoors due to poor IAQ and makes humidity/temperature control difficult.
- The humidity control has been upgraded from a central steam system to stand alone ultrasonic humidity controllers located on columns throughout the print shop.

#### Recommendations

Implement a Re-commissioning effort for the facility HVAC system. Targeted improvements would include:


- Efficient modification of control sequencing issues (as applicable).
- Optimization of the RTUs, Heating System, Cooling System & Unit Heaters.
- Modify control sequencing on RTU's to improve ventilation air control. This could help with economizer efficiency and odor control in the print shop.
- Control DHW pump to turn unit off when the facility is unoccupied.
- Implement Optimum Start/Stop schedule for all systems.
- Optimize unit heater operating sequence at dock doors to prevent unnecessary operation.
- Reduce ventilation air during typically unoccupied periods to reduce nighttime heating requirements.
- Pre & Post Testing and Air Balancing (TAB).

#### Advantages/Benefits



- Improve operating efficiency of HVAC control system
- Solve operational issues
- Improve energy efficiency
- Improve occupant comfort

**(Note: The proposed modification to the RTU control that will result in improved ventilation to the space will also result in an increase in the heating/cooling required to condition this increase in outside air. As a result, a baseline modification to the energy use baseline is being proposed.)**

### Supporting Documentation







## 4.2 Project Notations/Clarifications/Exclusions

1. Adequate space will be provided for the staging of materials.
2. Owner shall provide access as required per the coordinated schedule.

3. This project does not include any hazardous material identification, material handling, removal and disposal, which may be found during construction of this project.
4. This project does not include any asbestos testing or abatement.
5. This project does not allow for cost associated with working in hazardous or confined spaces.
6. This project does not include hazardous material identification, material handling or removal & disposal that may be found during construction. This includes mold remediation.
7. This project does not include any upgrades to the existing electrical system due to load or code requirements at facility.
8. This project does not include any upgrades to the existing fire protection system.
9. This proposal does not include the repair or replacement of existing damaged lighting fixtures, hardware and lenses/fixture enclosures.
10. This project does not include any costs for temporary construction utilities other than temporary heating.
11. This project does not include any costs for structural upgrades.
12. This project excludes architectural sheet metal
13. This project excludes sound consultant or acoustical engineering
14. All work as proposed is expected to be done during normal working hours.
15. Boiler Replacement and Upgrade assumes that there are no unforeseen issues with the existing vertical chase when installing the proposed new, stainless steel exhaust stack. There are sections of this chase that were not accessible during the development of this IAG.

### **4.3 Conservation Measures Not Included in Current Proposal**

1. Upgrade HW Boiler System:

- The existing HW boilers (2) are standard efficiency boilers and are nearing the end of their useful life.
- The HW distribution piping must be maintained at a constant temperature at all times to prevent leaks that occur at gaskets/joints throughout the facility. The requirement to maintain temperature 24/7 causes the system to be extremely inefficient.
- The HW piping located within the boiler room is extremely complex, making it difficult to efficiently control HW distribution efficiently.
- The pumping system is constant volume.

UMC recommends replacing the existing boilers and upgrading the piping system throughout the facility, improving the piping distribution/layout within the boiler room and upgrading the pumping distribution system to variable volume. If this ECM were incorporated with the boiler replacement being recommended at the Records Center, there may be an opportunity to combine the two separate systems into one. This would reduce the initial capital cost and the ongoing operations/maintenance costs.

2. Replace the four existing rooftop units:

- The existing RTUs are well past their useful life.
- The DD/VAV system currently serving this facility is inefficient for this type of operation.

UMC recommends redesigning the existing HVAC air side system and replacing the DD rooftop units with a more efficient system for this facility.

3. Implement water conservation upgrades throughout the facility

4. Install VFD on cooling tower fan motor

5. Review opportunities for improving weatherization around loading dock doors.

## 5.0 PROJECT FINANCIALS

This section provides an overview of the financial impact provided through implementation of this program. We have attempted to convey this information in a manner that identifies the costs, savings, fees, rates and structures along with a cash flow analysis.

### 5.1 Project Cost Structure

For development and performance of the Work described in this proposal, the Washington State Department of Enterprise Services shall pay to University Mechanical Contractors, Inc. the Contract Sum of \$375,392 - (excluding estimated WA State Sales Tax, contingency and, estimated WA State GA Project Management Fees). The following table outlines all of these costs, including UMC's fees and compensation.

CATEGORY	COST (\$)	% OF CONSTRUCTION COST
<b>CONSTRUCTION COST (MTRL &amp; LBR)</b>	\$ 276,430	
PERFORMANCE & PAYMENT BOND	\$ 4,146	1.5%
PROJECT SUPERVISION (ON-SITE)	\$ -	
<b>Subtotal</b>	<b>\$ 280,576</b>	
<b>PROJECT DEVELOPMENT</b>		
INVESTMENT GRADE AUDIT	\$ 10,875	
VAV BOX AUDIT	\$ -	
<b>Subtotal</b>	<b>\$ 10,875</b>	
<b>PROJECT IMPLEMENTATION</b>		
MECH DESIGN (CONSTRUCTION DOCUMENTS)	\$ 13,215	7.0%
LIGHTING DESIGN	\$ 4,383	5.0%
PROJECT/CONSTRUCTION MANAGEMENT	\$ 16,586	6.0%
<b>Subtotal</b>	<b>\$ 34,183</b>	
<b>PERFORMANCE MEASUREMENT &amp; VERIFICATION</b>		
MEASUREMENT & VERIFICATION (YRS 2 & 3)	excluded	
<b>Subtotal</b>	<b>\$ -</b>	
<b>OTHER PROJECT COSTS</b>		
OVERHEAD	\$ 27,643	10.0%
PROFIT	\$ 22,114	8.0%
<b>Subtotal</b>	<b>\$ 49,757</b>	
<b>TOTAL PROJECT COST - (EXCLUDING TAX)</b>	<b>\$ 375,392</b>	
<b>CONSTRUCTION CONTINGENCY</b>	<b>\$ 20,732</b>	
<b>SUBTOTAL (WITH CONTINGENCY)</b>	<b>\$ 396,124</b>	
<b>CONSTRUCTION ALLOWANCE FOR B&amp;G</b>	<b>\$ -</b>	
<b>WA STATE GA PROJECT MANAGEMENT FEE</b>	<b>\$ -</b>	
<b>WA STATE GA M&amp;V FEE (YEARS 2 &amp; 3)</b>	<b>\$ -</b>	
<b>ESTIMATED TAX (@ 8.7%)</b>	<b>\$ 32,659</b>	
<b>SUBTOTAL (WITH CONTINGENCY)</b>	<b>\$ 428,783</b>	
<b>Notes:</b>	Mechanical design fee is % of mechanical construction cost only	
	Lighting design fee is % of lighting construction cost only	
	Project Management, bond and O&P fees are % of total construction cost	
	Estimated Tax applies to Total Project Cost (excluding contingency)	

## 5.2 Project Cash Flow Analysis

The following table provides a sample cash flow analysis for this project.

State Modular Building				Projected Cash Flow Analysis				
<b>Project Data</b>				<b>Loan Data</b>				
Project Implementation Cost*	\$	375,392		Interest Rate (annual)		2.0%		
Sales Tax	\$	32,659		Loan Period		12		
Grant or Capital Contribution	\$	-		Payments per Year		12		
Utility Incentives, Rebates, Tax Credits	\$	13,500		Total Interest Paid	\$	49,565		
Resultant Project Amount to be Financed	\$	394,551						
Amount Financed	\$	394,551						
<b>Ongoing Support Services</b>				<b>Escalation Rates</b>				
Utility Savings (annual)	\$	16,916		Utility Escalation Rate		2.0%		
Operational Savings (annual)	\$	1,500		Operational Cost Escalation Rate		2.0%		
				*excludes contingency cost				
Year	Project Savings			Project Costs			Cashflow	
	Utility	Operational	Project	Principal & Interest	Ongoing Support	Program	Annual Net	Cumulative Net
0	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1	\$ 16,916	\$ 1,500	\$ 18,416	\$ (37,010)	\$ -	\$ (37,010)	\$ (18,594)	\$ (18,594)
2	\$ 17,254	\$ 1,530	\$ 18,784	\$ (37,010)	\$ -	\$ (37,010)	\$ (18,225)	\$ (36,819)
3	\$ 17,599	\$ 1,561	\$ 19,160	\$ (37,010)	\$ -	\$ (37,010)	\$ (17,850)	\$ (54,669)
4	\$ 17,951	\$ 1,592	\$ 19,543	\$ (37,010)	\$ -	\$ (37,010)	\$ (17,466)	\$ (72,135)
5	\$ 18,310	\$ 1,624	\$ 19,934	\$ (37,010)	\$ -	\$ (37,010)	\$ (17,076)	\$ (89,211)
6	\$ 18,677	\$ 1,656	\$ 20,333	\$ (37,010)	\$ -	\$ (37,010)	\$ (16,677)	\$ (105,888)
7	\$ 19,050	\$ 1,689	\$ 20,739	\$ (37,010)	\$ -	\$ (37,010)	\$ (16,270)	\$ (122,158)
8	\$ 19,431	\$ 1,723	\$ 21,154	\$ (37,010)	\$ -	\$ (37,010)	\$ (15,855)	\$ (138,014)
9	\$ 19,820	\$ 1,757	\$ 21,577	\$ (37,010)	\$ -	\$ (37,010)	\$ (15,432)	\$ (153,446)
10	\$ 20,216	\$ 1,793	\$ 22,009	\$ (37,010)	\$ -	\$ (37,010)	\$ (15,001)	\$ (168,447)
11	\$ 20,621	\$ 1,828	\$ 22,449	\$ (37,010)	\$ -	\$ (37,010)	\$ (14,561)	\$ (183,008)
12	\$ 21,033	\$ 1,865	\$ 22,898	\$ (37,010)	\$ -	\$ (37,010)	\$ (14,112)	\$ (197,119)
13	\$ 21,454	\$ 1,902	\$ 23,356	\$ -	\$ -	\$ -	\$ 23,356	\$ (173,763)
14	\$ 21,883	\$ 1,940	\$ 23,823	\$ -	\$ -	\$ -	\$ 23,823	\$ (149,940)
15	\$ 22,320	\$ 1,979	\$ 24,300	\$ -	\$ -	\$ -	\$ 24,300	\$ (125,641)
16	\$ 22,767	\$ 2,019	\$ 24,786	\$ -	\$ -	\$ -	\$ 24,786	\$ (100,855)
17	\$ 23,222	\$ 2,059	\$ 25,281	\$ -	\$ -	\$ -	\$ 25,281	\$ (75,574)
18	\$ 23,686	\$ 2,100	\$ 25,787	\$ -	\$ -	\$ -	\$ 25,787	\$ (49,787)
19	\$ 24,160	\$ 2,142	\$ 26,303	\$ -	\$ -	\$ -	\$ 26,303	\$ (23,485)
20	\$ 24,643	\$ 2,185	\$ 26,829	\$ -	\$ -	\$ -	\$ 26,829	\$ 3,344

### Project Net Cash Flow (Cumulative Savings)

Year	Net Cash Flow	Cumulative Net
0	\$0	\$0
1	\$(18,594)	\$(18,594)
2	\$(18,225)	\$(36,819)
3	\$(17,850)	\$(54,669)
4	\$(17,466)	\$(72,135)
5	\$(17,076)	\$(89,211)
6	\$(16,677)	\$(105,888)
7	\$(16,270)	\$(122,158)
8	\$(15,855)	\$(138,014)
9	\$(15,432)	\$(153,446)
10	\$(15,001)	\$(168,447)
11	\$(14,561)	\$(183,008)
12	\$(14,112)	\$(197,119)
13	\$23,356	\$(173,763)
14	\$23,823	\$(149,940)
15	\$24,300	\$(125,641)
16	\$24,786	\$(100,855)
17	\$25,281	\$(75,574)
18	\$25,787	\$(49,787)
19	\$26,303	\$(23,485)
20	\$26,829	\$3,344



This cash flow analysis has been estimated based on the best information available at this time. The variables (taxes, interest rate, utility incentive, etc) are subject to change and will be re-evaluated at the time of proposal acceptance & contract completion.

### **5.3 Investment Summary**

#### Investment Grade Audit (IGA)

The Cost for the IGA is per Contract Agreement No. 20101-004 A (1) between the WA State Department of Enterprise Services and University Mechanical Contractors

#### Labor and Materials

Details of the Scope of Work associated with the Labor and Material Costs are provided in the Section 4.0.

#### Construction Contingency

Construction Contingency consists of three parts (1) Latent Conditions, (2) Owner Directed Contingency and (3) Design Contingency.

- 1) Latent Conditions Contingency is an allowance provided within the contract on the assumption that latent or unknown conditions do exist related to existing systems, facilities or the facility sites. The discovery of these latent conditions could not have been reasonably known prior to construction. Furthermore, the owner has disclosed all adverse conditions that are known or could be reasonably known prior to construction. These conditions may include, but are not limited to: defects, malfunctions or obsolescence in systems being modified or in supporting systems; systems and conditions required to be upgraded to meet current or new building or safety codes; defective structures; discovery of hazardous materials including asbestos; buried utilities or underground obstructions; etc. In addition, UMC reserves the right to use the contingency to fund unforeseen cost-to-capital costs. Such conditions when uncovered shall be dealt with in the course of the project and the project responses to the unknown conditions shall be treated as Change Orders.
- 2) Owner Contingency is an allowance to accommodate adjustments to scope directed by the Owner through change orders as outlined below:
  - a) Change Orders for Latent Conditions and for Owner Directed Changes requiring price adjustments, if any, shall be funded first from the Construction Contingency Allowance less the Design Contingency part to the extent of the available allowance budget and then from additional funds added to the Contract Price targeted to the Construction Contingency Allowance through the Change Order process.

- b) In addition, such changes may delay the Contract Schedule or contiguous tasks or both. The contractor shall be entitled to equitable adjustments to the schedule. Such schedule adjustments and the resultant price of such adjustments shall be included in the Change Order.
- 3) Design Contingency Allowance is used to provide small project adjustments to contract costs due to minor errors, happenstance or minor circumstances. These contingency funds are separate from all other contingency funds and are accessible solely by change order.
- 4) Increased mobilization cost associated with implementing the project in two separate phases.
- 5) Potential increases in the cost of labor & materials for the measures that will be implemented in subsequent years.

#### Re-commissioning Contingency

Re-commissioning Contingency is provided to allow for repair/replacement of control & operational issues identified during the re-commissioning process. This contingency is wholly Owner Directed.

#### Mechanical, Electrical and Plumbing Design Costs:

The following items and tasks are included in the fee:

- ✓ Conduct Design Analysis
- ✓ Evaluate Design Alternatives
- ✓ General Project Engineering
- ✓ Preliminary and Final design submittal and review
- ✓ Design documentation
- ✓ Review and selection of materials and systems

#### Construction Management / Administration:

The following items and tasks are included in the construction management / administration fee:

- ✓ General Quality Oversight
- ✓ Project Progress Reports
- ✓ Permitting Process
- ✓ Coordination with civic, county and/or federal code officials
- ✓ Subcontractor Contract Development
- ✓ Construction Administration
- ✓ Coordination with Client
- ✓ Project Accounting and Invoicing
- ✓ Commissioning Co-ordination
- ✓ Project Logs and Records
- ✓ MEP Redlines and As-Built Development
- ✓ Project Close-Out
- ✓ Release of Purchase Orders



## 6.0 MEASUREMENT & VERIFICATION

### 6.1 Summary of Total Guaranteed Savings

The tables in this section illustrate the total savings in 2012 dollars and extended over a 20 year life span. The actual savings guarantee will be in units of energy (kwh, demand kw, and gallons water). The dollars shown in these tables are calculated by applying the current rates (as shown in Section 6) to the guaranteed units of energy saved. An annual escalation rate has been applied equal to 2% for utility rates and 2% for operational costs (this is for projecting estimated annual savings only - escalation is not included in any guarantee).

Year	Annual Utility Savings	Annual Operational Savings	Cummulative Project Savings
<b>Construction</b>			
1	\$16,916	\$1,500	\$18,417
2	\$17,255	\$1,530	\$37,202
3	\$17,600	\$1,561	\$56,363
4	\$17,952	\$1,592	\$75,907
5	\$18,311	\$1,624	\$95,842
6	\$18,677	\$1,656	\$116,175
7	\$19,051	\$1,690	\$136,916
8	\$19,432	\$1,723	\$158,071
9	\$19,820	\$1,758	\$179,649
10	\$20,217	\$1,793	\$201,659
11	\$20,621	\$1,829	\$224,109
12	\$21,034	\$1,865	\$247,008
13	\$21,454	\$1,903	\$270,365
14	\$21,883	\$1,941	\$294,189
15	\$22,321	\$1,980	\$318,489
16	\$22,767	\$2,019	\$343,276
17	\$23,223	\$2,060	\$368,558
18	\$23,687	\$2,101	\$394,346
19	\$24,161	\$2,143	\$420,650
20	\$24,644	\$2,186	\$447,479

The following Table summarizes the first year savings of the Total Guaranteed Savings (Total Guaranteed Savings Summary) in Guarantee Type categories. **All guarantees are based on units of energy (not dollars).**

Proposed M&V Type				
Energy Conservation Measure	Measurement & Verification Option Proposed			
	Option A Partially Measured Retrofit Isolation	Option B Retrofit Isolation	Option C Whole Facility	Option D Calibrated Simulation
UCM 1: Lighting & Lighting Controls Upgrades	X			
UCM 2: HVAC Controls Upgrade				X
UCM 3: Energy Based Re-Commissioning	X			

The following Table illustrates the total guaranteed savings in units of energy.

Utility Conservation & Facility Upgrade Measures	Guaranteed Energy/Utility Savings				
	Electric kW/yr	Electric kWh/yr	Natural Gas therms	Water / Sewer Usage gal/yr	Sewer gal/yr
UCM 1: Lighting & Lighting Controls Upgrades	216	61,200	-	-	-
UCM 2: HVAC Controls Upgrade	-	-	1,100	-	-
UCM 3: Energy Based Re-Commissioning	-	22,853	7,704	-	-
<b>Subtotal</b>	<b>216</b>	<b>84,053</b>	<b>8,803</b>	<b>-</b>	<b>-</b>

## 6.2 Energy Guarantee

UMC is prepared to guarantee the performance of the installed measures to reduce energy consumption. The table shown in section 6.1 provides the specific energy guaranteed consumption savings for each utility conservation measure. Savings calculations are based upon both baseline operating characteristics and proposed operation criteria. These target energy savings are dependent upon the stipulated conditions as defined in the individual UCM M&V plans.

The measurement & verification plan provides the specific on-going reporting tasks that will be performed in order to verify that the UCMs are performing as specified. The intent is to measure and verify key indicators on which the energy savings are based. Once these key indicators are verified to be in accordance with the proposed criteria, the savings due to the performance of the equipment or measure shall be deemed as met. The proposed measurements for each UCM are defined in Section 6.3.



Baseline: The “baseline” refers to the current operating characteristics of the facility, system or equipment prior to the implementation of the conservation measures identified in this audit. All parties acknowledge that the baseline characteristics as identified in this audit and as associated with specific measures have been determined based on the following:

- Actual operating information gathered during this audit through field observation, site measurements, occupant interviews, trending or owner operational log books. In certain situations, this information has been used to determine stipulated factors such as occupancy schedules, typical equipment operating hours, operational expenditures, light fixture burn-hours, etc.
- Owner provided information.
- In certain instances, a modified baseline may have been developed and discussed with the owner. A modified baseline is instituted when the pre-retrofit conditions do not reflect a system that is operating per current code or per owner’s desired normally anticipated operating conditions.

Proposed: The proposed operating criteria, including system performance and operational expenditures, which were used for savings calculations are provided in Section 6 of this IGA. Systems must be operated per the proposed criteria to ensure energy cost savings are realized. UMC will provide the initial start-up and commissioning of the system to ensure that the UCMs operate per the proposed operating criteria. **The Owner acknowledges responsibility to ensure that these criteria are maintained and associated energy savings are realized. Energy Savings Guarantees are predicated based upon Owner maintaining their responsibilities as provided below in “Owner Responsibilities.”**

## 6.3 Measurement and Verification Plan

### Guarantee Savings Types

The IPMVP protocol includes four guarantee options to measure and verify savings: Option A – Partially Measured Retrofit Isolation, Option B – Retrofit Isolation, Option C – Whole Facility, and Option D – Calibrated Simulation. The following table describes these options in more detail.

M&V Option	How Savings Are Calculated	Typical Applications
<p><b>Option A. Partially Measured Retrofit Isolation</b>            This approach is intended for Facility Improvement Measures where a one-time measurement for specific equipment or systems instantaneous baseline energy use, and a one-time measurement for specific equipment or systems instantaneous post-implementation energy</p>	<p>Savings are determined by partial field measurement of the energy use of the system(s) to which an ECM was applied; separate from the energy use of the rest of the facility. Measurements may be either short-term</p>	<p>Lighting retrofit where power draw is measured periodically. Operating hours of the lights are assumed to be one half hour per day longer than store</p>

<p>use can be measured. Baseline and Post energy consumption is calculated by multiplying the measured end use instantaneous capacity (i.e. – kW, Gal/hr, BTU/hr) by stipulated hours of operation for each mode of operation (i.e. – hours, week, month).</p>	<p>or continuous. Partial measurement means that some but not all parameter(s) may be stipulated, if the total impact of possible stipulation error(s) is not significant to the resultant savings. Careful review of ECM design and installation will ensure that stipulated values fairly represent the probable actual value. Stipulations should be shown in the M&amp;V Plan along with analysis of the significance of the error they may introduce.</p>	<p>open hours.</p>
<p><b>Option B. Retrofit Isolation</b> This approach is intended for Facility Improvement Measures where continuous periodic measurements for specific equipment or systems baseline energy use, and continuous periodic measurements for that equipment or systems post-implementation energy use can be measured.</p>	<p>Savings are determined by field measurement of the energy use of the systems to which the ECM was applied; separate from the energy use of the rest of the facility. Short-term or continuous measurements are taken throughout the post-retrofit period.</p>	<p>Application of controls to vary the load on a constant speed pump using a variable speed drive. Electricity use is measured by a kWh meter installed on the electrical supply to the pump motor. In the base year this meter is in place for a week to verify constant loading. The meter is in place throughout the post-retrofit period to track variations in energy use.</p>
<p><b>Option C. Whole Facility</b> This approach is intended for measurements of the whole-facility where specific meter baseline energy use and measurements of whole-facility or specific meter post-implementation energy use can be measured.</p>	<p>Savings are determined by measuring energy use at the whole facility level. Short-term or continuous measurements are taken throughout the post-retrofit period.</p>	<p>Multifaceted energy management program affecting many systems in a building. Energy use is measured by the gas and electric utility meters for a twelve month base year period and throughout the post-retrofit period.</p>
<p><b>Option D. Calibrated Simulation</b> This approach is intended for Facility Improvement Measures where the end use capacity or operational efficiency; demand, energy consumption or power level; or</p>	<p>Savings are determined through simulation of the energy use of components or the whole facility. Simulation routines must</p>	<p>Multifaceted energy management program affecting many systems in a building but where no</p>

<p>manufacturer's measurements, industry standard efficiencies or operating hours are known in advance, and used in a calculation or analysis method that will calculate the outcome.</p>	<p>be demonstrated to adequately model actual energy performance measured in the facility. This option usually requires considerable skill in understanding facility interactions and in calibrated simulation.</p> <p>Factors that are stipulated should be shown in the M&amp;V Plan.</p>	<p>base year data are available. Post-retrofit period energy use is measured by the calibrated simulation using a model (usually Excel or whole facility model such as Trane Trace). Base year energy use is determined by simulation using a model calibrated by the post-retrofit period utility data.</p>
---	---	--

The following information outlines are applicable for this contract:

Measurement and Verification (M&V) methods provided under this Article:

- Option A – Partially Measured Retrofit Isolation
- Option B – Retrofit Isolation
- Option C – Whole Facility
- Option D – Calibrated Simulation

General Overview:

The purpose of the Measurement and Verification (M&V) Section is to identify the methods, measurements, procedures and tools that will be used to verify the savings for each ECM. Savings have been determined by comparing prior usage, consumption or efficiencies defined as the Baseline to the selected ECMs being implemented against the resulting post ECM implementation usage, consumption or efficiencies.

The baseline usage, consumption and equipment efficiencies associated with this facility is defined as the Contracted Baseline. The utility baseline for the facility and the baseline operating practices are defined in Section 3. The operating characteristics pertaining to specific equipment, systems and/or operating practices that have been used to determine the estimated savings associated with individual ECMs is described in the following M&V plan for each measure.

The actual guaranteed savings associated with this Program is outlined in the tables provided in Section 6.1.

**UCM 1.00 – Lighting & Controls Upgrade**

Proposed M&V Method – Option A: Partially Measured Retrofit Isolation

M&V Procedure

All M&V activities associated with the Project will be conducted by UMC.

An audit has been performed to determine the total number of existing fixtures at the facility, as well as identifying the type of fixture and the corresponding usage.

**Pre-Installation Measurements:** Measurements will be made of the energy usage of selected representative existing lighting systems for connected load prior to implementation of retrofit work. The wattages of these fixtures will be measured using a calibrated kW meter. This measurement will occur once prior to retrofit work.

Baseline Key Parameters	Quantity	Measured (Y/N)	Verification Method
Existing Annual Burn Hours (ABH <sub>exist</sub> )	See spreadsheet in Appendix	N	Stipulated (Estimated based on typical warehouse hours of operation and trend information)
Existing Fixture Demand (kW)	See spreadsheet in Appendix	Y	<ul style="list-style-type: none"> <li>• Measure 1 circuit serving high bay 8' T12 fixtures</li> <li>• Measure 1 circuit serving typical low bay 4' T8 32 watt fixtures</li> </ul>
Existing Number of fixtures	See spreadsheet in Appendix	N	Stipulated (Counted during lighting audit)

**Post-Installation Measurements:** One-time post-retrofit energy usage measurement will be made on the same or similar fixtures as the pre-retrofit measurements. The wattages of these fixtures will be measured using a calibrated kW meter. This measurement will occur once after completion of retrofit work.

Whenever there is a discrepancy between the energy usage (kW) utilized in the energy savings calculations and that measured in the pre- and post-retrofit measurements then either more circuits will be measured, or the difference in the energy usage will be applied to all similar fixtures that were not measured.

Annual % savings associated with reduced annual burn hours due to the implementation of lighting controls will be stipulated.

Operational savings are based on material savings only (cost of labor has not been included). These operational savings take into account the reduction in lamp & ballast replacements that will be a direct result of this UCM. Operational Savings associated with this measure will be stipulated.

Proposed Key Parameters	Quantity	Measured (Y/N)	Verification Method
Proposed Annual Burn Hours (ABH <sub>proposed</sub> )	See spreadsheet in Appendix	N	Stipulated (Estimated based on typical warehouse hours of operation and trend information)

New Fixture Demand (kW)	See spreadsheet in Appendix	Y	<ul style="list-style-type: none"> <li>Measure same high bay circuit as during pre-measurement</li> <li>Measure same low bay circuit as during pre-measurement</li> </ul>
Proposed Number of fixtures	See spreadsheet in Appendix	N	Counted during lighting audit and confirmed during commissioning
Reduction in Annual Burn Hours due to Installation of Lighting Controls	20%	N	Stipulated
Operational Savings due to Reduced Lamp/Ballast Replacements (material savings only)	See spreadsheet in Appendix	N	Stipulated

**End of Year One M&V:** None proposed

Calculations

All calculations associated with the estimated pre & post energy usage will be made according to standard engineering practice. All savings estimates are provided in the Appendix for review.

**UCM 2.00 – HVAC Controls Upgrade**

Proposed M&V Method – Option D: Calibrated Simulation (all savings associated with this measure will be stipulated)

M&V Procedure

All M&V activities associated with the Project will be conducted by UMC.

**Pre-Installation Measurements:** Confirm baseline operating schedules via BAS system. The existing baseline operating characteristics of the State Modular Building HVAC have been documented in Section 3 and in the savings calculation spreadsheet provided in the appendix.

Baseline Key Parameters	Quantity	Measured (Y/N)	Verification Method
Existing HVAC system operating schedule	See Section 3 Baseline Operating Practices (all systems currently operate 8760hrs/yr)	Y	Confirmed during pre-construction monitoring through review of current BAS operating schedule - <u>stipulated</u>



**Post-Installation Measurements:** There will be no post-installation measurements made. All savings associated with this measure are based on an industry standard savings percentage for the type of work implemented.

Proposed Key Parameters	Quantity	Measured (Y/N)	Verification Method
Proposed HVAC system operating schedule	Same as Baseline (see Section 3)	N	Schedule will be confirmed during project commissioning - <u>stipulated</u>
Annual Savings associated with Facility Heating	2.0% of total baseline heating usage	N	<u>Stipulated</u>

**End of Year One M&V:** None Proposed.

Calculations

All calculations associated with the estimated pre & post energy usage will be made according to standard engineering practice. Following final inspection and commissioning, a verification of the original savings estimate will be performed to confirm savings based on the actual installation. Savings presented in the contract documents will be stipulated throughout the duration of the contract. All savings estimates are provided in the Appendix for review.

**UCM 3.00 – Energy Based Re-Commissioning**

Proposed M&V Method – Option A: Partially Measured Retrofit Isolation

M&V Procedure

All M&V activities associated with the Project will be conducted by UMC.

**Pre-Installation Measurements:** The existing baseline operating characteristics of the State Modular Building heating system have been documented in Section 3 and in the savings calculation spreadsheet provided in the appendix. Specific variables have been measured and documented during the IGA. These variables will be stipulated for the course of the project. There are no additional measurements that will be made.

Baseline Key Parameters	Quantity	Measured (Y/N)	Verification Method
Existing HVAC system operating schedule	See Section 3 Baseline Operating Practices	Y	Confirmed during pre-construction monitoring through review of current BAS operating schedule - <u>stipulated</u>
Average Annual RTU	S1=6,175cfm	N	Estimated based on 50% of Design

Airflow	S2=8,550cfm		Airflow - <u>stipulated</u>
Average Annual RTU Airflow	S3=19,725cfm S4=23,340cfm	N	Estimated based on 75% of Design Airflow - <u>stipulated</u>
% Average RTU Airflow Supplied to HD when OAT < 60F	25%	N	Estimated based Design Airflow - <u>stipulated</u>
Average % OA for RTUs S1 & S2 from 10:00pm to 10:00am	40%	Y	Calculated based on trended RA/OA/MA temperatures obtained during IGA - <u>stipulated</u>
Average % OA for RTUs S3 & S4 from 10:00pm to 10:00am	80%	Y	Calculated based on trended RA/OA/MA temperatures obtained during IGA - <u>stipulated</u>
Average Space Temperature during Heating Mode	72	Y	Trended during IGA - <u>stipulated</u>
Average % OA provided by RTUs from 10:00am to 10:00pm	Between 0% & 5%	Y	Estimated based on trended information obtained during IGA - <u>stipulated</u>

**Post-Installation Measurements:** Short term monitoring/trending (2-4 weeks) of select system operating characteristics will be implemented to confirm that the HVAC airside system is operating as anticipated. The operating characteristics to be measured will include the following.

- Monitor RAT, OAT & MAT serving three (2) RTUs to confirm OA reduction during unoccupied periods (10 minute intervals)

In addition to the short term trending of facility operating characteristics, additional M&V will consist of confirmation/documentation of system commissioning to implement all proposed operating requirements. Future savings will be calculated with the Excel spreadsheet models that have been developed to estimate energy savings (these are included in the appendix). Proposed operating schedules (if included) have been reviewed and agreed to by the owner and will be stipulated for future operation.

Proposed Key Parameters	Quantity	Measured (Y/N)	Verification Method
Proposed HVAC system operating schedule	Same as Baseline (see Section 3)	N	Schedule will be confirmed during project commissioning - <u>stipulated</u>
Average Annual RTU Airflow	S1=8,028cfm S2=11,115cfm S3=17,095cfm S4=20,228cfm	N	Estimated based on 65% of Design Airflow - <u>stipulated</u>
% Average RTU Airflow Supplied to HD when OAT	25%	N	Estimated based Design Airflow - <u>stipulated</u>

< 60F			
Average % OA for RTUs from 10:00pm to 10:00am	5%	Y	Confirmed via post-construction monitoring of OA, RA & MA for 2 of 4 RTUs
Average Space Temperature during Heating Mode	68	N	<u>Stipulated</u>
Annual Savings associated with RTU Fan Energy Usage	27,397 kWh (5% of total baseline SF & RF motor usage)	N	<u>Stipulated</u>
Annual Savings associated with Chiller Energy Usage	5,250 kWh (5% of total baseline chiller usage)	N	<u>Stipulated</u>

**End of Year One M&V:** None Proposed.

Calculations

All calculations associated with the estimated pre & post energy usage will be made according to standard engineering practice. Following final inspection and commissioning, a verification of the original savings estimate will be performed to confirm savings based on the actual installation. Savings presented in the contract documents will be stipulated throughout the duration of the contract. All savings estimates are provided in the Appendix for review.

**6.4 Utility Rate Structure and Escalation Rates**

Utility costs used for savings calculations will be based on the utility rate in effect for the predominant bill or the utility rate in effect for the corresponding period of the Baseline period, whichever is greater. The rate, in effect during the Baseline period, will be designated the floor price, and is shown below for each utility.

Electricity		
Tariff Number or Designation:	Schedule 26 Large Demand General Service	
Utility Name:	Puget Sound Energy	
Rate Structure:	\$ 104.46	Basic Charge
Electricity	\$ 0.066949	\$ per kWh
Demand (Oct – Mar)	\$ 8.94	\$ per kW
Demand (Apr – Sep)	\$ 5.96	\$ per kW
	6%	City of Tumwater Tax Rate
<b>Total Elect Rate (including Tax)</b>	<b>\$ 0.070966</b>	<b>\$ per kWh</b>
	<b>\$ 9.48 / \$ 6.32</b>	<b>\$ per kW</b>
Blended Rate	\$ 0.0957 kWh	Average \$ per kWh <sup>1</sup>

1. Based on baseline load profile

Natural Gas		
Tariff Number or Designation:	Schedule 31	
Utility Name:	Puget Sound Energy	
Rate Structure:	\$ 33.32	Basic Charge
	\$ 0.32599	Delivery Charge - \$ per therm
	\$ 0.60040	Cost of Gas - \$ per therm
	\$ 0.04028	Gas Conservation Charge - \$ per therm
	6%	City of Tumwater Tax Rate
	<b>\$ 1.0247</b>	<b>Total Gas Cost - \$ per therm</b>

## 6.5 Applicable Codes

Federal, State, and Local codes or regulations are applicable to the use and operation of the facility. All work installed under this project will meet the requirements of the following codes:

- The International Building Code and appendices thereto pertaining to building accessibility, not including the adoption of the incorporated electrical codes, plumbing codes, fire codes or property maintenance codes other than specifically referenced subjects or sections of the International Fire Code, but including the incorporated International Residential Code; International Mechanical Code; International Fuel Gas Code; International Energy Conservation Code.
- The Washington State Energy Code
- The Uniform Mechanical Code
- The Uniform Code for Building Conservation
- The Safety Code for Elevators and Escalators (ASME/ANSI A 17-.1)
- The NEC
- The NFPA Fire Alarm Systems
- The NFPA 13 Fire Sprinkler Systems
- The Uniform Plumbing Code
- The Washington State Ventilation and Indoor Air Quality Code
- All applicable local city codes

UMC is not responsible for the code compliance of systems not installed under this project.

## 6.6 M&V Costs

The cost for the first 12 months of M&V reporting is included in the project implementation cost.

The owner has the option to continue M&V and associated energy guarantees for the subsequent years at the prices shown below (including a labor escalation rate of 4%). To elect this option owner shall provide written notification to UMC one month after the end of the prior period. In the event this option is not elected for a particular year, it may not be elected in subsequent years. UMC's ongoing fee for M&V for years 2 through 4 is shown below.

Year	Annual M&V Cost
1	(1)
2	\$4,600
3	\$4,784
4	\$4,975

(1) Included in project cost

## 6.7 M&V Reporting

UMC will provide a commissioning report to the Owner within 90 days of completion of the project.

At the completion of the 12 months of energy savings, UMC will provide the first year of reporting within 90 days of this date.

Ongoing M&V reporting beyond year one is not included as part of this proposal. The annual cost for the continued M&V is shown above and can be opted for continuation by the Owner. The savings guarantee associated with this project will only continue past year one as long as the Owner includes the continuation of M&V services as defined herein.

## 6.8 Owner Responsibilities

This section details the responsibilities the Owner, in connection with the management and administration of the Performance Guarantee. UMC is not responsible for increased energy or operational issues that result from items beyond



its control or in the event that the Owner fails to comply with the following requirements.

- The Owner will provide a representative at each facility to coordinate work and provide required data described below. Owner will provide access to all spaces required for pre measurement and post measurement. At the Owner's discretion, one representative will witness all pre and post measurements. UMC will provide calibration reports on all meters as required by the Owner.
- The Owner will provide UMC with accurate facility operating information, as defined below, and in the Contracted Baseline article of this Section during each Annual Period, as soon as such information becomes available to the Owner.
- Owner will provide UMC with copies of utility bills within 7 days of receipt by Owner or provide access to utility vendor information.
- Owner will provide telephone/data remote access as UMC reasonably requests. All charges related to telephone/data line installation, activation and communication services are the responsibility of the Owner.
- Owner will be responsible for notification of UMC regarding schedule changes of the air handling systems associated with this measure. Owner will be responsible for maintaining proposed schedules and setback temperatures. If, for any reason, schedules or setback temperatures must change, Owner will be responsible to make UMC aware of the change.
- Owner will maintain all proposed operating schedules as defined in this proposal and as discussed during training. UMC cannot be responsible for excess energy usage that occurs due to atypical operating hours that are the result of equipment overrides, failure to maintain vacation/holiday scheduling or changes in building use or operating characteristics beyond that as identified during the development of the IGA.
- Owner will provide equipment service and preventative maintenance to keep all equipment installed as part of this project operating efficiently. This includes all service & maintenance as defined in equipment O&M & warranty documents and as discussed during training. Equipment must be maintained in peak operating condition to provide ongoing efficient operation in a manner to meet the savings estimates set forth in this document. Unless otherwise contracted, UMC will provide no additional equipment maintenance or repairs outside of the warranty period
- Owner agrees that the existing operating schedules and equipment conditions, as provided in this IGA, are complete and correct. If, for any

reason, the Owner requires that the equipment be operated in excess of the proposed schedules, UMC will not be responsible for resulting increased energy usage.

- During the performance guarantee period, any post-retrofit changes made by the Owner that may affect the baseline data (i.e., new construction, additional electrical loads, manual control of automatic devices, etc.) shall be reported to UMC so that adjustments can be made to reflect the changes and proper adjustments to the savings guarantees can be made.
- UMC will provide an operations and maintenance manual. Upkeep of the equipment installed as part of this project is the responsibility of the Owner's maintenance personnel. Any loss of efficiency that occurs to the installed equipment caused by a lack of ongoing maintenance or upkeep shall be taken into account and appropriate impact to annual savings adjusted.
- Owner must make every effort to make sure that all appropriate personnel attend equipment/system training provide by UMC during the implementation of this project. These training sessions will be scheduled with the Owner to make sure they are held during a period when appropriate personnel can attend.

## **Section 6.9 On-Going Space Operating Conditions**

The following section provides the space conditions that Owner must maintain to ensure the comfort of the building occupants. These conditions also provide the basis upon which all energy savings calculations have been made. Deviations beyond these conditions that are made at the discretion of the Owner could negatively affect the ongoing savings performance of this project.

HVAC Operating Criteria: Heating, ventilating, and air conditioning (HVAC) systems provided as a part of this project will provide space conditions in accordance with the Standards of Comfort described below. This standard will pertain only to buildings and areas of buildings that are directly affected by measures implemented in this project and under which this HVAC equipment has direct control over space comfort conditions. HVAC comfort conditions cannot be guaranteed when operable windows or doors are open.

### Space Conditions:

#### Occupied:

- Office:
  - Heating Set Point - 68 degrees F
  - Cooling Set Point - 78 degrees F (where mechanical cooling systems are employed)
- Warehouse:

- Heating Set Point - 65 degrees F
- Cooling Set Point - 70 degrees F (where mechanical cooling systems are employed)
- 30% - 50% RH (as capable of being maintained with current HVAC system)

Unoccupied:

- Office:
  - Minimum - 55 degrees F
  - Maximum - 90 degrees F (where mechanical cooling systems are employed)
- Warehouse:
  - Minimum - 65 degrees F
  - Maximum - 70 degrees F (where mechanical cooling systems are employed)
  - 30% - 50% RH (as capable of being maintained with current HVAC system)

Minimum outside air per occupant:

- In accordance with ANSI/ASHRAE Standard 62.1-2007, standards and the International Mechanical Code as adopted by the Washington State Building Code Council effective July 1 2010.


HVAC Equipment Operating Hours:

- The operating schedules for the equipment installed as a part of this project will remain the same as the original baseline operating schedule unless schedule changes have been proposed and implemented as a part of this project.

## 7.0 IMPLEMENTATION PLAN

### 7.1 Project Schedule

A preliminary project schedule for the State Modular Building ESPC project milestones is shown below.



---

## **8.0 APPENDIX**

---



# UCM 1.0 Lighting & Lighting Controls Upgrades - Energy Savings Estimates

Project Name	State Modular Building			Facility Contact	Scott Locke UMC			Auditor(s)	Mike Campbell		NWE Contact Phone	(509) 680-3963						
	Address	7580 New Market St SW			Building Contact	(206) 295-3214			Audit Date	Office Phone #		(425) 806-9200						
		City	Tumwater			Phone	Ext.			Last Revised	Office Fax #		(425) 806-7455					
			State				Washington				Tax Rate	0.00%	Facility Type	Heat		Utility	Puget Sound Energy	kWh Rate
County	Thurston	Zip Code	98501	Sq. Feet	AC		Lamp Replace Group Spot	Ballast Replace PCB/Percent		Second Tier Start Level		0.0000						

ECM #	Location	Fixture Qty	Fixture ID	Existing / Proposed Fixture Description	Lamp Watt	Fixture Watt	Fixture Heig	Hours/Day	Days/Week	FC	Sensor Qty	Sensor / Power Pat	Energy Save	Sensor Heig	Survey Notes
1	Entry / Reception	3	EFMV100	Existing Fixture Mercury Vapor 100 watt Lamp	100	125		9	5						use 841 lamps unless specified
	Entry / Reception	3	CFLR32	Retrofit HID with 32 watt CFL Lamp and Ballast	32	32		9	5						
2	Entry / Reception	12	ECFL32	Existing 32 watt CFL Lamp	32	32		9	5						leave as is
	Entry / Reception	12	ECFL32	Existing 32 watt CFL Lamp	32	32		9	5						
3	Entry / Reception	2	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5						3L ballast existing has one lamp removed
	Entry / Reception	2	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		9	5						
4	Entry / Reception	1	ET217N	Existing Troffer 2x2 2L F17 T8, NBF Ballast	17	33		9	5						relamp for color
	Entry / Reception	1	RL217N	Relamp with 2 F17 T8 Lamps	17	33		9	5						
5	Conf 115	7	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5						
	Conf 115	7	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5						
6	101 Office	7	ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5						
	101 Office	7	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5						
7	Shop Area - Under Mezz	34	ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	32	112		16	5	35					850. lots of end caps missing. 11 burned out lamps
	Shop Area - Under Mezz	34	LB428N	Lamp And Ballast Retrofit w 4 F32 28 watt Lamp, NBF Ballast	28	96		16	5						
8	Production Manager Office	5	EW4332N	Existing Wrap T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5		1.00	WSDPDT2P	20%		
	Production Manager Office	5	WK4228NP	Wrap Kit with Reflector 4' 2L F32 T8 28 watt Lamps, PRS NBF Ballast	28	48		9	5				20%		
9	Closet	1	EW4232N	Existing Wrap T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5						
	Closet	1	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		2	5						
10	Mezzanine	29	ES8232N	Existing Strip T8 8' w 2 F32 32 watt Lamp, NBF Ballast	32	58		16	5						850
	Mezzanine	29	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		16	5						
11	Rest of Production Area	152	ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	32	112	25.0 ft	16	5						217 lamps burned out. 850
	Rest of Production Area	152	LB428N	Lamp And Ballast Retrofit w 4 F32 28 watt Lamp, NBF Ballast	28	96	25.0 ft	16	5						
12	Rest of Production Area - Over Machine	5	ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	32	112	14.0 ft	16	5						
	Rest of Production Area - Over Machine	5	LB428H	Lamp And Ballast Retrofit w 4 F32 28 watt Lamp, HBF Ballast	28	130	14.0 ft	16	5						
13	Rest of Production Area - Over Machine	4	ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		16	5						850
	Rest of Production Area - Over Machine	4	TK4228H	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, HBF Ballast	28	65		16	5						
14	Rest of Production Area - Over Machine	8	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		16	5						
	Rest of Production Area - Over Machine	8	LB228H	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, HBF Ballast	28	65		16	5						
15	Rest of Production Area - Over Machine	31	ES8296H	Existing Strip 8' 2 Lamp P96 T12 HO Ballast	95	221		16	5						850
	Rest of Production Area - Over Machine	31	SKR8428H4	Strip Kit with Reflector 8' w 4 F32 28 watt Lamp, HBF Ballast 4.25' Brackets	28	130		16	5						
16	Rest of Production Area - Over Machine	1	EW4432N	Existing Wrap T8 4' w 4 F32 32 watt Lamp, NBF Ballast	32	112		16	5						850. no cover
	Rest of Production Area - Over Machine	1	WK4228H	Wrap Kit with Reflector 4' 2L F32 T8 28 watt Lamps, HBF Ballast	28	65		16	5						
17	Rest of Production Area	4	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		16	5						
	Rest of Production Area	4	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		16	5						
18	Rest of Production Area	2	ET217N	Existing Troffer 2x2 2L F17 T8, NBF Ballast	17	33		16	5						
	Rest of Production Area	2	RL217N	Relamp with 2 F17 T8 Lamps	17	33		16	5						
19	Rest of Production Area	6	ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	32	112	14.0 ft	16	5						850. against wall - walkway
	Rest of Production Area	6	LB428N	Lamp And Ballast Retrofit w 4 F32 28 watt Lamp, NBF Ballast	28	96	14.0 ft	16	5						

20	E	Room 209 - Press Supervisor	2	ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	Room 209 - Press Supervisor	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
21	E	208 Bindery Office	4	ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	208 Bindery Office	4	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
22	E	207 Office	2	ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	207 Office	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
23	E	301 Electrical	2	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	301 Electrical	2	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		2	5								
24	E	302 Telephone Room	2	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	302 Telephone Room	2	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		2	5								
25	E	119 Womens RR	5	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5		1.00	WSDPDTI	20%				
	P	119 Womens RR	5	LB228LP	Lamp and Ballast Retrofit 2L F32 T8 28 watt Lamps, PRS LBF Ballast	28	42		9	5					20%			
26	E	201 Office	4	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	201 Office	4	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
27	E	202 Server Room	6	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	202 Server Room	6	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		2	5								
28	E	305 Electrical	4	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	305 Electrical	4	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		2	5								
29	E	210 Press Room	8	ES4248H	Existing Strip 4' 2 Lamp F48 T12 HO Ballast	60	133		16	5								850
	P	210 Press Room	8	NVS4328H	New V-Strip Fixture 4' 3L F32 T8 28 watt Lamps, High BF Ballast	28	99		16	5								
30	E	210 Press Room	3	ES8296H	Existing Strip 8' 2 Lamp F96 T12 HO Ballast	95	221		16	5								
	P	210 Press Room	3	SKR8428H4	Strip Kit with Reflector 8' w 4 F32 28 watt Lamp, HBF Ballast 4.25' Brackets	28	130		16	5								
31	E	210 Press Room	1	ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	32	112		16	5								850
	P	210 Press Room	1	LB428N	Lamp And Ballast Retrofit w 4 F32 28 watt Lamp, NBF Ballast	28	96		16	5								
32	E	Mezzanine	9	ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	32	112		16	5								850
	P	Mezzanine	9	LB428N	Lamp And Ballast Retrofit w 4 F32 28 watt Lamp, NBF Ballast	28	96		16	5								
33	E	307 Vault	8	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	307 Vault	8	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
34	E	Mezz Above Vault	3	ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	32	112		9	5								
	P	Mezz Above Vault	3	LB428N	Lamp And Ballast Retrofit w 4 F32 28 watt Lamp, NBF Ballast	28	96		9	5								
35	E	Chemical Room	1	EINC100	Existing Incandescent 100 watt Lamp	100	100		9	5								explosion proof
	P	Chemical Room	1	CFLR32	Retrofit HID with 32 watt CFL Lamp and Ballast	32	32		9	5								
36	E	309 Area	7	ES8232N	Existing Strip T8 8' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5	25							850
	P	309 Area	7	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
37	E	313 Locked Room	2	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	313 Locked Room	2	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
38	E	312 Locked Room	2	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	312 Locked Room	2	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
39	E	311	4	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	311	4	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								



60	E	1104D	4	ET432N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	1104D	4	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
61	E	200 Facilities Office	2	ET432N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	200 Facilities Office	2	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
62	E	Telephone Room	1	ES4132N	Existing Strip T8 4' w 1 F32 32 watt Lamp, NBF Ballast	32	32		2	5								
	P	Telephone Room	1	LB128L	Lamp And Ballast Retrofit w 1 F32 28 watt Lamp, LBF Ballast	28	22		2	5								
63	E	100	105	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	100	105	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
64	E	109 HR Office	4	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	109 HR Office	4	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
65	E	108 Conf	6	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	108 Conf	6	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
66	E	107 Office	4	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	107 Office	4	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
67	E	106 Office	2	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	106 Office	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
68	E	105 Office	2	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	105 Office	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
69	E	104 Office	2	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	104 Office	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
70	E	103 Office	4	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	103 Office	4	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
71	E	102 Office	2	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	102 Office	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
72	E	101 Office	2	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	101 Office	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
73	E	300 Admin Supply	2	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		2	5								
	P	300 Admin Supply	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		2	5								
74	E	113 Office	2	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	113 Office	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
75	E	114 Office	2	ET432N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	114 Office	2	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
76	E	Front of Main Shop - Halls	41	ET432N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	Front of Main Shop - Halls	41	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		9	5								
77	E	Front of Main Shop - Halls	10	ET2217N	Existing Troffer 2x2 2L F17 T8, NBF Ballast	17	33		9	5								
	P	Front of Main Shop - Halls	10	RL217N	Relamp with 2 F17 T8 Lamps	17	33		9	5								
78	E	Front of Main Shop - Halls	6	ECFL32	Existing 32 watt CFL Lamp	32	32		9	5								
	P	Front of Main Shop - Halls	6	ECFL32	Existing 32 watt CFL Lamp	32	32		9	5								
79	E	Front of Main Shop - Halls	3	EFMV100	Existing Fixture Mercury Vapor 100 watt Lamp	100	125		9	5								
	P	Front of Main Shop - Halls	3	CFLR32	Retrofit HID with 32 watt CFL Lamp and Ballast	32	32		9	5								

80	E	Telephone Room	1	ES4132N	Existing Strip T8 4' w 1 F32 32 watt Lamp, NBF Ballast	32	32		2	5								
	P	Telephone Room	1	LB128L	Lamp And Ballast Retrofit w 1 F32 28 watt Lamp, LBF Ballast	28	22		2	5								
81	E	Main Telephone Room	1	ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	Main Telephone Room	1	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		2	5								
82	E	Main Electrical	2	ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	Main Electrical	2	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		2	5								
83	E	705 Sprinkler Room	1	ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	705 Sprinkler Room	1	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		2	5								
84	E	507 Mens RR	4	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5		1.00	WSDPDTI	20%				
	P	507 Mens RR	4	LB228LP	Lamp and Ballast Retrofit 2L F32 T8 28 watt Lamps, PRS LBF Ballast	28	42		9	5					20%			
85	E	702 Fire Alarm Room	2	ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	702 Fire Alarm Room	2	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		2	5								
86	E	506 Womens RR	4	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5		1.00	WSDPDTI	20%				
	P	506 Womens RR	4	LB228LP	Lamp and Ballast Retrofit 2L F32 T8 28 watt Lamps, PRS LBF Ballast	28	42		9	5					20%			
87	E	504 Cafeteria	12	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	504 Cafeteria	12	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		9	5								
88	E	707 Conf	12	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	707 Conf	12	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
89	E	708 6A Storage	10	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	708 6A Storage	10	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		2	5								
90	E	Telephone Room	1	ES4132N	Existing Strip T8 4' w 1 F32 32 watt Lamp, NBF Ballast	32	32		2	5								
	P	Telephone Room	1	LB128L	Lamp And Ballast Retrofit w 1 F32 28 watt Lamp, LBF Ballast	28	22		2	5								
91	E	Mech to left	1	ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5								
	P	Mech to left	1	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		2	5								
92	E	710 Fulfillment	135	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								
	P	710 Fulfillment	135	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
93	E	710 Fulfillment	29	ET2217N	Existing Troffer 2x2 2L F17 T8, NBF Ballast	17	33		9	5								
	P	710 Fulfillment	29	RL217N	Relamp with 2 F17 T8 Lamps	17	33		9	5								
94	E	710 Fulfillment	58	ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	710 Fulfillment	58	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
95	E	715	6	ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	715	6	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
96	E	714 in 710	6	ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	32	85		9	5								
	P	714 in 710	6	TK4228N	Troffer Kit with Reflector 4' w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
97	E	Telephone Room A back in Hall	1	ES4132N	Existing Strip T8 4' w 1 F32 32 watt Lamp, NBF Ballast	32	32		2	5								
	P	Telephone Room A back in Hall	1	LB128L	Lamp And Ballast Retrofit w 1 F32 28 watt Lamp, LBF Ballast	28	22		2	5								
98	E	500 Info Doc Service	113	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5								850, except 4 over cubes get 841
	P	500 Info Doc Service	113	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5								
99	E	500 Info Doc Service	8	ET2217N	Existing Troffer 2x2 2L F17 T8, NBF Ballast	17	33		9	5								
	P	500 Info Doc Service	8	RL217N	Relamp with 2 F17 T8 Lamps	17	33		9	5								

100	E	501 Office	6	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5							
	P	501 Office	6	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5							
101	E	502 Mens RR (back in hall)	3	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5		1.00	WSPDPTI	20%			
	P	502 Mens RR (back in hall)	3	LB228LP	Lamp and Ballast Retrofit 2L F32 T8 28 watt Lamps, PRS LBF Ballast	28	42		9	5				20%			
102	E	503 Womens RR	3	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5		1.00	WSPDPTI	20%			
	P	503 Womens RR	3	LB228LP	Lamp and Ballast Retrofit 2L F32 T8 28 watt Lamps, PRS LBF Ballast	28	42		9	5				20%			
103	E	700 State Library	110	ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		9	5							
	P	700 State Library	110	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		9	5							
104	E	700 State Library	1	ET217N	Existing Troffer 2x2 2L F17 T8, NBF Ballast	17	33		9	5							
	P	700 State Library	1	RL217N	Relamp with 2 F17 T8 Lamps	17	33		9	5							
105	E	700A Electrical	2	ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5							
	P	700A Electrical	2	LB228N	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, NBF Ballast	28	48		2	5							
106	E	700B Custodian	1	ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	32	58		2	5							
	P	700B Custodian	1	LB228L	Lamp And Ballast Retrofit w 2 F32 28 watt Lamp, LBF Ballast	28	42		2	5							
	E	<b>Existing Fixture Total</b>	<b>1,254</b>														
	P	<b>Proposed Fixture Total</b>	<b>1,247</b>										<b>Sensor Total</b>	<b>7</b>			

### Project Analysis for State Modular Building

#### Energy Analysis

Existing System Baseline	283,234 kWh / Yr.
Energy Efficient System	215,256 kWh / Yr.
Energy Reduction	24.00%
Annual Energy Savings	67,978 kWh / Yr.

### Maintenance Savings Calculations

Code	Description	Qty	Lamps	Type	Lamp Watts	Input Watts	Lamp Life	Annual Hours	Lamp Changes Per Year	Retail Price	Lamps x Cost	Year 1 Lamp Replacement Costs	Year 2 Lamp Replacement Costs	Year 3 Lamp Replacement Costs	Year 4 Lamp Replacement Costs	Year 5 Lamp Replacement Costs
ECFL32	Existing 32 watt CFL Lamp	18	1	CFL	32	32	10,000	2,340	4.21	\$5.00	\$21.06	\$21.06	\$21.69	\$22.34	\$23.01	\$23.70
ET217N	Existing Troffer 2x2 2L F17 T8, NBF Ballast	51	2	T8	17	33	20,000	2,340	5.97	\$4.00	\$8.00	\$47.74	\$49.17	\$50.64	\$52.16	\$53.73
ET223N	Existing Troffer 2x2 2L F32 T8 U-Tube Lamps, NBF Ballast	6	2	T8	32	58	20,000	2,340	0.70	\$4.00	\$8.00	\$5.62	\$5.78	\$5.96	\$6.14	\$6.32
ES4248H	Existing Strip 4' 2 Lamp F48 T12 HO Ballast	8	2	F	60	133	20,000	4,160	1.66	\$4.00	\$8.00	\$13.31	\$13.71	\$14.12	\$14.55	\$14.98
ES8260N	Existing Strip 8' 2 Lamp F96 60 watt Lamp T12 Standard Ballast	2	2	F	60	138	20,000	2,340	0.23	\$4.00	\$8.00	\$1.87	\$1.93	\$1.99	\$2.05	\$2.11
ES8296H	Existing Strip 8' 2 Lamp F96 T12 HO Ballast	34	2	F	95	221	20,000	4,160	7.07	\$4.00	\$8.00	\$56.58	\$58.27	\$60.02	\$61.82	\$63.68
EINCB0	Existing Incandescent 60 watt Lamp	11	1	INC	60	60	1,000	2,340	25.74	\$2.00	\$2.00	\$51.48	\$53.02	\$54.62	\$56.25	\$57.94
EINC100	Existing Incandescent 100 watt Lamp	1	1	INC	100	100	1,000	2,340	2.34	\$2.00	\$2.00	\$4.68	\$4.82	\$4.97	\$5.11	\$5.27
EFMV100	Existing Fixture Mercury Vapor 100 watt Lamp	6	1	MV	100	125	20,000	2,340	0.70	\$23.00	\$23.00	\$16.15	\$16.63	\$17.13	\$17.64	\$18.17
ES4132N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	4	1	F	32	32	20,000	520	0.10	\$4.00	\$4.00	\$0.42	\$0.43	\$0.44	\$0.45	\$0.47
ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	19	2	F	32	58	20,000	520	0.49	\$4.00	\$8.00	\$3.95	\$4.07	\$4.19	\$4.32	\$4.45
ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	608	2	F	32	58	20,000	2,340	71.14	\$4.00	\$8.00	\$569.09	\$586.16	\$603.75	\$621.86	\$640.51
ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	228	3	F	32	85	20,000	2,340	26.68	\$4.00	\$12.00	\$320.11	\$329.72	\$339.61	\$349.80	\$360.29
EW4432N	Existing Wrap T8 4' w 2 F32 32 watt Lamp, NBF Ballast	1	2	F	32	58	20,000	520	0.03	\$4.00	\$8.00	\$0.21	\$0.21	\$0.22	\$0.23	\$0.23
EW4432N	Existing Wrap T8 4' w 3 F32 32 watt Lamp, NBF Ballast	5	3	F	32	85	20,000	2,340	0.59	\$4.00	\$12.00	\$7.02	\$7.23	\$7.45	\$7.67	\$7.90
EW4432N	Existing Wrap T8 4' w 4 F32 32 watt Lamp, NBF Ballast	1	4	F	32	112	20,000	4,160	0.21	\$4.00	\$16.00	\$3.33	\$3.43	\$3.53	\$3.64	\$3.75
ES8232N	Existing Strip T8 8' w 2 F32 32 watt Lamp, NBF Ballast	36	2	F	32	58	20,000	2,340	4.21	\$4.00	\$8.00	\$33.70	\$34.71	\$35.75	\$36.82	\$37.93
ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	215	4	F	32	112	20,000	2,340	25.16	\$4.00	\$16.00	\$402.48	\$414.55	\$426.99	\$439.80	\$452.99
												\$1,558.78	\$1,605.54	\$1,653.71	\$1,703.32	\$1,754.42


Code	Description	Qty	Ballasts	Type	Lamp Watts	Input Watts	Ballast Life	Annual Hours	Ballast Changes Per Year	Retail Price	Ballasts x Cost	Year 1 Ballast Replacement Costs	Year 2 Ballast Replacement Costs	Year 3 Ballast Replacement Costs	Year 4 Ballast Replacement Costs	Year 5 Ballast Replacement Costs
ECFL32	Existing 32 watt CFL Lamp	18	1	CFL	32	32	50,000	2,340	0.84	\$20.00	\$20.00	\$16.85	\$17.35	\$17.87	\$18.41	\$18.96
ET217N	Existing Troffer 2x2 2L F17 T8, NBF Ballast	51	2	T8	17	33	60,000	2,340	1.99	\$11.00	\$22.00	\$43.76	\$45.07	\$46.42	\$47.82	\$49.25
ET223N	Existing Troffer 2x2 2L F32 T8 U-Tube Lamps, NBF Ballast	6	2	T8	32	58	60,000	2,340	0.23	\$11.00	\$22.00	\$5.15	\$5.30	\$5.46	\$5.63	\$5.79
ES4248H	Existing Strip 4' 2 Lamp F48 T12 HO Ballast	8	2	F	60	133	60,000	4,160	0.55	\$25.00	\$50.00	\$27.73	\$28.57	\$29.42	\$30.30	\$31.21
ES8260N	Existing Strip 8' 2 Lamp F96 60 watt Lamp T12 Standard Ballast	2	2	F	60	138	60,000	2,340	0.08	\$25.00	\$50.00	\$3.90	\$4.02	\$4.14	\$4.26	\$4.39
ES8296H	Existing Strip 8' 2 Lamp F96 T12 HO Ballast	34	2	F	95	221	60,000	4,160	2.36	\$25.00	\$50.00	\$117.87	\$121.40	\$125.04	\$128.80	\$132.66
EFMV100	Existing Fixture Mercury Vapor 100 watt Lamp	6	1	MV	100	125	60,000	2,340	0.23	\$65.00	\$65.00	\$15.21	\$15.67	\$16.14	\$16.62	\$17.12
ES4132N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	4	1	F	32	32	60,000	520	0.03	\$11.00	\$11.00	\$0.38	\$0.39	\$0.40	\$0.42	\$0.43
ES4232N	Existing Strip T8 4' w 2 F32 32 watt Lamp, NBF Ballast	19	2	F	32	58	60,000	520	0.16	\$11.00	\$22.00	\$3.62	\$3.73	\$3.84	\$3.96	\$4.08
ET4232N	Existing Troffer T8 4' w 2 F32 32 watt Lamp, NBF Ballast	608	2	F	32	58	60,000	2,340	23.71	\$11.00	\$22.00	\$521.66	\$537.31	\$553.43	\$570.04	\$587.14
ET4332N	Existing Troffer T8 4' w 3 F32 32 watt Lamp, NBF Ballast	228	3	F	32	85	60,000	2,340	8.89	\$11.00	\$33.00	\$293.44	\$302.24	\$311.31	\$320.65	\$330.26
EW4432N	Existing Wrap T8 4' w 2 F32 32 watt Lamp, NBF Ballast	1	2	F	32	58	60,000	520	0.01	\$11.00	\$22.00	\$0.19	\$0.20	\$0.20	\$0.21	\$0.21
EW4432N	Existing Wrap T8 4' w 3 F32 32 watt Lamp, NBF Ballast	5	3	F	32	85	60,000	2,340	0.20	\$11.00	\$33.00	\$6.44	\$6.63	\$6.83	\$7.03	\$7.24
EW4432N	Existing Wrap T8 4' w 4 F32 32 watt Lamp, NBF Ballast	1	4	F	32	112	60,000	4,160	0.07	\$11.00	\$44.00	\$3.05	\$3.14	\$3.24	\$3.33	\$3.43
ES8232N	Existing Strip T8 8' w 2 F32 32 watt Lamp, NBF Ballast	36	2	F	32	58	60,000	2,340	1.40	\$11.00	\$22.00	\$30.89	\$31.81	\$32.77	\$33.75	\$34.76
ES8432N	Existing Strip T8 8' w 4 F32 32 watt Lamp, NBF Ballast	215	4	F	32	112	60,000	2,340	8.39	\$11.00	\$44.00	\$368.94	\$380.01	\$391.41	\$403.15	\$415.25
												\$1,459.07	\$1,502.84	\$1,547.93	\$1,594.37	\$1,642.20


Year	1	2	3	4	5
Annual Savings =	\$3,017.85	\$3,108.39	\$3,201.64	\$3,297.69	\$3,396.62



## UCM 2.0 HVAC Controls Upgrade - Energy Savings Estimates

<b>Energy Savings Estimate</b>						
<b>Overview:</b>						
Implement RCx on primary HVAC systems (HW, CHW, RTUs)						
<b>Notes:</b>						
Savings Calculations						
		<b>Baseline Operation</b>		<b>Annual Savings</b>		
		<b>Annual kWh</b>	<b>Annual Therms</b>	<b>% Savings</b>	<b>kWh</b>	<b>Therms</b>
	HW Heating		61120	2%	-	1,222
					-	-
	Subtotal	-			-	1,222
<b>Assumptions:</b>						
HVAC system currently operates 24/7.						
Unoccupied setback is not currently occupied in any location within the facility						
RCx commissioning will result in a minimum average savings of 5% of current usage on chillers						
RCx commissioning will result in a minimum average savings of 5% of current usage on fan motor operation of all 4 RTUs						
<b>Estimated Annual Savings:</b>						
	Gas Savings =	1,222	therms			
	Elect Savings =	-				
	Water Savings =					
	Sewer Savings =					
	Cost Savings (\$) =	\$	-			
<b>Utility Information:</b>						
	Electrical Cost (\$/kwh) =			Water Cost (\$/kgal) =		
	Heating Cost (\$/therm) =			Sewer Cost (\$/kgal) =		
 <b>UNIVERSITY MECHANICAL CONTRACTORS, INC.</b> <i>We Build Value</i>		<b>Project:</b>	State Modular Building		<b>Job #:</b>	
		<b>Subject:</b>	ECM-2: HVAC Controls Upgrade		<b>Date:</b> 10/30/2012	
					<b>By:</b> SRL	
					<b>Page:</b>	

## UCM 3.0 Energy Based Re-Commissioning - Energy Savings Estimates

Energy Savings Estimate				
<b>Overview:</b>				
Implement RCx on primary HVAC systems (HW, CHW, RTUs)				
<b>Notes:</b>				
Modify control sequence to reduce OA at night to minimum OA at all times. The RTUs currently modulate to full OA during these periods.				
Savings Calculations				
	<b>Annual</b>	<b>Existing Annual Heating</b>	<b>Proposed Annual Heating</b>	<b>Estimated Annual Savings</b>
<b>OAT</b>	<b>Hours</b>	<b>(therms)</b>	<b>(therms)</b>	<b>(therms)</b>
57.5	774	1,528	109	1,418
52.5	816	2,165	155	2,010
47.5	781	2,604	187	2,418
42.5	641	2,575	184	2,390
37.5	391	1,835	131	1,704
32.5	140	750	54	697
27.5	35	209	15	194
22.5	15	98	7	91
17.5	11	78	6	72
12.5	2	12	1	11
<b>Subtotal</b>	<b>3,602</b>	<b>11,854</b>	<b>849</b>	<b>11,005</b>
<b>Assumptions:</b>				
HVAC system currently operates 24/7.				
Unoccupied setback is not currently occupied in any location within the facility				
Total Avg Annual RTU cfm (total of 2 High Bay RTUs) =			43,065	cfm
Total Avg Annual RTU cfm (total of 2 Low Bay RTUs) =			14,725	cfm
% Avg RTU cfm supplied to HD =			25%	
<b>High Bay Units:</b>				<b>High Bay Units:</b>
RTU control dampers currently modulate to	80%	OA at ~ 10:00pm each night		Design cfm (total 2 HB RTUs) = 57,420
Amount of OA provided by RTUs during daytime	0%	OA at ~ 10:00am each morning		Average VFD Speed = 75%
<b>Low Bay Units:</b>				<b>Low Bay Units:</b>
RTU control dampers currently modulate to	40%	OA at ~ 10:00pm each night		Design cfm (total 2 HB RTUs) = 29,450
Amount of OA provided by RTUs during daytime	0%	OA at ~ 10:00am each morning		Average VFD Speed = 50%
Average Space Temperature (heating) =		72	F	
Heating System Efficiency =		80%		
RTU control dampers proposed to modulate to	5%	OA during unoccupied periods (night)		Minimum Design OA (all 4 RTUs) = 10,700
<b>Estimated Annual Savings:</b>				
<b>Gas Savings =</b>	<b>11,005</b>	<b>therms</b>		
<b>Elect Savings =</b>				
<b>Water Savings =</b>				
<b>Sewer Savings =</b>				
<b>Cost Savings (\$) =</b>	<b>\$</b>	<b>-</b>		
<b>Utility Information:</b>				
Electrical Cost (\$/kwh) =		Water Cost (\$/kgal) =		
Heating Cost (\$/therm) =		Sewer Cost (\$/kgal) =		
		<b>Project:</b> State Modular Building	<b>Job #:</b>	
			<b>Date:</b> 10/30/2012	
		<b>Subject:</b> ECM-3: Energy Based Re-Commissioning	<b>By:</b> SRL	
			<b>Page:</b>	

**Energy Savings Estimate**

**Overview:**

Implement RCx on primary HVAC systems (HW, CHW, RTUs)

**Notes:**

Savings associated with main RTU average fan speed reduction & reducing reduction in chiller operation.

Savings Calculations

	Baseline Operation		% Savings	Annual Savings	
	Annual kWh	Annual Therms		kWh	Therms
RTU Fans	547,901		5%	27,395	-
Chillers	105,000		5%	5,250	-
<b>Subtotal</b>	<b>652,901</b>			<b>32,645</b>	

**Assumptions:**

HVAC system currently operates 24/7.

Unoccupied setback is not currently occupied in any location within the facility

RCx commissioning will result in a minimum average savings of 5% of current usage on chillers


RCx commissioning will result in a minimum average savings of 5% of current usage on fan motor operation of all 4 RTUs

**Estimated Annual Savings:**


Gas Savings = - therms  
 Elect Savings = 32,645  
 Water Savings =  
 Sewer Savings =  
  
 Cost Savings (\$) = \$ -

**Utility Information:**

Electrical Cost (\$/kwh) = Water Cost (\$/kgal) =  
 Heating Cost (\$/therm) = Sewer Cost (\$/kgal) =

 <b>UNIVERSITY MECHANICAL CONTRACTORS, INC.</b> <i>We Build Value.</i>	<b>Project:</b> State Modular Building	<b>Job #:</b>
	<b>Subject:</b> ECM-3: Energy Based Re-Commissioning	<b>Date:</b> 10/30/2012
		<b>By:</b> SRL
		<b>Page:</b>

## Baseline Adjustment Calculation Associated with the Implementation of UCM 3.0 (Increased ventilation air during occupied periods)


<b>Baseline Adjustmnet</b>											
<b>Overview:</b>											
Baseline Adjustment calculations applied to allow for required ventilation air during occupied hours											
<b>Notes:</b>											
Modify OA/RA damper operation & RA fan speed to provide minimum OA during occupied operation											
Savings Calculations											
		<b>Annual</b>	<b>Existing Annual Heating</b>	<b>Proposed Annual Heating</b>	<b>Estimated Baseline Adjustment</b>		<b>Annual</b>	<b>Existing Annual Cooling</b>	<b>Proposed Annual Cooling</b>	<b>Estimated Baseline Adjustment</b>	
	<b>OAT</b>	<b>Hours</b>	<b>(therms)</b>	<b>(therms)</b>	<b>(therms)</b>		<b>OAT</b>	<b>Hours</b>	<b>kWh</b>	<b>kWh</b>	
	57.5	650	-	359	359		97.5	1	-	8,848	
	52.5	662	-	492	492		92.5	4	-	7,236	
	47.5	686	-	641	641		87.5	20	-	5,676	
	42.5	516	-	580	580		82.5	64	-	2,891	
	37.5	266	-	350	350		77.5	128	-	781	
	32.5	74	-	111	111		72.5	250	-	20	
	27.5	23	-	38	38		67.5	412	-	(54)	
	22.5	11	-	20	20		62.5	607	-	(53)	
	17.5	5	-	9	9						
	12.5	2	-	3	3						
	<b>Subtotal</b>	<b>2,893</b>	<b>-</b>	<b>2,603</b>	<b>2,603</b>		<b>Subtotal</b>	<b>1,484</b>	<b>-</b>	<b>25,344</b>	
<b>Assumptions:</b>											
HVAC system currently operates 24/7.											
Unoccupied setback is not currently occupied in any location within the facility											
Total Avg Annual RTU cfm (total of all 4 RTUs) =						56,466	cfm	Design cfm (total all 4 RTUs) =		86,870	
% Avg RTU cfm supplied to HD =						25%		Average VFD Speed =		65%	
RTU control dampers currently modulate to				0%	OA at ~ 10:00am each morning		Minimum Design OA (all 4 RTUs) =		10,700		
RTU control dampers currently modulate to				80%	OA at ~ 10:00pm each night						
Average Space Temperature (heating) =						72	F				
Heating System Efficiency =						80%					
Estimated chiller efficiency =						0.70	kW/ton				
Average Space Temperature (cooling) =						72	F				
% Avg RTU cfm supplied to CD =						75%					
Proposed Operation:											
RTU control dampers proposed to modulate to				5%	OA during unoccupied periods (night)						
RTU control dampers proposed to modulate to				20%	OA during occupied periods (7:00am to 10:00pm)						
<b>Estimated Baseline Adjustment:</b>											
<b>Gas Adjustment =</b>			<b>2,603 therms</b>								
<b>Elect Adjustment =</b>			<b>25,344</b>								
<b>Utility Information:</b>											
Electrical Cost (\$/kwh) =						Water Cost (\$/kgal) =					
Heating Cost (\$/therm) =						Sewer Cost (\$/kgal) =					
											
<b>Project:</b> State Modular Building						<b>Job #:</b>					
<b>Subject:</b> Baseline Adjustment associated with UCM-3						<b>Date:</b> 10/30/2012					
						<b>By:</b> SRL					
						<b>Page:</b>					











Sanitary Waste Piping Map, Exterior Site Plan  
 Appendix-1-03



Project: 16-150

Location: \_\_\_\_\_

Completed by: JSG

Date: \_\_\_\_\_

<b>Note</b>
C - complies
NC - non-compliant
N/A - not applicable
U - unknown

**16.1.2LS LIFE SAFETY BASIC CONFIGURATION CHECKLIST**

**Low Seismicity**

**Building System**

*General*

- C NC N/A U **LOAD PATH:** The structure shall contain a complete, well defined load path, including structural elements and connections, that serves to transfer the inertial forces associated with the mass of all elements of the building to the foundation. (Commentary: Sec. A.2.1.1. Tier 2: Sec. 5.4.1.1)
- C NC N/A U **ADJACENT BUILDINGS:** The clear distance between the building being evaluated and any adjacent building is greater than 4% of the height of the shorter building. This statement shall not apply for the following building types: W1, W1a, and W2. (Commentary: Sec. A.2.1.2. Tier 2: Sec. 5.4.1.2)
- C NC N/A U **MEZZANINES:** Interior mezzanine levels are braced independently from the main structure or are anchored to the seismic-force-resisting elements of the main structure. (Commentary: Sec. A.2.1.3. Tier 2: Sec. 5.4.1.3)

*Building Configuration*

- C NC N/A U **WEAK STORY:** The sum of the shear strengths of the seismic-force-resisting system in any story in each direction is not less than 80% of the strength in the adjacent story above. (Commentary: Sec. A.2.2.2. Tier 2: Sec. 5.4.2.1)
- C NC N/A U **SOFT STORY:** The stiffness of the seismic-force-resisting system in any story is not less than 70% of the seismic-force-resisting system stiffness in an adjacent story above or less than 80% of the average seismic-force-resisting system stiffness of the three stories above. (Commentary: Sec. A.2.2.3. Tier 2: Sec. 5.4.2.2)
- C NC N/A U **VERTICAL IRREGULARITIES:** All vertical elements in the seismic-force-resisting system are continuous to the foundation. (Commentary: Sec. A.2.2.4. Tier 2: Sec. 5.4.2.3)
- C NC N/A U **GEOMETRY:** There are no changes in the net horizontal dimension of the seismic-force-resisting system of more than 30% in a story relative to adjacent stories, excluding one-story penthouses and mezzanines. (Commentary: Sec. A.2.2.5. Tier 2: Sec. 5.4.2.4)
- C NC N/A U **MASS:** There is no change in effective mass more than 50% from one story to the next. Light roofs, penthouses, and mezzanines need not be considered. (Commentary: Sec. A.2.2.6. Tier 2: Sec. 5.4.2.5)
- C NC N/A U **TORSION:** The estimated distance between the story center of mass and the story center of rigidity is less than 20% of the building width in either plan dimension. (Commentary: Sec. A.2.2.7. Tier 2: Sec. 5.4.2.6)

**Moderate Seismicity: Complete the Following Items in Addition to the Items for Low Seismicity.**

**Geologic Site Hazards**

- C NC N/A U **LIQUEFACTION:** Liquefaction-susceptible, saturated, loose granular soils that could jeopardize the building's seismic performance shall not exist in the foundation soils at depths within 50 ft under the building. (Commentary: Sec. A.6.1.1. Tier 2: 5.4.3.1)
- C NC N/A U **SLOPE FAILURE:** The building site is sufficiently remote from potential earthquake-induced slope failures or rockfalls to be unaffected by such failures or is capable of accommodating any predicted movements without failure. (Commentary: Sec. A.6.1.2. Tier 2: 5.4.3.1)
- C NC N/A U **SURFACE FAULT RUPTURE:** Surface fault rupture and surface displacement at the building site are not anticipated. (Commentary: Sec. A.6.1.3. Tier 2: 5.4.3.1)

**High Seismicity: Complete the Following Items in Addition to the Items for Low and Moderate Seismicity.**

**Foundation Configuration**

- C NC N/A U **OVERTURNING:** The ratio of the least horizontal dimension of the seismic-force-resisting system at the foundation level to the building height (base/height) is greater than  $0.6S_u$ . (Commentary: Sec. A.6.2.1. Tier 2: Sec. 5.4.3.3)
- C NC N/A U **TIES BETWEEN FOUNDATION ELEMENTS:** The foundation has ties adequate to resist seismic forces where footings, piles, and piers are not restrained by beams, slabs, or soils classified as Site Class A, B, or C. (Commentary: Sec. A.6.2.2. Tier 2: Sec. 5.4.3.4)

Project: 16-150

Location: \_\_\_\_\_

Completed by: JSG

Date: \_\_\_\_\_

## 16.5LS LIFE SAFETY STRUCTURAL CHECKLIST FOR BUILDING TYPES S2: STEEL BRACED FRAMES WITH STIFF DIAPHRAGMS AND S2A: STEEL BRACED FRAMES WITH FLEXIBLE DIAPHRAGMS

### Low Seismicity

#### Seismic-Force-Resisting System

- NC N/A U COLUMN AXIAL STRESS CHECK: The axial stress caused by gravity loads in columns subjected to overturning forces is less than  $0.10F_y$ . Alternatively, the axial stress caused by overturning forces alone, calculated using the Quick Check procedure of Section 4.5.3.6, is less than  $0.30F_y$ . (Commentary: Sec. A.3.1.3.2. Tier 2: Sec. 5.5.2.1.3)
- NC N/A U BRACE AXIAL STRESS CHECK: The axial stress in the diagonals, calculated using the Quick Check procedure of Section 4.5.3.4, is less than  $0.50F_y$ . (Commentary: Sec. A.3.3.1.2. Tier 2: Sec. 5.5.4.1)

#### Connections

- NC N/A U TRANSFER TO STEEL FRAMES: Diaphragms are connected for transfer of seismic forces to the steel frames. (Commentary: Sec. A.5.2.2. Tier 2: Sec. 5.7.2)
- NC N/A U STEEL COLUMNS: The columns in seismic-force-resisting frames are anchored to the building foundation. (Commentary: Sec. A.5.3.1. Tier 2: Sec. 5.7.3.1)

**Moderate Seismicity: Complete the Following Items in Addition to the Items for Low Seismicity.**

#### Seismic-Force-Resisting System

- NC N/A U REDUNDANCY: The number of lines of braced frames in each principal direction is greater than or equal to 2. The number of braced bays in each line is greater than 2. (Commentary: Sec. A.3.3.1.1. Tier 2: Sec. 5.5.1.1)
- NC N/A U CONNECTION STRENGTH: All the brace connections develop the buckling capacity of the diagonals. (Commentary: Sec. A.3.3.1.5. Tier 2: Sec. 5.5.4.4)
- NC N/A U COMPACT MEMBERS: All brace elements meet compact section requirements set forth by AISC 360, Table B4.1. (Commentary: Sec. A.3.3.1.7. Tier 2: Sec. 5.5.4)
- NC N/A U K-BRACING: The bracing system does not include K-braced bays. (Commentary: Sec. A.3.3.2.1. Tier 2: Sec. 5.5.4.6)

**High Seismicity: Complete the Following Items in Addition to the Items for Low and Moderate Seismicity.**

#### Seismic-Force-Resisting System

- NC N/A U COLUMN SPLICES: All column splice details located in braced frames develop 50% of the tensile strength of the column. (Commentary: Sec. A.3.3.1.3. Tier 2: Sec. 5.5.4.2)
- NC N/A U SLENDERNESS OF DIAGONALS: All diagonal elements required to carry compression have  $K/l_r$  ratios less than 200. (Commentary: Sec. A.3.3.1.4. Tier 2: Sec. 5.5.4.3)
- NC N/A U CONNECTION STRENGTH: All the brace connections develop the yield capacity of the diagonals. (Commentary: Sec. A.3.3.1.5. Tier 2: Sec. 5.5.4.4)
- NC N/A U COMPACT MEMBERS: All brace elements meet section requirements set forth by AISC 341, Table D1.1, for moderately ductile members. (Commentary: Sec. A.3.3.1.7. Tier 2: Sec. 5.5.4)
- NC N/A U CHEVRON BRACING: Beams in chevron, or V-braced, bays are capable of resisting the vertical load resulting from the simultaneous yielding and buckling of the brace pairs. (Commentary: Sec. A.3.3.2.3. Tier 2: Sec. 5.5.4.6)
- NC N/A U CONCENTRICALLY BRACED FRAME JOINTS: All the diagonal braces shall frame into the beam-column joints concentrically. (Commentary: Sec. A.3.3.2.4. Tier 2: Sec. 5.5.4.8)

#### Diaphragms (Stiff or Flexible)

- NC N/A U OPENINGS AT FRAMES: Diaphragm openings immediately adjacent to the braced frames extend less than 25% of the frame length. (Commentary: Sec. A.4.1.5. Tier 2: Sec. 5.6.1.3)

### Flexible Diaphragms

- C NC N/A U CROSS TIES: There are continuous cross ties between diaphragm chords. (Commentary: Sec. A.4.1.2. Tier 2: Sec. 5.6.1.2)
- C NC N/A U STRAIGHT SHEATHING: All straight sheathed diaphragms have aspect ratios less than 2-to-1 in the direction being considered. (Commentary: Sec. A.4.2.1. Tier 2: Sec. 5.6.2)
- C NC N/A U SPANS: All wood diaphragms with spans greater than 24 ft consist of wood structural panels or diagonal sheathing. (Commentary: Sec. A.4.2.2. Tier 2: Sec. 5.6.2)
- C NC N/A U DIAGONALLY SHEATHED AND UNBLOCKED DIAPHRAGMS: All diagonally sheathed or unblocked wood structural panel diaphragms have horizontal spans less than 40 ft and aspect ratios less than or equal to 4-to-1. (Commentary: Sec. A.4.2.3. Tier 2: Sec. 5.6.2)
- C NC N/A U OTHER DIAPHRAGMS: The diaphragm does not consist of a system other than wood, metal deck, concrete, or horizontal bracing. (Commentary: Sec. A.4.7.1. Tier 2: Sec. 5.6.5)





## TIER 1 QUICK CHECKS

### COLUMN AXIAL STRESS CHECK (WORST-CASE)

ROOF LOADS:

$$DL_R = 20 \text{ psf}$$

$$LL_R = 25 \text{ psf}$$

MEZZANINE LOADS:

$$PL_M = 20 \text{ psf} + 3''/12'' \times (150 \text{ psf}) = 57.5 \text{ psf}$$

$$LL_M = 125 \text{ psf (POSTED)}$$

$$\text{TYP. T.A.} = 200 \text{ ft}^2$$

$$P_{\text{max}} (\text{SOUTH}) = (\Sigma DL + \Sigma LL) \text{ T.A.} = 45.5 \text{ KIPS}$$

$$P_{\text{max}} (\text{NORTH}) = (DL_R + LL_R) \text{ T.A.} = 9.0 \text{ KIPS}$$

$$\text{SOUTH COLUMN} \Rightarrow W10 \times 33, A = 9.71 \text{ in}^2$$

$$\text{NORTH COLUMN} \Rightarrow W6 \times 15, A = 4.43 \text{ in}^2$$

$$\underline{P/A (\text{SOUTH})} = 4.69 \text{ ksi} < 0.1 F_y = 5 \text{ ksi}, \text{ OK}$$

$$\underline{P/A (\text{NORTH})} = 2.03 \text{ ksi} < 0.1 F_y = 5 \text{ ksi}, \text{ OK}$$

TIER 1 QUICK CHECKS (CONT.)

BRACE AXIAL STRESS CHECK

$$f_j^{AVE} = \frac{1}{M_s} \left( \frac{V_j}{S N_{br}} \right) \left( \frac{L_{br}}{A_{br}} \right)$$

$L_{br}$ : AVG LENGTH OF BRACE = VARIES

$N_{br}$  = 2 BRACES / FRAME

$S$  = 20ft

$A_{br}$ : SEE TABLE TO RIGHT

$V_j$  = SEE BELOW

$M_s$  = SEE TABLE TO RIGHT

TABLE 4-10

$d/t$	$M_s$
14.79	6.0
31.24	3.0

LOCATION	$d/t^*$	$M_s$	$A_{br}$
SOUTH, TOP TS 8x4x1/4	22	4.69	4.30 in <sup>2</sup>
SOUTH, BOT TS 8x4x3/8	14.33	5.17	7.58 in <sup>2</sup>
NORTH 6x3x3/8	14	6.0	5.48 in <sup>2</sup>

STORY SHEAR FORCES ( $V_j$ )

\* CALCULATED PER AISC 360 TABLE B4.1

NORTH BUILDING:

$$V_j = C S_a W$$

$W$  = WALL WEIGHT + ROOF WEIGHT

$$\text{WALL WEIGHT} = 10 \text{ psf} \times 100 \text{ ft} \times \frac{1}{2} \left( \frac{15.58 + 13.5}{2} \right) = 7.27 \text{ KIPS}$$

$$\text{ROOF WEIGHT} = 20 \text{ psf} \times 100 \text{ ft}^2 = 200 \text{ KIPS}$$

$$W = 207 \text{ KIPS / BRACE}$$

$$S_a = S_{xs} = 0.674 \text{ g (SH.5)}$$

$$C = 1.4 \text{ (TABLE 4-8)}$$

$$V_j = 196 \text{ KIPS}$$




TIER 1 QUICK CHECKS (CONT.)

$L_{br} = 17.65 \text{ ft}$

$f_j^{AVG} = \frac{1}{6} \left( \frac{196}{20 \times 2} \right) \left( \frac{17.65}{5.48} \right)$

$f_j^{AVG} = 2.62 \text{ KSI} < 0.5 F_y = 18.5 \text{ KSI, OK}$



SOUTH BUILDING:

$F_x = \frac{W \times h^k}{\sum W_i h_i^k} V$ ;  $K = 1.0 \text{ (T < 15)}$

ROOF WEIGHT,  $W_r = 20 \text{ psf} \times 120 \text{ ft} \times 120 \text{ ft} = 288 \text{ KIPS}$

2<sup>ND</sup> STORY WALL WEIGHT,  $W_{w2} = 10 \text{ psf} \times 120 \text{ ft} \times \frac{1}{2} \left( \frac{30 + 27.5}{2} - 17.79 \right)$

$W_{w2} = 6.58 \text{ KIPS}$

MEZZANINE T.A. =  $40 \text{ ft} \times 120 \text{ ft} = 4,800 \text{ ft}^2$

MEZZANINE WEIGHT,  $W_m = (4,800 \text{ ft}^2) (57.5 \text{ psf} + 0.25 \times 125 \text{ psf}) = 426 \text{ KIPS}$

1<sup>ST</sup> STORY WALL WEIGHT,  $W_{w1} = 10 \text{ psf} \times 120 \text{ ft} \times \frac{1}{2} \left[ 17.79 + \left( \frac{30 + 27.5}{2} - 17.79 \right) \right]$

$W_{w1} = 17.25 \text{ KIPS}$

STORY	$W_i$ (KIPS)	$h_i$ (ft)	$W_i h_i$	$\frac{W_i h_i}{\sum W_i h_i}$	$F_x$ (KIPS)
2 <sup>ND</sup> (ROOF)	295	28.75	8,481	0.518	314
1 <sup>ST</sup>	443	17.79	7,881	0.482	292
GROUND	10.7	0	0	-	-
$\Sigma$	749		16,362	1	606

$V = C_s W$ ,  $C = 1.2$

$V = (1.2)(0.674)(749) = 606 \text{ KIPS/BRACE}$


TIER 1 QUICK CHECK (CONT.)

$$V_2 = 314 \text{ KIPS/BRACE}$$

$$L_{br2} = 14.84 \text{ FE}$$

$$f_2 = \frac{1}{4.69} \left( \frac{314}{20 \times 2} \right) \left( \frac{14.84}{4.3} \right)$$

$$\underline{f_2 = 5.78 \text{ KSI} < 0.5F_y = 18.5 \text{ KSI, OK.}}$$




$$V_1 = 606 \text{ KIPS/BRACE}$$

$$L_{br1} = 20.41 \text{ FE}$$

$$f_1 = \frac{1}{5.17} \left( \frac{606}{20 \times 2} \right) \left( \frac{20.41}{7.58} \right)$$

$$\underline{f_1 = 7.89 \text{ KSI} < 0.5F_y = 18.5 \text{ KSI, OK.}}$$




# USGS Design Maps Summary Report

## User-Specified Input

**Building Code Reference Document** ASCE 41-13 Retrofit Standard, BSE-1E  
(which utilizes USGS hazard data available in 2008)

**Site Coordinates** 46.97832°N, 122.9131°W


**Site Soil Classification** Site Class D – “Stiff Soil”




## USGS-Provided Output

$S_{S,20/50}$	0.475 g	$S_{XS,BSE-1E}$	0.674 g
$S_{1,20/50}$	0.178 g	$S_{X1,BSE-1E}$	0.372 g

**Horizontal Spectrum**



**Vertical Spectrum**



Although this information is a product of the U.S. Geological Survey, we provide no warranty, expressed or implied, as to the accuracy of the data contained therein. This tool is not a substitute for technical subject-matter knowledge.



## CONNECTION STRENGTH

### TENSION LOADS

<u>BRACE</u>	<u>L<sub>BR</sub> (ft)</u>	<u>A<sub>BR</sub> (in<sup>2</sup>)</u>	<u>F<sub>y</sub>A<sub>BR</sub> (KIPS)</u>
TS 6x3x3/8	17.65	5.48	203
TS 6x4x1/4	14.84	4.30	159
TS 8x4x3/8	20.41	7.58	280

### BRACE BUCKLING LOADS

TS 6x3x3/8:

$$P_n = 42 \text{ KIPS (INTERPOLATED, TABLE 4-3, AISC 360)}$$

TS 6x4x1/4:

$$P_n = 82 \text{ KIPS (INTERPOLATED, TABLE 4-3, AISC 360)}$$

TS 8x4x3/8:

$$P_n = 82 \text{ KIPS (INTERPOLATED, TABLE 4-3, AISC 360)}$$

### CONNECTION CAPACITIES (BRACE YIELDING)

TS 8x4x3/8:

(6) 3/4"  $\phi$  BOLTS (A325) PER AS-BOLTS

$$\underline{V_{\text{BOLTS}} = (6) 17.9 / \phi = 143 \text{ KIPS} < F_y A_{BR}, \text{ N.G.}}$$

TS 6x4x1/4:

(4) 3/4"  $\phi$  BOLTS (A325)

$$T = 159 (10.96 / 14.84) = 117.4 \text{ KIPS}$$

$$V = 159 (10 / 14.84) = 107.1 \text{ KIPS} : F_{rv} = \frac{V}{1450.442} = 60.6 \text{ KSI/BOLT}$$

(BEFORE BRACE YIELDS)

BY OBSERVATION, BOLTS FAIL IN SHEAR, N.G.

$$\underline{V_{\text{BOLTS}} = 95 \text{ KIPS}}$$


CONNECTION STRENGTH (CONT.)

TS 6x3x3/8:

(3) (3/4")  $\phi$  BOLTS (A325)

$V_{\text{BOLTS}} = (3)(17.9) / \phi = 72 \text{ KIPS} < F_y A_{325} = 203 \text{ KIPS, N.C.}$

## VERTICAL IRREGULARITIES



MEMBER SIZES PER AS BUILTS


- 1) CHECK LOAD REQUIRED FOR BRACE BUCKLING
- 2) ALL CONNECTIONS PINNED
- 3) CHECK UTILIZATION OF SUPPORTING MEMBERS WHEN BRACE UTILIZATION IS @ 100%

FROM SH. 11:

CENTER BEAM FAILS BEFORE BRACES  
CAN BUCKLE;  $\therefore$  CORRECTIVE ACTION  
NEEDED

Sections	
<span style="color: green;">■</span>	W10x49
<span style="color: blue;">■</span>	W10x33
<span style="color: red;">■</span>	W12x26
<span style="color: purple;">■</span>	W14x26
<span style="color: cyan;">■</span>	TS6x4x1/4
<span style="color: yellow;">■</span>	TS8x4x3/8


Patch Material	
<span style="border: 1px solid black; display: inline-block; width: 10px; height: 10px;"></span>	(No Material)





Sections	
<span style="color: green;">■</span>	W10x49
<span style="color: blue;">■</span>	W10x33
<span style="color: red;">■</span>	W12x26
<span style="color: purple;">■</span>	W14x26
<span style="color: cyan;">■</span>	TS6x4x1/4
<span style="color: olive;">■</span>	TS8x4x3/8

Default Color	
<span style="color: blue;">■</span>	All loads



SH - 10



SI-11

Plot View - Overall Efficiency